

AD-A189 838

BUNNE POINT SHORELINE EROSION DEMONSTRATION PROJECT
VOLUME 2 APPENDICES E(U) ARMY ENGINEER DISTRICT LOS
ANGELES CA AUG 87


1/3

UNCLASSIFIED

F/G 13/2

NL






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

(2)

DTIC FILE COPY


AD-A189 838

**BUHNE POINT SHORELINE EROSION
DEMONSTRATION PROJECT**



FINAL

**APPENDICES VOL. II
E**



**SAN FRANCISCO AND LOS ANGELES DISTRICTS
CORPS OF ENGINEERS**

**LOCAL SPONSOR
HUMBOLDT BAY HARBOR, RECREATION AND CONSERVATION DISTRICT**

AUGUST 1987

88 1 19 044

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) BUHNE POINT SHORELINE EROSION DEMONSTRATION PROJECT Vol. II		5. TYPE OF REPORT & PERIOD COVERED Final, 1983-1987
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Corps of Engineers, Los Angeles District P.O. Box 2711 Los Angeles, CA 90053-2325		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Corps of Engineers, San Francisco District 211 Main Street San Francisco, CA 94105-1905		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Federal Highway Administration P.O. Box 1915 Sacramento, CA 95809		12. REPORT DATE August 1987
		13. NUMBER OF PAGES 1,100
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Beach restoration Shoreline erosion control Dune restoration Native plants		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides detailed information on the rebuilding of the Buhne Point marine beach, the construction of retaining structures, and the establishment of native dune vegetation to prevent wind erosion. The various appendices which are part of the report thoroughly document physical and numerical model studies done at the Waterways Experimentation Station (WES) in Vicksburg Mississippi for the structures and beach, as well as the post-construction and post-planting monitoring programs. (continued)		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. Abstract, continued.

Buhne Point is located about 250 air miles north of San Francisco, on the east shore of Humboldt Bay, Humboldt County, California. A natural sand spit was located on the western face of the point, but the area lies directly in line with wind and waves entering Humboldt Bay from the Pacific Ocean. Reports of erosion there have been recorded since the mid-19th century. By the late 1970s, erosion had become so severe that the beach had disappeared, and the shoreline had eroded back to the roadway, threatening the road and underground water, gas and sanitary sewer lines. Storm waves 10' in height are common, and were sending rock flying across the road and against adjacent homes of the community of King Salmon. This appendix includes a map of the area.

In 1982, Congress included the area in an authorization to the Federal Highway Administration to undertake a demonstration project to apply "state-of-the-art methods for repairing damage to highways and preventing damage to highways resulting from shoreline erosion." A four-year, four-phase program was implemented, and is described in this final report.

The First Phase consisted of designing and constructing a 1,250' timber groin and a 200' long rubble-mound head to prevent sand from being transported south, downcoast.

Phase II consisted of placing 600,000 yds³ of fine-to-medium grain sand to reform the almost-24-acre beach.

In Phase III, a 1,050' shore-connected, rubble-mound breakwater was constructed on the northerly face of the beach. The Phase I timber groin and breakwater was given an additional 425' arched extension.

Phase IV consisted of vegetating the sandfill with native plants. The vegetation program included experimental collecting and growing of 20 different native and naturalized species for a two-year period, and then extensive plantings and monitoring.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

APPENDIX E

- (45132)
- SECTION 1 BUHNE SPIT/KING SALMON SHORE
PROTECTION PROJECT (PHASE I)
- SECTION 2 PHASE II BASIS FOR DESIGN
- SECTION 3 PHASE II FOUNDATION REPORT



Accession For	
NTIS CRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution /	
Availability Codes	
Dist	Avail and/or Special
A-1	

SECTION 1

BUHNE SPIT/KING SALMON SHORE PROTECTION PROJECT (PHASE I)

BOATING FACILITIES DIVISION

DESIGN STUDY

for

**BUHNE SPIT/KING SALMON
SHORE PROTECTION PROJECT**

at

HUMBOLDT BAY

in the

COUNTY of HUMBOLDT

May 1983

STATE of CALIFORNIA

RESOURCES AGENCY

DEPARTMENT of BOATING and WATERWAYS

PREFACE

The Buhne Spit/King Salmon area, located within Humboldt Bay easterly of the entrance channel jetties of the bay, has had a serious erosion problem for the last decade. The Department of Boating and Waterways, Beach Erosion Branch, was asked by Humboldt Bay Harbor, Recreation and Conservation District to design a project to mitigate shoreline erosion and reduce the shoaling of Fishermans Channel.

We have reviewed all prior reports written by the U. S. Army Corps of Engineers, historical literature, maps, and other data collected in the vicinity of Buhne Spit. We have compiled a data and information base that would give us insight into the environmental and climatological factors that have a direct affect on the shoreline erosion within the area of study.

Presented in this design study is a compilation of the data and information applicable to the Buhne Spit erosion area which aided our staff in the development of numerous conceptual designs. These alternative designs were evaluated by a numerical process to pick what we feel is the best, most efficient and least costly project to provide shoreline protection to the Buhne Spit area for several decades.

Excellent assistance and technical information was obtained from the Humboldt County Department of Natural Resources and the U. S. Army Corps of Engineers. Without their help, it would have been necessary to collect additional engineering and environmental data which would have resulted in additional design time and increased time to the project. We have also received keen cooperation from the U. S. Army Corps of Engineers who have agreed to place their channel maintenance dredge spoils within our project area to rebuild the spit to its 1955 area.

TABLE OF CONTENTS

	Page
PREFACE	ii
TABLE OF CONTENTS	iii
ABSTRACT	1
PURPOSE AND APPROACH	3
DESIGN STUDY SCOPE	3
DESCRIPTION OF AREA	3
STATEMENT OF PROBLEM	5
PROPOSED PROJECT	7
BENEFITS	8
CLIMATOLOGICAL FACTORS	9
Storms	9
Tidal Data	9
Winds	10
Waves	10
Waves Within Bay	12
Offshore Waves	12
Wave Statistics	15
ENVIRONMENTAL FACTORS WITHIN BUHNE SPIT AREA	19
GEOMORPHOLOGY	19
WINDBORNE TRANSPORT OF BEACH MATERIAL	20
CHARACTERISTICS OF LITTORAL MATERIAL	20
SUBSURFACE MATERIALS	20
SOURCES OF LITTORAL MATERIAL	20
Littoral Transport	21
Buhne Spit Nourishment	21
EROSION OF BUHNE SPIT	22
TRIBUTARY DRAINAGE	22
MAPS	27
SHORE OWNERSHIP	27
ENGINEERING DESIGN CRITERIA	29
Offshore Breakwater Structure	29
Rubble-Mound Seawall	30
Rubble-Mound Groins	31
H-Pile Groin With Wood Lagging	31
ALTERNATIVE COMPARISONS	33
Preliminary Screening	33
Final Selection	35
CONCLUSIONS AND RECOMMENDATIONS	37
Summary of Findings	37
Recommendations	37
REFERENCES	38
APPENDIX	
A Cost Estimates	
B Wave Data Statistics	
C Wind Data Statistics	
D Plates From Previous U.S. Corps Reports	
E Conceptual Plans of Alternate Designs	
F Correspondence and Documents	

TABLE OF CONTENTS CONT'D

FIGURES:

	Page
1 Vicinity Map	2
2 Project Location Map	4
3 Project Layout, Plan A.....	6
4 Typical Wave Pattern, Buhne Spit	10

PLATES:

	Page
I Local Wind, Fetch and Wind Diagram	13
II Erosion Buhne Spit 1939-1980	23
III Historical Spit Shoreline 1926-1955	25

TABLES:

	Page
1 Monthly Average and Maximum Winds	11
2 California Coastal Data Program, Waves..	16
Deepwater Wave Statistics, Waves	16
3 Deepwater Wave Statistics Comparison ...	17
4 Erosion at Buhne Point Area	22
5 Summary of Cost Estimates	34
6 Design Selection Table	35

GENERAL REMARKS
 Under the direction of the Hydrographic Survey, the following information was obtained from the local authorities and the crew of the vessel, the U.S.S. Albatross, during the survey of Humboldt Bay, California, in 1874.

Scale
 One inch = one mile
 One mile = 1.609 kilometers
 One kilometer = 0.621 miles

Notes
 The following information was obtained from the local authorities and the crew of the vessel, the U.S.S. Albatross, during the survey of Humboldt Bay, California, in 1874.

Remarks
 The following information was obtained from the local authorities and the crew of the vessel, the U.S.S. Albatross, during the survey of Humboldt Bay, California, in 1874.


Sheet 2 of 8
U.S. COAST SURVEY
AD. BARNES, SUPERINTENDENT
PRELIMINARY SURVEY OF
HUMBOLDT BAY
CALIFORNIA

By the Hydrographic Party under command of
Lieut. James Milton U.S.N. and Assist. CAS.

Scale 1:62,500
 1874



View of Coast Range from Humboldt Bay, 1874 (Photograph by U.S.S. Albatross)



Sketch of
HUMBOLDT
BAY
Scale 1:62,500



U.S. COAST SURVEY

ABSTRACT

The Department of Boating and Waterways along with the U. S. Army Corps of Engineers have been studying the shoreline problems along Buhne Spit in Humboldt Bay since the early 1960's. The results of our combined studies indicate that there is a severe erosion problem on the spit with continuing shoreline retreat. Without the construction of some type of groin system or other shore protection configuration continued erosion is inevitable. Erosion has already progressed to a point where Buhne Point Drive and extensive underground public utilities are in immediate danger. A permanent shore protection project must be constructed soon if these facilities are to be preserved.

This design study investigates several combinations of shore protection configurations that can be utilized to prevent continuing erosion of Buhne Spit and recreate the spit to its area in 1955.

A 1000-1400 foot groin constructed of H-Beam Pile with timber lagging between the piles, a rock reveted bayward end and a 400 foot rock rubble-mound offshore breakwater with a sand filled pocket is the least expensive and most cost effective solution to the problem. This project, exclusive of sand fill, will cost about \$640,000. The project including sand fill to form the protective beach is estimated to cost about \$1,700,000.

The proposed project with groin and offshore breakwater is considered to be Phase I of the project. Phase II of the project, the filling of the groin pocket with sand would be accomplished during the periodic maintenance dredging of Humboldt Bay's navigation channels by the U. S. Army Corps of Engineers. Subsequent lengthening of the groin after monitoring the project through several winter storms would be Phase III. Construction funding for the project would be by a combination of State-Local or State-Local-Federal funds.




Figure 1

BUHNE SPIT/KING SALMON SHORE PROTECTION PROJECT

PURPOSE AND APPROACH

The purpose of the Buhne Point/King Salmon Design Study was to devise a method for long-term control of erosion problems which have eliminated Buhne Spit and which now threaten Buhne Point Drive and the residences shoreward of the road in the King Salmon area located on Humboldt Bay in Humboldt County.

As an initial phase of this design study, an analysis of the alternative erosion control methods was conducted. The approach to alternative design analysis included the following steps:


- a. Define the erosional problem on Buhne Spit by review and analysis of existing data and past reports.
- b. Develop specific goals and constraints as a basis for analyzing and comparing alternative designs for erosion protection.
- c. Determine the functional effectiveness, advantages, disadvantages and estimated cost for each alternative.
- d. Compare the alternatives against the specific project needs and select the best method for long-term erosion control.

DESIGN STUDY SCOPE

A total of twelve alternative beach erosion control plans were analyzed to determine their effectiveness and acceptability in reducing erosion in the Buhne Spit/King Salmon area. Preliminary screening was used to eliminate less practical and costly plans. Four of the alternatives met the functional, economic and environmental criteria when compared against specific project design goals and constraints. This final selection analysis determined the alternative recommended for detailed engineering, final design and future construction.

DESCRIPTION OF AREA

Buhne Point is located about 3 miles south of the City of Eureka and is opposite the jettied entrance to Humboldt Bay. King Salmon Harbor (Fisherman's Channel) was developed shoreward of Buhne Spit on what was previously a dredge spoil area. The area is now a small fishing village, camping/recreation site and a home for retired persons. The highest point on Buhne Spit Shoal is about 8-10 feet above the mean lower low water datum (MLLD).



LOCATION MAP

Figure 2

The spit has a length of about 2,000 feet measured from the juncture of the shoal and the Fields Landing Channel bayside to Buhne Point. The shoreline between Buhne Point and the Elk River Spit is protected by stone revetment. Buhne Point Drive, the bayside boundary between the shoal and King Salmon, is the main transportation link to the area. The road also carries all the underground utilities including the main sanitary sewer line. The road has been protected by emergency placement of rock along its entire length from Buhne Point to the Fields Landing Channel. The existing rock protection is inadequate and erosion and undermining of the roadway continues.

The entrance to PG&E's cooling water intake channel (Fisherman's Channel) is located southeasterly of King Salmon Harbor where it confluent with the Fields Landing Channel. The cooling water intake channel also serves as the harbor entrance to King Salmon and is the berthing area for the deeper draft boats moored within/along the channel. Shoaling caused by sand transport off Buhne Spit shoal has closed the channel entrance numerous times during the past few years blocking the channel for boat entrance/exit and safe mooring. This severe shoaling situation has also reduced the capacity of the cooling water intake channel supplying PG&E's steam power plant. Continuous dredging at the entrance and along the channel has been the short-term solution to provide adequate cooling water and access to King Salmon Harbor.

STATEMENT OF PROBLEM

During the past decade the Buhne Spit shoal has eroded away at an accelerated rate due to a redirection of the waves that enter Humboldt Bay through the entrance channel. Modifications on the bayside of the south channel jetty have generated an additional refracted wave train that commingles with the main waves that are transmitted through the entrance channel. Local observers believe that this modification has shifted the focus of the waves southwesterly toward Buhne Point from its previous location northeast of PG&E's steam power plant and along the Northwestern Pacific Railroad, thus accelerating sand transport along the shoal and into Fields Landing Channel as well as into PG&E's cooling water intake/Fisherman's Channel. The Department's assessment of the present sand transport system at Buhne Spit shoal is that the previous unrefracted wave pattern within the bay carried sediment along the spit which formed a point bar shoal along the navigation channel. The sediment eventually was deposited within the channel. The modification of the south jetty within the bay generated an additional wave pattern that passes through the main wave with a slight change in direction, rounds off the shoal and transports sand directly into the navigation channel, then down the edge of the channel into Fisherman's Channel creating a shoal.

During the period from 1977 to date, the shoal has eroded away southwesterly along Buhne Point Drive in the King Salmon area. The shoal has lowered 5-10 feet along the road and is secured to the bay mud foundation material along its entire length. There is a very small shoal between Halibut Avenue and the ship channel that is above mean lower low water. To protect Buhne Point Drive and the underlying utilities (consisting of water lines, natural gas lines and the main sanitary sewer line) from destruction, Humboldt County has reveted the bayside of the road with large rock. The emergency rock revetment has protected the roadway during recent storms but was not designed as a permanent structure to withstand large breaking waves. Consequently, during all subsequent severe storms, the revetment has been overtopped by waves. Smaller rocks from the revetment have been carried onto the roadway and cascaded into nearby homes, breaking windows and causing minor structural damage. The revetment has settled and also unravelled at numerous locations. Buhne Point Road has been undermined by wave wash-through and has collapsed at numerous locations. The above conditions have created an extreme safety hazard during moderate large storm wave conditions. It is a matter of time until one of the large rocks on the revetment is dislodged and rolls/tumbles onto the roadway, blocking access to King Salmon for emergency vehicles and the public. The present condition can only grow worse as the remaining sand spit recedes horizontally and vertically allowing larger and larger waves to break further up onto the rock revetment.

PROPOSED PROJECT

The proposed project consists of a 1000 to 1400-foot groin constructed of H-Beam Piles with timber lagging between the piles with a rock reveted bayward end and a 400-foot rock rubble mound offshore breakwater as shown on Figure 3. The groin follows an alignment parallel to the Fields Landing Channel from the southwest end of Buhne Point Drive near the intersection of Halibut Avenue. The offshore rock rubble mound breakwater will be constructed parallel to the shore about 250 feet bayward of the intersection of Buhne Point Road and Herring Avenue, extending northeasterly to the Eureka Shipbuilders Incorporated/Pacific Gas and Electric Company common boundary line. The long groin will provide a downcoast impervious barrier to reduce sand transport into Fisherman's Channel/FG&E's cooling water intake channel and at the same time accumulate sand to rebuild the shoal. The offshore breakwater will provide a sheltered region shoreward of the structure that will reduce sand transport and build out a protective beach from Buhne Point Drive. Both structures will function as barriers to retain sand to build out a wide protective beach along the existing rock revetment which parallels Buhne Point Drive. The groin pockets formed by the two structures will be filled with sand and dredge spoils from the U. S. Army Corps of Engineers harbor maintenance dredging. With the use of these dredge spoils

and other imported sand Buhne Spit can be reconstructed to its area that existed in 1955.

This project is designed to restore Buhne Spit shoal to its 1955 area and provide an interim project for shore protection until the Corps of Engineers constructs the project proposed in House Document No. 282, 85th Congress, 2nd Session.

BENEFITS

The proposed groin and offshore breakwater project and anticipated dredge spoil sand from the U. S. Army Corps of Engineers maintenance dredging from the Fields Landing Channel will restore a protective/recreation beach on Buhne Spit. The project will protect the adjacent recreation area and residences along Buhne Point Drive from wave damage, and maintain accessibility to the public, emergency vehicles and county maintenance crews during severe high wave conditions. Additionally, the project will protect the road and underlying public utilities from wave damage due to the extreme erosion of the low spit upon which they are located.

CLIMATOLOGICAL FACTORS

STORMS

The Pacific Ocean area in the vicinity of Humboldt Bay is subject to storms accompanied by high waves during the winter months. Data are available regarding the duration, frequency, or intensity of storms from "Winds of California" and "Wind Storms in California". Wind data contained in these publications indicate that winds with velocities of 40 miles per hour or greater generally occur from the southwest and south. The greatest wind velocity of record is 56 miles per hour. Information furnished to USCE by local residents and by officials of the Northwestern Pacific Railroad Company indicates that, during storms occurring at the time of high tides, waves break on and overtop the revetment bordering the railroad right-of-way north of Buhne Point. Also, at such times, waves inundate and wash out sections of Buhne Point Drive, the only access road to the King Salmon area on Buhne Spit. Such storms are reported to occur about 10 times each year. Although these storms cause no serious structural damage, railroad officials state that railroad operations are suspended, on the average of about 4 hours during each storm, in order to clear the tracks of sand and rocks deposited by waves overtopping the existing structures. Thus, railroad operations are interrupted about 40 hours annually.

TIDAL DATA

Tidal data obtained at the north jetty of Humboldt Bay, which are considered to be representative of tidal conditions in the study area, are summarized below. The data, abstracted from National Ocean Surveys publications, Tidal Bench Mark, Part 1, Northern California, are based on 11 1/2 months of automatic tide-gaging records (October 1940 to March 1941 and June to December 1942) reduced to mean values. Unless otherwise noted, elevations in this report refer to the plane of mean lower low water (MLLW).

TIDAL DATA, NORTH JETTY, HUMBOLDT BAY

	Feet (MLLW)	Feet (NGVD)
Estimated Highest Water Level	9.50	6.16
Mean Higher High Water	6.70	3.36
Mean High Water	6.00	2.66
Mean Tide Level	3.60	0.26
Mean Sea Level (NGVD)	3.34	0.00
Mean Low Water	1.20	-2.14
Mean Lower Low Water	0.00	-3.34
Estimated Lowest Water Level	-3.00	-6.34

WINDS

Wind characteristics in the Lohme Point area were assumed to be similar to those for the city of Eureka for which wind records are available. Data obtained by the United States Weather Bureau station at Eureka covering the period July 1939 to December 1942 and at the Humboldt Bay Power Plant from January 1966 to December 1966 were used to prepare the wind diagram shown on Plate I. The available data indicate that during the greater part of the year the prevailing winds are from the north and northwest and have velocities ranging from 4 to 15 miles per hour. However, the climatological summary given on Table 1 indicates that the prevailing direction of the wind shifts seasonally.

TABLE 1

MONTHLY AVERAGE AND MAXIMUM WINDS

MONTH	MEAN WIND SPEED (MPH)	PREVAILING DIRECTION	MAXIMUM WIND SPEED (MPH)	DIRECTION
JAN	6.9	SE	54	S
FEB	7.2	SE	48	SW
MAR	7.6	N	48	SW
APR	8.0	N	49	N
MAY	7.9	N	40	NW
JUN	7.4	N	39	NW
JUL	6.8	N	35	N
AUG	5.8	NW	34	N
SEP	5.5	N	44	N
OCT	5.6	N	56	SW
NOV	6.0	SE	43	S
DEC	6.4	SE	56	S
ANNUAL	6.8	N	56	SW
LENGTH OF RECORD (YRS)	54	54	67	67



WAVES

No statistical data are available for wave conditions within Humboldt Bay. Insofar as wind waves within the bay are concerned, the critical direction of wave approach in the problem area is from the southwest, for which direction the fetch is maximum. Based on the maximum wind record from this direction (56 miles per hour) and the assumption that the duration of the wind was sufficient for maximum wind wave generation, it is estimated that the maximum wind waves generated would have had a significant height of about 3 feet and a period of 3 seconds. Based on the historical record, wind waves of this height are rare occurrences. However, the area under investigation is exposed to waves generated in the Pacific Ocean that enter the bay through the pettied entrance. The relative alignment of the entrance and the eastern shore of the bay


is such that all waves entering the bay impinge on the shore in the study area. Although the seaward end of the jettied entrance is exposed to high waves, the height of waves reaching the eastern shore is controlled by the available depth of water over the two shoal areas near the bayward end of the jetties and by the shallow water in the study area. At extreme high tide (9.5 feet above mean lower low water), the controlling depth over the shoals near the jetties is about 25 feet. Thus, only waves of about 18 feet or less in height can enter the bay without breaking on the shoal. Entering waves less than 18 feet would cross the bay and break at varying distances from the shoreline, depending upon their initial height. (For example, neglecting the effect of refraction and diffraction, a 15 foot wave would break at about the 10 foot depth contour during a 9.5 foot high tide.) After breaking, the wave would reform and continue on to shore. Local residents report that waves about 6 feet high break directly on shore in the problem area when high waves enter the bay at high tide. Wave analysis made by USCE in connection with their previous report also indicate that breakers 6 feet high can reach shore.

WAVES WITHIN BAY. USCE used available aerial photographs of waves entering the bay to show that the waves diffract and fan out so that the wave crests increase in length with increasing distance from the bayward end of the entrance channel. Measurements made from aerial photographs taken by USCE during the occurrences of high waves in the Pacific Ocean and at times when waves were breaking upon the shoal area near the jetties indicate that the wave length averaged about 80 feet at a point about 2,400 feet from the Buhne Point shore at a water depth of 10 feet. The effective period of these waves would be about 5-seconds. Aerial photographs also show that waves impinge on Buhne Point in a manner likely to cause littoral movement both to the north and to the south of the point. Typical wave patterns within the bay approaching Buhne Spit transferred from historical aerial photographs are shown on Figure 4.

OFFSHORE WAVES. A study of wave action in the vicinity of the Humboldt Bay jetties was made by the USCE for a survey report "Humboldt Bay-1950" using refraction diagrams. The characteristics of the waves used for the diagrams were for waves occurring most frequently as shown in the Scripps Institution of Oceanography "Wave Report No. 68". The diagrams were constructed for existing conditions of the bar seaward of the jetties and assumed a condition in which the depths over the bar and areas adjacent to it were increased to 40 feet. Their refraction diagrams indicated that, for 1950 conditions, waves were affected by the seaward submarine slope of the bar which caused some convergence to occur before the waves reached and/or passed over the bar crest. The crest of the bar produced additional convergence so that waves either broke on the bar or advanced toward the jettied entrance considerably higher than waves in comparable




FREQUENCY DISTRIBUTION ROSE
STATION 2. 1951-1974 COMBINED SEA/SWELL






SOUTHWEST WINDS			
RETURN PERIOD (YEARS)			
FASTEST MILE			
YEARS	25	50	100
MPH	56	59	62
H	2.45	2.56	2.65
T	2.89	2.94	2.99
I	0.51	0.49	0.46

BUHNE SPIT/KING SALMON
LOCAL WIND WAVES
DIRECTION, HEIGHT & PERIOD



SWELL



SPIT/KING SALMON

WIND FREQUENCY

DISTRIBUTION ROSE
JULY 1938-DEC 1942 EUREKA WEATHER BUREAU STA
JAN 1943-DEC 1967 HUMBOLDT BAY P.F.

PLATE I

STATE OF CALIFORNIA		RESOURCES AGENCY	
BOATING	FACILITIES	DIVISION	
HUMBOLDT COUNTY			
BUHNE SPIT - KING SALMON			
LOCAL WIND, FETCH & WAVE DIAGRAM			

DATE		DESIGNED BY	
DRAWING NUMBER		CHECKED BY	
SHEET NUMBER		BY	
OF		REVISION	
		DATE	
		SUPERVISOR	
		DATE	
		DIVISION CHIEF	
		DATE	

depths elsewhere. The USCE refraction diagrams also indicate that waves advancing from any direction south of west-northwest will tend to produce upcoast littoral drift along the south and north spits.

Waves with a height of 10 feet or greater, occurring most frequently in the Pacific Ocean in the vicinity of Humboldt Bay, have an average period of 9 seconds. This period over the bar, assumed as 20 feet, has little effect on the wave height so that the effect of refraction determines the height of waves seaward of the jetties. Waves having a period of from 12 seconds to 16 seconds are increased in height from 15 percent to 30 percent, respectively, by the bar. This increase is in addition to the effect of USCE's comparisons of the refraction diagrams constructed for conditions existing during their survey report study period with those drawn for an assumed depth of 40 feet over the bar and indicated that no appreciable reduction in the height of 9 second waves would occur with an increase in depth over the bar. The reason for this assumption by USCE is that the seaward slope of the bar, in depths greater than 40 feet, caused wave convergence before the 40 foot depth is reached. However, the increase in depth would permit practically all 9 second waves from the northwest and the west to pass over the bar without breaking. Present depths over the bar cause northwest waves and west waves to break when the deep-water wave height is about 12 to 15 feet. For waves with periods of 12 seconds or greater, the USCE comparison indicated that a bar depth of 40 feet would result in a decrease in wave height in the vicinity of the entrance channel. For example, a 12 second wave from the northwest breaks on the bar when the deep-water wave height is about 9 feet or greater. When the depth over the bar is increased to 40 feet, 12 second northwest waves do not break on the bar. USCE indicated that these waves are reduced in height about 12 percent at the bar and about 7 percent near the jetties.

WAVE STATISTICS. The Department of Boating and Waterways has compiled wave statistics from the California Coastal Data Program (CCDP). Humboldt Bay wave rider (Inner) buoy and the California Deep-Water Wave Statistics (Station 2) (CDWS) to compare the occurrence and frequency of ocean waves near the entrance to Humboldt Bay as shown in Table 2. The California Coastal Data Program buoy was in operation for 15 months and can only be used for a general comparison against the 25 year record of the deep-water statistics. CCDP indicated that, 22.6% of the time waves with a significant height of 4-6 feet occurred, compared with CDWS where waves with a significant height of 4.9-6.6 feet occurred 27.3% of the time. The major wave activity occurred between periods of 4-6 to 6-8 seconds with significant heights between 1.6 to 6.5 feet, comprising 57.2 percent of the time. These waves can pass through the Humboldt Bay entrance jetty and be the dominant sediment transport vehicle. A review of the wave statistics compiled

TABLE 2
CALIFORNIA COASTAL DATA PROGRAM
Humboldt Bay Wave Rider (Inner)

Number Of Days in Month That Significant Wave Height > 18-Feet																	Total Occ's (Days)
Wave Height-	YEAR 1981										YEAR 1982						
(Feet)	-JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	OCT	NOV	JAN	FEB	MAR	APR	MAY		
18+	3	-	-	-	-	-	-	-	-	1	-	-	-	-	-	4	
16-18	2	-	-	-	-	-	-	-	-	-	-	-	-	2	-	4	
14-16	3	1	2	-	-	-	-	-	1	3	4	-	2	-	-	16	
12-14	1	2	4	2	-	1	-	-	2	3	3	-	3	1	1	23	
10-12	5	2	9	3	1	1	-	-	1	4	4	1	6	4	5	46	
8-10	1	4	6	7	5	2	4	-	5	4	4	2	4	4	5	57	
6-8	2	6	4	11	6	5	10	8	5	7	2	1	4	7	9	87	
4-6	0	5	3	5	11	12	9	13	12	2	2	2	3	9	5	92	
2-4	0	3	0	2	7	7	6	10	4	1	1	1	1	3	6	52	
0-2	14	5	3	0	1	2	2	-	1	0*	0*	-	1	0	0	29	
Total	31	28	31	30	31	30	31	31	31	25	20	7	24	30	31	411	
	* Gage not recording part of month																

* Gage not recording part of month

DEEP-WATER WAVE STATISTICS
of the
CALIFORNIA COAST--STATION 2
January 1951-1974
PERIOD FREQUENCY OF OCCURRENCE DISTRIBUTION
COMBINED SEA/SWELL

WAVE PERIOD (Seconds)	4-6	6-8	8-10	10-12	12-14	14-16	16+	TOTAL OCC'S
WAVE HEIGHT (Feet)								
23.0-+	-	-	-	2	10	2	-	14
19.7-23.0	-	-	-	17	2	-	-	19
16.4-19.7	-	-	19	58	5	2	-	64
13.1-16.4	-	1	112	7	17	3	-	140
9.8-13.1	-	114	220	59	22	5	3	402
8.2-9.8	-	289	34	38	19	9	6	394
6.6-8.2	13	493	107	37	41	14	21	726
4.9-6.6	372	499	135	87	64	62	38	1257
3.3-4.9	934	329	169	121	188	147	21	1909
1.6-3.3	683	231	115	111	270	55	4	1469
0.0-1.6	10	75	31	16	65	15	3	215
TOTAL	2012	2031	942	512	700	314	96	6607

by Marine Consultants (MC) for the same station as CDWS indicated waves with a significant height between 1 to 4.9 feet occurred 60% of the time. Table 3 below compares the three statistical bases for offshore deep-water combined sea/swell waves in the vicinity of Humboldt Bay.

TABLE 3

HEIGHT (Feet)	DEEP-WATER WAVE STATISTICS COMPARISON COMBINED SEA/SWELL		
	Occurrence percent of time		
	CDWS	CCDP	MC
0-2	7.0	7.1	27.2
2-4	15.2	12.7	24.5
4-6	25.8	22.6	18.5
6-8	23.2	21.2	10.1
8-10	8.5	13.9	6.0

The above comparison indicates that the CDWS and CCDP have very close correlation with wave heights between 0 to 6 feet and that the MC statistical data for combined sea/swell does not compare to CDWS or CCDP until the 8 to 10 foot wave height. This would indicate that CDWS and CCDP should be used for sediment transport within the bay, assuming that these waves would pass through the jetties and reach Buhne Spit without breaking offshore and reforming.

ENVIRONMENTAL FACTORS WITHIN THE BUHNE POINT AREA

GEOMORPHOLOGY

The area adjacent to Buhne Point is composed of alluvium-filled valley floors between ridges of Pliocene-Pleistocene marine sediments. Inland and east of Buhne Point are rocks of the Franciscan formation. The bluff area at Buhne point is part of the Pliocene-Pleistocene marine deposits and is composed of interbedded layers of medium and fine-grained, reddish to buff-colored sandstone, blue clay (Mud-rock) and gravel. The material comprising the bluff is relatively soft and, prior to the construction of the PG&E's rock revetment along the base of the bluff, was easily eroded by wave action. The adjacent low land to the north and east of the bluff at Buhne Point is peaty silt underlain by sandy silts and clay to a depth averaging about 10 feet below mean lower low water. The bluff at Buhne Point is probably the last remnant of a more extensive series of beds, which once extended over the area.

Two sandy spits are located in the vicinity of Buhne Point. The Elk River Spit at the northern end of the area is composed of fine, cohesionless, gray sand with a trace of shell. Additionally, small rounded gravel is also found on Elk River Spit. The spit has an average height of about 17 feet above mean lower low water. Buhne Spit, located at the southern end of the area, projects from shore at the southwestern end of Buhne Point. The surface material of the spit consists of coarse to fine sand, gray to black in color, with a trace of shell. Buhne Spit has an average height of about 16 feet above mean lower low water. Over the period of record, both Buhne Spit and Elk River Spit have undergone considerable change with respect to location. Details regarding changes in the location of the spit are given in the section of this report headed "EROSION BUHNE SPIT" and shown on Plates II and III.

Samples of materials obtained in connection with the USCE investigations indicate that the bottom material in the study area consists generally of cohesionless, gray to black-colored sand, ranging in size from very fine to medium. In the vicinity of the juncture of Buhne Point and Buhne Spit, the bottom is also composed of bluish clay, clayey silt, pieces of shells and organic material.

WINDBORNE TRANSPORT OF BEACH MATERIAL

There is no evidence of extensive windborne transport of beach material in the study area. However, during strong northerly and northwesterly winds, it has been observed that movement of sand occurs from the north spit into the jettied entrance channel near the root of the north jetty. The amount of sand moved in this manner is unknown.

CHARACTERISTICS OF LITTORAL MATERIAL

Samples of shore and bottom materials were obtained by USCE from the Buhne Spit-Elk River Spit area at locations shown on Figure 2 in Appendix 2 of their Buhne Point Study 1956 (BPS). Shore samples were taken at midtide level, approximately 3.5 feet above mean lower low water, and bottom samples were taken in depths of 6 feet below mean lower low water. The samples were analyzed for grain size. Details of the analyses are contained in BPS appendix 2.

USCE found that the shore materials consisted of grayish-black colored, fine and medium sands, with median diameters ranging from 0.20 millimeter to 1.40 millimeters and sorting coefficients ranging from 1.24 to 3.34. The bottom samples were also grayish-black in color and consisted principally of fine sand having median diameters ranging from 0.22 to 0.25 millimeter and sorting coefficients ranging from 0.21 to 1.31. Of four bottom samples taken, 1 consisted of a sandy silt or clay with a median diameter and sorting coefficient of 0.017 and 3.74, respectively.

SUBSURFACE MATERIALS

For the USCE's Buhne Point Study, 1 boring was made in the Buhne Point area to a depth of 34 feet below mean lower low water at the location shown on Figure 2 in Appendix 2. The boring indicates that the problem area was underlain by a 4.5 foot layer of sand, silt, and loose sand and gravel extending to a depth of about 3 feet above mean lower low water. Below this elevation, the subsurface material consists of a gumbolike clay extending to 9 feet below mean lower low water. Additional borings were taken by USCE along the Fields Landing Channel in July 1974 for their "Navigation Channel Implementations Study" and indicates a gray silty clay at a depth of 29.5 feet MLLW. A comparison of the two borings confirms the presence of a sandy silty clay below any remaining sand on Buhne Spit.

SOURCES OF LITTORAL MATERIAL

USCE has identified five possible sources of littoral material available to the present shore in the study area.

These sources are: (a) sediment brought into the bay by tributary streams; (b) material from within Humboldt Bay made available by scouring action of currents and waves on the banks and channels and on shoals and shallow-bottom areas; (c) littoral material from the Pacific Ocean deposited in the bay channels by waves, tidal currents, or winds; (d) material dredged from project channels and dumped in the bay; and (e) material eroded from the Buhne Point area. Due to the nature of the tributary drainage areas and the size of the streams entering Humboldt Bay, the amount of sediment carried by streams is considered insignificant and will not be considered as a source for beach nourishment.

In the Buhne Point area, marked changes have occurred in the shallow-water area between Buhne Spit and Elk River Spit. For the period 1911 to 1955, the net change in the shallow-water area has been erosion. Within the limits covered by the USCE 1955 survey, it was estimated that 2,107,000 cubic yards of bottom material below mean lower low water were eroded during this period. Some of this material may have been carried to shore by wave action and tidal currents.

LITTORAL TRANSPORT. Material derived from littoral transport along the Pacific Ocean shoreline may be deposited within the bay by waves, tidal currents, or winds. Based on studies made by USCE in connection with navigation improvements of Humboldt Bay, it appears that the predominant direction of littoral transport along the Pacific Ocean shoreline is from north to south. The net rate of transport is not known. However, the relative stability of the Humboldt Bay bar and of the shoreline of the South Spit seems to indicate a fairly constant supply of sand from littoral sources. Therefore, it is possible that littoral material deposited in the vicinity of the entrance channel is redeposited ultimately on the bar or moves past the jettied entrance.

BUHNE SPIT NOURISHMENT. Prior to 1950, material derived from maintenance dredging of the Humboldt Bay project channels was dumped within the limits of the Bay. As determined from available dredging maps, the principal dump areas were: (a) deep water at the bayward end of the entrance channel; (b) a deep water area west of the northern end of Fields Landing Channel; and (c) deep water near Fairhaven, in what is now part of North Bay Channel. Before 1915, no dredged material was dumped in the bay. Between 1915 and 1949, inclusively, it is estimated that 2,711,000 cubic yards of dredge spoil were dumped in the bay. Since 1950, all dredge spoil material has been deposited in the Pacific Ocean in deep water south of the bar and entrance channel.

Between 1854 and 1952, it has been estimated by USCE that 4,700,000 cubic yards of material were eroded from the Buhne Spit area. Table 4 gives the loss above elevation +6.0 (MLLW), that occurred for certain intervals during the period of record.

TABLE 4
EROSION AT BUHNE POINT AREA HUMBOLDT BAY
Above Elevation +6.0 Feet (MLLW)

Period	Years	Amount	Average Annual Rate
1854-1911	57	1,850,000	32,500
1911-1930	20	650,000	32,500
1930-1946	16	1,470,000	92,000
1946-1952 1/	6	780,000	130,000
1854-1952	99	4,750,000	48,000




1/ Erosion during period 1946-52 based in part on a survey made in June 1955. However, the 1955 survey is considered to represent 1952 conditions at the point because the revetment, now protecting the shore, was constructed in 1952.

EROSION BUHNE SPIT

The Department of Boating and Waterways has compiled aerial photographs for the period 1948 through 1980 and transferred the interpreted high water line to a base map shown on Plate II to determine the area of the spit bounded by the present development at King Salmon. The area of the spit in 1948 was about 25 acres, increasing to about 29 acres in 1956, and was assumed to reach zero in the spring of 1982. There was a uniform rate of erosion on the spit from 1961 until 1979. The annual erosion rate was about 14,000 cubic yards per year. During this period the beach face eroded at a rate of about 27 feet per year. The average rate of erosion of the beach face from 1948 through 1980 was about 25 feet per year. The offshore profiles along USCE profile line NO. 15 indicate that only the sand fill area has suffered appreciable erosion. The offshore beyond the sand fill has maintained a fairly uniform elevation during the entire period, indicating very little erosion of the clayey material. Some scouring has occurred along the rock revetment paralleling Buhne Point Drive.

TRIBUTARY DRAINAGE

The drainage area tributary to Humboldt Bay is about 225 square miles in extent. The principal streams entering the bay between Eureka and the southerly limits of the Bay are Elk River and Salmon Creek, which have drainage areas of 57



Notes:
1. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
2. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
3. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
4. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
5. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
6. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
7. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
8. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
9. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.
10. The map shows the location of the study area relative to the coastline and the location of the study area relative to the coastline.

AERIAL PHOTOGRAPHY		
AGENCY	DATE	PHOTO NO.
U.S.C.E.	DEC. 1939	
TELEDYNE	NOV. 6, 1941	7490-720
U.S.C.E.	DEC. 23, 1941	CVL-58
U.S.C.E.	FEB. 8, 1942	R14-52
HUMBOLDT CO.	JUNE 22, 1948	CDF2-14-80
U.S.G.S.	DEC. 23, 1956	QUAD MAP
HUMBOLDT CO.	AUG. 1962	HCN-2-7-118
U.S.C.E.	DEC. 19, 1962	HH7-4
D.W.R.	MAY 14, 1970	76-8-58
D.N.O.D.	DEC. 19, 1976	AFU-C-124
AIR DATA SYSTEMS	JUNE 6, 1979	
AIR DATA SYSTEMS	MARCH 24, 1980	23-124







PHOTO NO.

7490 - 720
CVL - 58
R14 - 52
CDF2-14-80
QUAD MAP
HCN-2-7-118
HH7-4
76-8-58
AFU - C - 124

13-124

PLATE II



LEGEND


SHORELINE LOCATIONS BY YEARS

— • — 1955 — • —
• • • • • 1946 • • • • •
— — — 1939 — — —
— — — 1931 — — —
— • • — 1929 — • • —
— • • — 1926 — • • —

NOTES:

Base Map is 1972 USGS Map of Fields
Landing Quadrangle.
Shore line shown represents the
approx. line of Mean High Water.
Depth contours are in feet below
Mean Lower Low Water (MLLW) Datum.
One foot depth contours (---) are
approximated from a July 1960 U.S.C. of
G.'s Hydrographic Survey Contract and
from Humboldt Co. Aerial Photography
taken at 9:05 a.m. on May 29, 1962 (Tide
Elev. = -1.51).
Grid coordinates are from the Calif.
Coordinate System Zone 1.
Bunka Shipbuilders, Inc., property
lines established from P.C.M.'s map of
Tidelands Survey #102.





Map is 1972 USGS Map of Pacific
coastline
Line shows represents the
line of Mean High Water.
Contours are in feet below
Low Water (MLLW) Datum.
and depth contours (100 fathoms)
are from a July 1960 U.S.C. of
Graphic Survey Contract and
100 fathoms Aerial Photography
taken on May 25, 1962 (Tide
11).
Coordinates are from the Calif
System Zone 1
Shipbuilders, Inc., property
obtained from P.C.M.'s map of
Survey 1102.

PLATE III

and 17 square miles respectively. No data are available regarding runoff from the sediments carried by these streams. At the present time, Elk River drains an area consisting of, for the most part, second-growth timber lands on which selective logging is practiced. Even during periods of high runoff, Elk River is seldom able to break through Elk River Spit. Several attempts have been made to provide a channel across Elk River Spit but the river has not been able to maintain such a channel. This lack of sediment transport by the two major tributary streams confluent with Humboldt Bay does not provide sufficient beach nourishment to sustain the sand bar and protective beaches in the Buhne Point to Elk River stretch of bayfront. The major beach nourishment material is transported into the bay through the jettied entrance across the navigation channels and onto the bar. The Corps of Engineers present maintenance dredging program which dredges the main navigation channels within the bay and deposits the dredge spoil at a deep ocean site has further depleted any beach nourishment material available to the the Buhne Spit area.

MAPS

The maps used in the preparation of this report include the latest and the historical editions of the National Ocean Survey Chart No. 18622; the U. S. Geological Survey quadrangle sheets for Eureka, Ferndale and Fortuna; and Corps of Engineers condition survey maps of Humboldt Bay. In addition, use was made of aerial photographs taken by various federal and state agencies for the years 1932 through 1982. These aerial photographs are on file in the Humboldt County Environmental Center. Maps were also prepared by the Department of Boating and Waterways to accompany this report.

SHORE OWNERSHIP

The entire Buhne Point area is privately owned. Buhne Spit has been developed as a fishing resort known as King Salmon Resort. No bathing beaches are involved within the proposed project area but the spit is utilized for sport fishing and clamming. The project area is presently owned in fee by the Eureka Shipbuilders Inc. and title to the property is in the process of being transferred to the Humboldt Bay Harbor, Recreation and Conservation District. The property line of the Eureka Shipbuilders holdings is delineated on the plan view of the project area on Plate II and is designated P/L.

BUHNE POINT/KING SALMON SHORE PROTECTION PROJECT

ENGINEERING DESIGN CRITERIA

The design of the rubble-mound structures in this project - breakwaters, seawalls, and groins - was done in accordance with procedures, tables, charts and criteria contained in the U.S. Army Corps of Engineers, SHORE PROTECTION MANUAL, Volumes I, II and III, dated 1977, (SPM), which was developed by their Coastal Engineering Research Center. The design wave selected was the largest wave possible that could break on the structure as determined by the still water depth (ds) at the toe of the structure. The design tidal stage is the estimated maximum high water level, which is +9.5 feet MLLW. The depth of the toe of the structure varies in the various structures. The average depth of the toe of the 400' offshore breakwater is -3.7' (MLLW) which will produce a still water depth of 13.2'. The average depth of the toe of the 2000' seawall varies from +0.0 feet at the south end to -1.5 feet MLLW at the northerly end, resulting in still water depths of 9.5' and 11.0' respectively. The depth of the toe of the outboard end of the groins is about -2.5' to -3.5' MLLW. The larger waves in this area have a period (T) of 8 to 14 seconds and a design wave period of 9 seconds was selected as explained in the section on Waves.

OFFSHORE BREAKWATER STRUCTURE: With $d = 13'$ and $T = 9$ sec
 $d / gT^2 = 13 / 32.2 (9) = 0.00498$, from Fig 7-4 with $d / gT^2 = 0.005$
 and $m = 0.01$; $H_b / d = 0.78$, so $H_b = 0.85 \times 13' = 11.0'$.

But with $T = 14$ sec, $H_b / d_s = 0.87$ and $H_b = 11.3'$
 So a design wave height of 11.5' was selected for the offshore structures. Using equation 7-110 from SPM to determine the nominal weight of the armour stone gives:

$$W = \frac{w}{r} \frac{H^3}{K_D} (S - 1) \quad \text{Det } C = 12,724\# \text{ or } 6 \text{ Tons}$$

for a K_D of 2.5 which anticipates that no damage would result from the design wave. These wave heights and rock sizes correspond very closely with the determinations of the Corps of Engineers in their Beach Erosion Control Report for Humboldt Bay (Buhne Point) dated 5 October 1956.

A top elevation of 7.0' was selected for the breakwater to enable it to practically eliminate any waves occurring at Mean High Tide and to substantially reduce any waves which might occur very rarely at the estimated highest water level of 9.5'. With a still water level of +6.0 feet MLLW the still water depth, d , is :

$$d = 6.0 + 3.7 = 9.7' \quad \text{and} \quad h = 7.0 + 3.7 = 10.7'$$

Using a 1:2 slope on the breakwater and a top thickness, b , of 12.0' will give $b/h = 12/10.7 = 1.12$ and $h/ds = 10.7/9.7 = 1.104$; with $ds/gT^2 = 9.7/32.2 (9)^2 = 0.0037$, so interpolating from figure 7-40 & 7-41 gives $H_t/H_i = 0.307$, or $H_t = 0.307 H_i$ which results in approx. 90% reduction of wave energy. With a still water level of 9.5', $ds = 13.2$, so $ds/gT^2 = 0.00506$, and $h/ds = 10.7 / 13.2 = 0.8106$, so $H_t = 0.575 H_i$ which results in approx. 66% reduction of the wave energy. The breakwater was placed about 250' offshore so it would be far enough from the shore to allow sand to accumulate behind it but not far enough to allow the waves to reform after they have broken over it.

RUBBLE-MOUND SEAWALL: For the seawall the ds varies from 11.0' to 9.5'. With $m = 0.02$, a $ds = 12.0'$ would produce $ds/gT^2 = 0.004$, and from Fig. 7-4 $H_b = 0.94 ds = 10.34'$. For $ds = 9.5$, $H_b = 9.0'$. Using equation 7-110 from the SPM again would indicate rock sizes of 5.0 Ton to 3.0 Ton with a K of 2.5.

Wave run-up was checked to determine the design height of the wall using $ds = 11.0'$, $m = 0.02$, $T = 9.0$ sec, and $H_b = 10.3'$; so $H_b/gT^2 = 0.00395$ and from Fig 7-5 $H_b/H_o! = 1.2$ which gives $H_o! = 8.6'$, $H_o!/gT^2 = 0.0033$, and $ds/H_o! = 1.28$. Using $\cot \theta = 2$ (2:1 slope on the face of the seawall) and interpolating between Fig. 7-10 and 7-11 will result in $R/H_o! = 2.9$ for a smooth surface. Therefore $R_s = 2.9 \times 8.6 = 25.3'$ or $R_r = 0.55 \times 25.3 = 13.9'$. This indicates run-up to elevation. $9.5 + 13.9 = 23.4'$ MLLW. Which is way above street level so run-up is rechecked using the composite slope method with a seawall to elev. 18.0' with a 10' wide top and a 2:1 slope.

$$\begin{aligned} \text{Then } H_o! &= 8.6, \quad H_o! / gT^2 = 0.0033, \\ \text{and } H_o! / L &= 2 (H_o! / gT^2) = 6.28 (0.0033) = 0.0207, \\ \text{then from Fig 7-3 } H_o! &= 10.2', \text{ and } H_o! / gT^2 = 0.00392. \\ \text{From Fig 7-2 } d / H_o! &= 1.15 \text{ so } d = 1.15 \times 10.2 = 11.73' \\ \text{and } X &= (11.73 - 11.0) / 0.02 = 36.5' \\ \text{Then } X &= 36.5 + 39 + 10 = 85.5, \text{ and } Y = 11.73 + 8.5 = 20.23, \text{ and } \cot \theta = 4.23 \end{aligned}$$

with $db/H_b = 1.73/8.6 = 1.35$. From Fig 7-10 & 7-11 $R/H_b = 1.73$ then $R = 1.73 \times 8.6 = 15.0$ which would indicate run-up to elev. $8.7 + 9.5 = 17.7'$ in the very worst conditions. So elev 19.0' is considered high enough for this design.

RUBBLE-MOUND GROINS: With a maximum $ds = 13'$ for the groins and a $T = 9$ sec. $ds/gT^2 = 0.0046$ and from Fig 7-4 $H_b/ds = 0.85$ for $m = 0.01$. So H_b will vary from 11.0' to 9.4'. Using equation 7-110 from the SPM again but using $K_d = 4.0$ will produce a rock size of 3.5 Tons to 2.2 Tons for the armour stone. The 2:1 slope would be used for 50' at the offshore end of the groin with a 1.5:1 slope on the rest of the length. It was anticipated that the protective sand beach would be built up to elev +10.0' MLLW so the top of the groin was set for +12.0' MLLW.

H-PILE WITH WOOD LAGGING GROIN: It is anticipated that the top of the sand fill upcoast of the groin would be elev. +10.0' max. The elev of the existing ground downcoast of the groin varies from 0.0 to -2.5' MLLW so the height of retained material would be 10 to 12 feet. General guidelines for cantilever sheet piles in fairly loose granular material call for a depth of penetration for the pile of 1.3 to 1.5 times the height of retained material. Using a factor of 1.5 would give a penetration length of 15 to 18 feet or a pile tip elev of -15' to -20' MLLW. For H-Beam piles with timber lagging, the penetration factor is increased to 2.0 which produces a penetration length of 20 to 24 feet and a pile tip elev. of -20' to -26' MLLW. Previous borings indicate that there may be some stiff material at these depths and the tip elevation may be reduced somewhat in the final design. Experience at previous projects indicates that the 4" x 12" lagging on a 6' simple span are adequate and that HP 12 x 74 pilings will also be sufficient.

ALTERNATIVES COMPARISON

The recommended shore protection alternative was determined from two analytical phases: (1) preliminary screening and, (2) final selection. Each of these comparative phases is described in the following sections.

PRELIMINARY SCREENING. A preliminary comparison of alternatives was used to eliminate those protection methods that clearly were less favorable than the others. This allowed the final selection to be more closely analyzed without unnecessary confusion. Since a relatively large number of alternatives were developed and analyzed, a numerical comparison was used for preliminary screening (see the following Table A).

The numerical comparison relates to the previously described project goals and constraints. Under the general category of "function", two factors are listed. The first is "protection capability", which encompasses the probable effectiveness in controlling erosion and the justifiable feeling of well being by adjacent residents. The other factor is "engineering confidence" which includes an evaluation of each alternative's ability to provide long-term project life and to withstand structural or operational stresses due to extreme storm events.

The "economics" category relates simply to factors of expected "construction cost" and "maintenance cost" for each alternative. The higher ratings reflect lower costs. To further enhance the economic comparison, the table presents the estimated construction costs of each alternative in dollar amounts and relative maintenance costs in terms of high, moderate or low.

The "environmental" category also is divided into two factors, "social" and "biological". The social factor relates to protection of aesthetics, visual, recreational, and navigational aspects. The biological factor accounts for impacts upon burial and destruction of habitats.

TABLE 5
BUHNE POINT/KING SALMON HARBOR
SUMMARY OF COST ESTIMATES

PLAN	DESCRIPTION	TOTAL COST
A-3	1400' Curved Combination Groin w/400' Rubble Mound Breakwater.	\$640,000
B-3	1600' Bent Combination Groin w/200' Rubble Mound Groin Upcoast.	\$602,000
C	1750' Combination Groin W/200' Rubble-Mound Groin Upcoast.	\$660,000
D	1400' Bent Combination Groin w/400' Rubble Mound Groin.	\$615,000
E	1200' Bent Combination Groin w/2 Rubble-Mound Groins Upcoast (400' & 300').	\$640,000
F	2000' Rubble-Mound Seawall along Buhne Point Drive.	\$1,080,000
G-1	Import 490,000 cyds. of Sand Fill to Rebuild Spit to 1961 Alignment.	\$1,970,000
G-3	Import 170,000 cyds. of Sand Fill to Rebuild Spit to 1980 Alignment.	\$650,000
H	700' Curved Combination Groin w/3-350' Rubble Mound Breakwaters.	\$736,000
I	1200' Curved Combination Groin w/550' "L" Shaped Rubble-Mound Groin.	\$602,000
J-1	1300' H-Beam Pile & Timber Groin on South End w/450' Rubble-Mound Groin on North End Connected by a 950' Low Rubble-Mound Sill.	\$795,000
J-2	J-1 + 350,000 cyds. Additional Sand Fill for Construction of a Perched Beach.	\$2,200,000

From Tables 5 and 6, certain conclusions can be readily drawn. The alternatives ranked in the top four places all are a long groin/retaining structure with sand filled pockets. Each of these top four alternatives attained more than 20 points. This creates a preponderance of evidence that the recommended alternative should be selected from within the group:

- (a) Alternative A-3, 1400' Groin w/400' Offshore Breawater
- (b) Alternative D, 1400' Groin w/400' Upcoast Groin
- (c) Alternative I, 1200' Groin w/550' "L" shaped groin
- (d) Alternative J, 1300' Groin w/950' low sill & perched beach.

Three of the other alternatives also relied principally upon beach filled groin pockets but appear to provide less functionality, higher costs, and/or notably adverse social impacts. These include Alternatives B,C, and E. The various other configurations of the top four alternatives seem to be too costly for the degree of protection provided.

TABLE 6
DESIGN SELECTION TABLE

Rating Factor	Points		Alternative Designs								
	Max	A-3	B-3	C	D	E	F	G-1	H	I	J-1
FUNCTION:											
Protection Capability	6	4	3	3	3	3	5	2	4	3	5
Engineering Confidence	6	5	2	2	4	3	5	1	4	4	5
COST :											
Construction Cost	6	4	5	4	5	4	2	1	3	6	3
Maintenance Cost	6	4	2	2	3	3	3	1	4	4	5
ENVIRONMENTAL:											
Social	6	4	2	2	4	4	1	2	3	4	4
Biological	6	5	3	3	4	4	2	2	5	4	3
TOTAL POINTS	36	26	19	17	23	21	18	9	23	25	25
RANKING		1	7	9	4	6	7	10	4	2	2

FINAL SELECTION. As a result of their inclusion in the final selection process, the long groin with the other alternate features were analyzed in more detail to more confidently assess comparative qualities.

Little comparative difference was found between these alternatives in the preliminary screening; therefore, the combination of long groin and offshore structure, the perched beach configuration and the long groin and upcoast groin were combined and analyzed. Because of the offshore depths and the three dimensional nature of the problem, a range of project effectiveness and costs can be achieved by the various combinations of groin length, length of offshore structure and segmentation configurations.

CONCLUSIONS AND RECOMMENDATIONS

SUMMARY OF FINDINGS: Approximately 2000 lineal feet of shoreline at Buhne Spit, located just west of King Salmon opposite the Humboldt Bay entrance jetties, persistently in the past few years has receded at rates of 15 to 27 feet per year, threatening Buhne Point Drive and adjacent residences. The shoreline recession is principally caused by waves and swell that enter Humboldt Bay through the navigation channel between the jetties. These waves (with annual recurrence heights of about 10 feet) impact on the beach in the Buhne Spit area and transport sand along the spit and into Fields Landing Channel and PG&E's powerplant cooling water intake channel.

An analysis of the twelve shoreline protection measures demonstrates that placement of various groins, seawalls, or other structures upon Buhne Spit to retard erosion is preferable for this project. Some of the alternatives exhibit excessive maintenance costs and would require renourishment of the beach at frequent intervals.

Offshore structures that dissipate wave energy, thereby reducing erosional conditions at the shoreline, are favored over other protection methods. These offshore structures can function effectively over the long-term and form an open pocket beach for nourishment to move downcoast into the groin pocket. They avoid unacceptable impact upon the social and biological values of the spit. Their slight danger to shallow water navigation can be mitigated by navigational aids (buoys and/or lights).

RECOMMENDATIONS: Future project phases should concentrate upon the design and construction of a long groin and offshore rock rubble breakwater to protect the eroding shoreline from excessive wave energy and concomitant erosion problem. The final design phase should begin with establishment of precise design criteria relating to function, cost, and environmental protection. The long groin and offshore rock rubble breakwater with a crest elevation of about 7 feet MLLW can be constructed for about \$640,000 and the configuration can be relied upon to substantially reduce long-term shore recession rates at Buhne Spit. This conceptual design can be altered to accomplish a wide variety of functional or cost requirements. The recommended design is Phase I of a total shore protection project to re-establish Buhne Spit to its approximate area in 1955. Subsequent phases include the placement of about 300,000 cubic yards of sand fill in the groin pocket established by Phase I. Beach nourishment would be furnished by USCE's periodic channel maintenance dredging within Humboldt Bay. Additionally, lengthening of the long groin would prevent sediment from being carried offshore and around the head of the groin during extreme winter wave conditions.

REFERENCES

- U. S. Army Corps of Engineers. San Francisco District, Study of Ocean Beaches Adjoining The Mad River Mouth, September 1973.
- U. S. Army Corps of Engineers. Coastal Engineering Research Center, Shore Protection Manual, Volumes I, II, III, Third Edition, 1977.
- U. S. Army Corps of Engineers. Coastal Engineering Research Center, Technical Report No. 82-3, August 1982, Depth-Limited Significant Wave Height: A Spectral Approach, C. Linwood Vincent.
- U. S. Army Corps of Engineers. Coastal Engineering Research Center, Technical Memorandum No. 35, May 1971, Storm Surge on the Open Coast: Fundamentals and Simplified Prediction, B.D. Bodine
- U. S. Army Corps of Engineers. Waterways Experiment Station, Miscellaneous Paper HL-83-1, Bank Protection Techniques using Spur Groins, R. R. Copeland.
- U. S. Army Corps of Engineers. Coastal Engineering Research Center, Technical Memorandum No. 48, January 1975, The Use of Aerial Photography in the Study of Wave Characteristics in the Coastal Zone, C. M. McClenan and D. L. Harris.
- U. S. Army Corps of Engineers. San Francisco District, Design Memorandum No. 1, Humboldt Harbor and Bay, California, Navigation Improvements, February 1976.
- U. S. Army Corps of Engineers. San Francisco District, Beach Erosion Control Report on Cooperative Study of Humboldt Bay (Buhne Point), Pacific Coast of California, October 5, 1956.
- U. S. Army Corps of Engineers. Coastal Research Center, Technical Memorandum No. 17, A Method for Calculating and Plotting Surface Wave Rays, February 1966, W. S. Wilson.
- D. Lee Harris. Shelf Sediment Transport, Chapter 5, Wave Estimates for Coastal Regions, 1972
- Department of Water Resources. Planning Division, Wind Storms in California, December 1979, J. D. Goodrich.
- Department of Water Resources. Bulletin 185, January 1978. Winds in California, J. D. Goodrich.

REFERENCES CONT'D.

Oregon State Sea Grant College. Reprint American Society of Civil Engineers Proceedings, Civil Engineering in the Ocean/III, June 9-11, 1975, Longshore Currents and Sand Transport, P. D. Komar.

Oregon State Sea Grant College. Reprint Journal of Sedimentary Petrology, 45(4):866-872, 1975, Society of Society of Economic Paleontologists and Mineralogists, Computer Simulation Models Of A Hooked Beach Shoreline Configuration, C.C. Rea, P. D. Komar.

American Society of Civil Engineers. Coastal Engineering 1972 Proceedings Volume II, Use of Crenulate Shaped Bays to Stabilize Coasts, R. Silvester and G. Koon Hoo.

American Society of Civil Engineers. Meeting Reprint 2141, Water Resources Engineering, Sediment Transport, Coast of Northern California, January 21-25, 1974, H. M. DeGraca and R. M. Ecker.

Journal of Geophysical Research. Reprint Volume 87, Pages 5741-5751 July 20, 1982, Bedload and Wave Thrust Computations of Alongshore Sand Transport, R. J. Hallermeier.

Department of Navigation and Development. Deep-Water Wave Statistics for the California Coast, Station 2, Prepared by Meteorology International Inc, February 1972.

National Marine Consultants. Prepared for U. S. Army Corps of Engineers, Los Angeles District, Wave Statistics for Seven Deep Water Stations Along the California Coast, December 1977.

U. S. Naval Weather Service Command. Summary of Synoptic Meteorological Observations. North American Coastal Marine Areas. Volume 8, Area 24-Point Mugu, Area 25-San Francisco, Area 26-Point Arena, May 1970.

APPENDIX A

COST ESTIMATES for ALTERNATE PLANS

at

BUHNE SPIT AREA

COST ESTIMATES

The cost estimates were prepared using 1983 mill price quotes for Mariner Steel at \$670 per ton plus \$120 for transportation from Pennsylvania to Eureka, Calif. Labor and equipment charges for installation were added at \$5.01 per linear foot of pile for a vibratory driving system. This results in a unit price for the steel H-Beam piles of \$32.20 per linear foot of pile installed. Wood prices used in these estimates were \$300 per Thousand Board Foot for treated Doug Fir timber plus \$1.00 per square foot for labor, equipment and misc. materials necessary for installation which results in an installed price of \$2.20 per square foot for the timber lagging. Prices for the rock and granular material were extracted from recent similar contracts in the project area.

In estimating the construction costs it was anticipated that the contractor would be allowed to import and compact granular material for a work platform/access road above high tide as part of his construction method. Although the amount of material could vary between alternatives and contractors, an amount of 25,000 cubic yards was considered with each alternate to maintain a consistent figure for comparison purposes. This material was estimated at a relatively low \$3.00 per cubic yard.

Concrete and steel sheet piling were also considered for groin construction at the beginning of the estimating. But, as their costs appeared to be more than double the cost per linear foot of the other types of construction, they were dropped from consideration at an early stage.

Buhne Point/King Salmon Harbor

Summary of Cost Estimates

<u>PLAN</u>	<u>DESCRIPTION</u>	<u>TOTAL COST</u>
A-3	1400' Curved Combination Groin w/400' Rubble-Mound Breakwater	\$ 640,000
B-3	1600' Bent Combination Groin w/200' Rubble-Mound Groin Upcoast	\$ 609,000
C	1750' Combination Groin w/200' Rubble-Mound Groin Upcoast	\$ 660,000
D	1400' Bent Combination Groin w/a 400' Rubble-Mound Groin	\$ 615,000
E	1200' Bent Combination Groin w/2 Rubble-Mound Groins Upcoast (400' & 300')	\$ 640,000
F	2000' Rubble-Mound Seawall along Buhne Dr.	\$1,080,000
G-1	Import 490,000 cu.yd. Sand to Rebuild Spit to 1961 Alignment	\$1,970,000
G-3	Import 170,000 cu.yd. Sand to Rebuild Spit to 1980 Alignment	\$ 680,000
H	700' Curved Combination Groin w/3-350' Rubble-Mound Breakwaters	\$ 736,000
I	1200' Curved Combination Groin w/550' "L" Shaped Rubble Mound Groin	\$ 602,000
J-1	1500' H Beam Pile & Timber Groin on South End w/350' Rubble-Mound Groin on North End Connected by a 950' Low Rubble Mound Sill	\$ 795,000
J-2	J-1 + 350,000 c.yds. Additional Sand Fill for Perched Beach	\$2,200,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan A-1

I. Rock Rubble-Mound Groin Alternate

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 1400 LF Rock Groin					
Core material	4,340	cu.yd.	\$ 6.00	\$ 26,100	
Rock armour stone, 4 ton average	11,620	ton	20.00	232,400	
Bedding layer 1/2" Ø avg.	7,420	ton	15.00	111,300	
Toe rock, 1/2 ton avg.	1,870	ton	15.00	28,000	
Filter cloth	84,000	sq.ft.	.25	21,000	
					\$418,000
2. 400 LF Rock Breakwater					
6 ton rock	4,280	ton	20.00	\$ 85,600	
Bedding stone, 50# avg.	2,120	ton	15.00	31,800	
Sand dike access road	9,000	cu.yd.	4.00	36,000	
					\$153,400
3. Imported Sand Fill					
Move sand dike	9,000	cu.yd.	1.50	13,500	
Additional sand	16,000	cu.yd.	3.00	48,000	
					\$ 61,500
					770,100
TOTAL ESTIMATED CONTRACT COST					\$853,700
Engineering, Contract Admin. & Contingency					\$126,500
					112,100
TOTAL ESTIMATED PROJECT COST					\$760,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan A-2

1. Steel H-Beam Piles w/Wood Lagging Alternate

Item	Quantity	Unit	Cost	Amount	Total
1. 1400 LF Pile Groin					
HP 12x74 piling	6,125	LF	\$32.20	\$197,500	
4x12 wood lagging	22,400	sq. ft.	2.20	49,300	
4 ton end rock	680	ton	20.00	13,600	
Sand dike access road	20,700	cu. yd.	4.00	82,800	
					\$343,000
2. 400 LF Rock Breakwater					
6 ton rock	4,280	ton	20.00	\$ 85,600	
Bedding stone, 50# avg.	2,120	ton	15.00	31,800	
Sand dike access road	9,000	cu. yd.	4.00	36,000	
					\$153,400
3. Imported Sand Fill					
Move sand dike	25,000	cu. yd.	1.50	\$ 37,500	
					<u>\$ 37,500</u>
TOTAL ESTIMATED CONTRACT COST					\$553,900
Engineering, Contract Admin. & Contingency					<u>\$107,100</u>
TOTAL ESTIMATED PROJECT COST					\$661,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan A-3

I. Combination Groin w/400' of Rubble-Mound Groin + 1000' of H-Beam Pile Groin

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 400 LF Rock Groin Section					
Core material	890	cu.yd.	\$ 6.00	\$ 5,300	
Rock armour stone, 4 ton average	2,995	ton	20.00	59,900	
Bedding layer 1/2" Ø avg.	1,987	ton	15.00	29,800	
Toe rock, 1/2 ton avg.	533	ton	15.00	8,000	
Filter cloth	24,000	sq.ft.	.25	6,000	\$109,000
2. 1000 LF Pile Groin Section					
HP 12x74 piling	4,375	LF	32.20	\$140,900	
4x12 wood lagging	15,000	sq.ft.	2.20	33,000	
Sand dike access road	14,000	cu.yd.	4.00	56,000	\$229,900
5. 400 LF Rock Breakwater					
6 ton rock	4,280	ton	20.00	\$ 85,600	
Bedding stone, 50# avg.	2,140	ton	15.00	31,800	
Sand dike access road	9,000	cu.yd.	4.00	36,000	\$153,400
4. Imported Sand Fill					
Move sand dike	23,000	cu.yd.	1.50	\$ 34,500	
Additional sand	7,000	cu.yd.	3.00	21,000	\$ 55,500
TOTAL ESTIMATED CONTRACT COST					\$532,800
Engineering, Contract Admin. & Contingency					\$107,200
TOTAL ESTIMATED PROJECT COST					\$640,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan B-1

1. Rock Rubble-Mound Groin Alternate

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 1600 LF Rock Groin					
Core material	4,960	cu.yd.	\$ 6.00	\$ 29,800	
Rock armour stone, 4 ton	13,280	ton	20.00	265,600	
Bedding layer, $\frac{1}{2}$ " ϕ	8,480	ton	15.00	127,200	
Toe rock, $\frac{1}{2}$ ton	2,130	ton	15.00	32,000	
Filter cloth	96,000	sq.ft.	.25	24,000	
					\$478,500
2. 200 LF Rock Groin					
Core material	620	cu.yd.	6.00	\$ 3,700	
Rock armour stone, 4 ton	1,660	ton	20.00	33,200	
Bedding layer, $\frac{1}{2}$ " ϕ	1,060	ton	15.00	15,900	
Toe rock, $\frac{1}{2}$ ton	267	ton	15.00	4,000	
Filter cloth	12,000	sq.ft.	.25	3,000	
					\$ 59,900
3. Imported Sand Fill	25,000	cu.yd.	3.00		\$ 75,000
TOTAL ESTIMATED CONTRACT COST					\$613,400
Engineering, Contract Admin. & Contingency					\$121,600
TOTAL ESTIMATED PROJECT COST					\$735,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan B-2

I. Steel H-Beam Piles w/Wood Lagging Alternate

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 1400 LF Pile Groin					
HP 12x74 piling	7,000	LF	\$32.20	\$225,400	
4x12 wood lagging	25,600	sq.ft.	2.20	56,300	
4 ton end rock	680	ton	20.00	13,600	
Sand dike access road	23,680	cu.yd.	4.00	94,700	
					\$390,000
2. 200 LF Rock Groin					
Core material	620	cu.yd.	6.00	\$ 3,700	
Rock armour stone, 4 ton	1,660	ton	20.00	33,200	
Bedding layer, 1/2" Ø	1,060	ton	15.00	15,900	
Toe rock, 1/2 ton	267	ton	15.00	4,000	
Filter cloth	12,000	sq.ft.	.25	3,000	
					\$ 59,800
3. Imported Sand Fill					
Move sand dike	23,500	cu.yd.	1.50	\$ 35,250	
Additional sand	1,500	cu.yd.	3.00	4,500	
					\$ 39,750
TOTAL ESTIMATED CONTRACT COST					\$489,550
Engineering, Contract Admin. & Contingency					\$ 98,800
TOTAL ESTIMATED PROJECT COST					\$588,350

Buhne Point/King Salmon Harbor

Cost Estimate for Plan B-3

I. Combination Groin w/600' of Rubble-Mound Groin + 1000' of H-Beam Pile Groin

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 600 LF Rock Groin Section					
Core material	1,334	cu.yd.	\$ 6.00	\$ 8,000	
Rock armour stone, 4 ton	4,490	ton	20.00	89,800	
Bedding layer, 1/2" Ø	2,980	ton	15.00	44,700	
Toe rock, 1/2 ton	800	ton	15.00	12,000	
Filter cloth	36,000	sq.ft.	.25	9,000	
					\$163,500
2. 1000 LF Pile Groin Section					
HP 12x74 piling	4,375	LF	32.20	\$140,900	
4x12 wood lagging	15,000	sq.ft.	2.20	33,000	
Sand dike access road	14,000	cu.yd.	4.00	56,000	
					\$229,900
3. 200 LF Rock Groin					
Core material	620	cu.yd.	6.00	\$ 3,700	
Rock armour stone, 4 ton	1,660	ton	20.00	33,200	
Bedding layer, 1/2" Ø	1,060	ton	15.00	15,900	
Toe rock, 1/2 ton	267	ton	15.00	4,000	
Filter cloth	12,000	sq.ft.	.25	3,000	
					\$ 59,900
4. Imported Sand Fill					
Move sand dike	14,000	cu.yd.	1.50	\$ 21,000	
Additional sand	11,000	cu.yd.	3.00	33,000	
					<u>\$ 54,000</u>
TOTAL ESTIMATED CONTRACT COST					\$507,300
Engineering, Contract Admin. & Contingency					<u>\$101,700</u>
TOTAL ESTIMATED PROJECT COST					\$609,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan C

I. 1750' Combination Groin w/200' Rubble-Mound Groin

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 750' Section of Rubble-Mount in Combination Groin					
Core material	1,667	cu.yd.	\$ 6.00	\$ 10,000	
Rock armour stone, 4 ton	5,613	ton	20.00	112,300	
Bedding layer, 1/2" Ø	3,725	ton	15.00	55,900	
Toe rock, 1/2 ton	1,000	ton	15.00	15,000	
Filter cloth	45,000	sq.ft.	.25	11,200	
					\$204,400
2. 1000' Section of H-Beam Piles in Combination Groin					
HP 12x74 piling	4,375	LF	32.20	\$140,900	
4x12 wood lagging	15,000	sq.ft.	2.20	33,000	
Sand dike access road	14,000	cu.yd.	4.00	56,000	
					\$229,900
3. 200' Rock Rubble-Mound Groin					
Core material	620	cu.yd.	6.00	\$ 3,700	
Rock armour stone, 4 ton	1,660	ton	20.00	33,200	
Bedding layer, 1/2" Ø	1,060	ton	15.00	15,900	
Toe rock, 1/2 ton	267	ton	15.00	4,000	
Filter cloth	12,000	sq.ft.	.25	3,000	
					\$ 59,900
4. Imported Sand Fill					
Move sand dike	14,000	cu.yd.	1.50	\$ 21,000	
Additional sand fill	11,000	cu.yd.	3.00	33,000	
					\$ 54,000
TOTAL ESTIMATED CONTRACT COST					\$548,200
Engineering, Contract Admin. & Contingency					\$111,800
TOTAL ESTIMATED PROJECT COST					\$660,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan D

I. 1400' Combination Groin w/400' Rubble-Mound Groin

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 400' Section of Rubble-Mound in Combination Groin					
Core material	888	cu.yd.	\$ 6.00	\$ 5,300	
Rock armour stone, 4 ton	3,000	ton	20.00	60,000	
Bedding layer, 1/2" Ø	2,000	ton	15.00	30,000	
Toe rock, 1/2 ton	533	ton	15.00	8,000	
Filter cloth	24,000	sq.ft.	.25	6,000	
					\$109,300
2. 1000' Section of H-Beam Piles in Combination Groin					
HP 12x74 piling	4,375	LF	32.20	\$140,900	
4x12 wood lagging	15,000	sq.ft.	2.20	33,000	
Sand dike access road	14,000	cu.yd.	4.00	56,000	
					\$229,900
3. 400' Rock Rubble-Mound Groin					
Core material	1,240	cu.yd.	6.00	\$ 7,400	
Rock armour stone, 4 ton	3,320	ton	20.00	66,400	
Bedding layer, 1/2" Ø	2,120	ton	15.00	31,800	
Toe rock, 1/2 ton	533	ton	15.00	8,000	
Filter cloth	24,000	sq.ft.	.25	6,000	
					\$119,800
4. Imported Sand Fill					
Move sand dike	14,000	cu.yd.	1.50	\$ 21,000	
Additional sand fill	11,000	cu.yd.	3.00	33,000	
					<u>\$ 54,000</u>
TOTAL ESTIMATED CONTRACT COST					\$513,000
Engineering, Contract Admin. & Contingency					<u>\$102,000</u>
TOTAL ESTIMATED PROJECT COST					\$615,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan E

I. 1200' Combination Groin w/400' & 300' Rubble-Mound Groins

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 300' Section of Rubble-Mound in Combination Groin					
Core material	666	cu.yd.	\$ 6.00	\$ 4,000	
Rock armour stone, 4 ton	2,250	ton	20.00	45,000	
Bedding layer, 1/2" Ø	1,500	ton	15.00	22,500	
Toe rock, 1/2 ton	400	ton	15.00	6,000	
Filter cloth	18,000	sq.ft.	.25	4,500	
					\$ 82,000
2. 900' Section of H-Beam Piles in Combination Groin					
HP 12x74 piling	3,940	LF	32.20	\$126,900	
4x12 wood lagging	13,500	sq.ft.	2.20	29,700	
Sand dike access road	12,600	cu.yd.	4.00	50,400	
					\$207,000
3. 400' Rock Rubble-Mound Groin					
Core material	888	cu.yd.	6.00	\$ 5,300	
Rock armour stone, 4 ton	3,000	ton	20.00	60,000	
Bedding layer, 1/2" Ø	2,000	ton	15.00	30,000	
Toe rock, 1/2 ton	533	ton	15.00	8,000	
					\$103,300
4. 300' Rock Rubble-Mound Groin					
Core material	930	cu.yd.	6.00	\$ 5,600	
Rock armour stone, 4 ton	2,490	ton	20.00	49,800	
Bedding layer, 1/2" Ø	1,590	ton	15.00	23,900	
Toe Rock, 1/2 ton	400	ton	15.00	6,000	
					\$ 85,300
5. Imported Sand Fill					
Move sand dike	12,500	cu.yd.	1.50	\$ 18,700	
Additional sand fill	12,500	cu.yd.	3.00	37,500	
					\$ 56,200
TOTAL ESTIMATED CONTRACT COST					\$533,800
Engineering, Contract Admin. & Contingency					\$106,200
TOTAL ESTIMATED PROJECT COST					\$640,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan F

I. 2000' Permanent Rock Seawall Along Buhne Drive

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 1200' of Rock Seawall using 6 ton Armour Stone					
Sand excavation	13,200	cu.yd.	\$ 3.00	\$ 39,600	
Move/re-use exist. rock	6,000	ton	7.00	42,000	
Rock armour stone, 6 ton	15,000	ton	20.000	300,000	
Rock riprap, 1 ton	9,700	ton	15.00	145,000	
Bedding layer	4,200	ton	12.00	50,400	
					\$577,500
2. 800' of Rock Seawall using 4 ton Armour Stone					
Sand excavation	3,600	cu.yd.	3.00	\$ 10,800	
Move/re-use exist. rock	4,000	ton	7.00	28,000	
Rock armour stone, 4 ton	5,520	ton	20.00	110,400	
Rock riprap, 3/4 ton	4,600	ton	15.00	69,000	
Bedding layer	2,600	ton	12.00	31,200	
					\$249,400
3. Imported Sand Fill	25,000	cu.yd.	3.00		<u>75,000</u>
TOTAL ESTIMATED CONTRACT COST					\$901,900
Engineering, Contract Admin. & Contingency (20% +)					<u>\$178,100</u>
TOTAL ESTIMATED PROJECT COST					\$1,080,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan G

I. Import Sand to Rebuild Spit to Approx. 1961 Alignment

1. Imported Sand Fill - 490,000 cu.yds. @ \$3.50 - \$1,715,000
2. Engineering, Contract Admin. & Contingency (15% +) - 255,000

TOTAL ESTIMATED PROJECT COST \$1,970,000

III. Import Sand to Rebuild Spit to Approx. 1980 Alignment

1. Imported Sand Fill - 170,000 cu.yds. @ \$3.50 - \$ 595,000
2. Engineering, Contract Admin. & Contingency (15% +) - 85,000

TOTAL ESTIMATED PROJECT COST \$ 680,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan H

I. 700' Combination Groin w/three - 350' Rock Rubble Breakwaters

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 200' Section of Rubble-Mound in Combination Groin					
Core material	236	cu.yd.	\$ 6.00	\$ 1,400	
Rock armour stone, 4 ton	1,264	ton	20.00	25,300	
Bedding layer, 1/2" Ø	1,028	ton	15.00	15,400	
Toe rock, 1/2 ton	266	ton	15.00	4,000	
Filter cloth	10,000	sq.ft.	.25	2,500	
					\$ 48,600
2. 500' Section of H-Beam Piles in Combination Groin					
HP 12x74 piling	2,064	LF	32.20	\$ 66,500	
4x12 wood lagging	7,500	sq.ft.	2.20	16,500	
Sand dike access	7,000	cu.yd.	4.00	28,000	
					\$111,000
3. Three - 350' Rock Rubble Breakwaters					
Rock armour stone, 6 ton	11,340	ton	20.00	\$226,800	
Bedding stone, 50#	6,300	ton	15.00	94,500	
Sand dike access	23,800	cu.yd.	4.00	95,200	
					\$416,500
4. Move Sand Dikes					
	25,000	cu.yd.	1.50		<u>37,500</u>
TOTAL ESTIMATED CONTRACT COST					\$615,600
Engineering, Contract Admin. & Contingency (20% +)					<u>122,400</u>
TOTAL ESTIMATED PROJECT COST					\$736,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan I

I. 1200' Combination Groin w/550' "I" shaped Rubble-Mound Groin

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 300' Section of Rubble-Mound in Combination Groin					
Core material	666	cu.yd.	\$ 6.00	\$ 4,000	
Rock armour stone, 4 ton	2,250	ton	20.00	45,000	
Bedding layer, 1/2" Ø	1,500	ton	15.00	22,500	
Toe rock, 1/2 ton	400	ton	15.00	6,000	
Filter cloth	18,000	sq.ft.	.25	4,500	
					\$ 82,000
2. 900' Section of H-Beam Piles w/Wood Lagging in Combination Groin					
HP 12x74 piling	3,940	LF	32.20	\$126,900	
4x12 treated timber lagging	13,500	sq.ft.	2.20	29,700	
Sand dike access	12,600	cu.yd.	4.00	50,400	
					\$207,000
3. 550' "I" Shaped Rubble-Mound Groin					
Core material	1,705	cu.yd.	6.00	\$ 10,200	
Rock armour stone, 4 ton	4,565	ton	20.00	91,300	
Bedding layer, 1/2" Ø	2,915	ton	15.00	43,700	
Toe rock, 1/2 ton	732	ton	15.00	11,000	
					\$156,200
4. Imported Sand Fill					
Move sand dike	12,500	cu.yd.	1.50	\$ 18,800	
Additional sand fill	12,500	cu.yd.	3.00	37,500	
					\$ 56,300
TOTAL ESTIMATED CONTRACT COST					\$501,500
Engineering, Contract Admin. & Contingency (20% +)					\$100,500
TOTAL ESTIMATED PROJECT COST					\$602,000

Buhne Point/King Salmon Harbor

Cost Estimate for Plan J

1. 800' Curved H-Beam Pile Groin w/400' Rubble-Mound Groin &
1400' Rubble-Mound Low Sill

<u>Item</u>	<u>Quantity</u>	<u>Unit</u>	<u>Cost</u>	<u>Amount</u>	<u>Total</u>
1. 1500' H Beam Pile w/Wood Lagging Groin					
HP 12x74 piling	5,850	LF	\$32.20	\$188,400	
4x12 treated timber lagging	20,800	sq.ft.	2.20	45,800	
Sand dike access	18,200	cu.yd.	4.00	72,800	
					\$307,000
2. 450' Rubble Mound Groin					
Core material	1,395	cu.yd.	6.00	\$ 8,400	
Rock armour stone, 4 ton	3,735	ton	20.00	74,700	
Bedding layer, 1/2' ϕ	2,385	ton	15.00	35,800	
Toe rock, 1/2 ton	600	ton	15.00	9,000	
					\$127,900
3. 950' Rubble-Mound Sill					
Rock armour stone, 1 ton	3,563	ton	20.00	\$ 71,300	
Bedding stone, 50'	4,180	ton	15.00	62,700	
Filter cloth	11,300	sq.ft.	.25	2,900	
Sand dike access	13,300	cu.yd.	4.00	53,200	
					\$190,100
4. Move Sand Dike	25,000	cu.yd.	1.50		
					<u>\$ 37,500</u>
TOTAL ESTIMATED CONTRACT COST					\$662,500
Engineering, Contract Admin. & Contingency (20% +)					<u>\$132,500</u>
TOTAL ESTIMATED PROJECT COST					\$795,000

APPENDIX B

WAVE DATA STATISTICS and SUMMARY

for

HUMBOLDT BAY AREA

WAVE DATA STATISTICS

The following pages of data were reproduced from the California Coastal Data Collection Program's monthly reports and from the Deep-Water Wave Statistics for the California Coast, Report for Station 2. This data, along with the summary sheet, were used to select the design wave conditions that the Pacific Ocean area could reasonably be expected to experience on a recurring basis. Wave heights are recorded as the H_s or $H_{1/3}$ value. The significant wave height is the average height of the highest 33 percent of waves for the specified time period. The Shore Protection Manual recommends that the H_{10} wave height be used as the design wave height along the North Pacific Coast. The H_{10} wave height is the average height of the highest 10 percent of waves for the specified time. The $H_{1/3}$ wave can be converted to a H_{10} wave height using the equation $H_{10} = 1.27 \times H_{1/3}$.

CALIFORNIA COASTAL DATA PROGRAM

Humboldt Bay Wave Rider (Inner)

Number Of Days in Month That Significant Wave Height \geq 18-Feet																Total Occ's (Days)
Wave Height - (feet)	YEAR 1981										YEAR 1982					
	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	OCT	NOV	JAN	FEB	MAR	APR	MAY	
18+	3	-	-	-	-	-	-	-	-	1	-	-	-	-	-	4
16-18	2	-	-	-	-	-	-	-	-	-	-	-	-	2	-	4
14-16	3	1	2	-	-	-	-	-	1	3	4	-	2	-	-	16
12-14	1	2	4	2	-	1	-	-	2	3	3	-	3	1	1	23
10-12	5	2	9	3	1	1	-	-	1	4	4	1	6	4	5	46
8-10	1	4	6	7	5	2	4	-	5	4	4	2	4	4	5	57
6-8	2	6	4	11	6	5	10	8	5	7	2	1	4	7	9	87
4-6	0	5	3	5	11	12	9	13	12	2	2	2	3	9	5	93
2-4	0	3	0	2	7	7	6	10	4	1	1	1	1	3	6	52
0-2	14	5	3	0	1	2	2	-	1	0*	0*	-	1	0	0	29
Total	31	28	31	30	31	30	31	31	31	25	20	7	24	30	31	411


* Same port regarding part of month.

* Gage not recording part of month

DEEP-WATER WAVE STATISTICS of the CALIFORNIA COAST--STATION 2 January 1951-1974 PERIOD FREQUENCY OF OCCURRENCE DISTRIBUTION COMBINED SEA/SWELL

WAVE PERIOD (Seconds)	4-6	6-8	8-10	10-12	12-14	14-16	16+	TOTAL OCC'S
WAVE HEIGHT (feet)								
22.0+	-	-	-	2	10	2	-	14
19.7-22.0	-	-	-	17	2	-	-	19
16.4-19.7	-	-	19	38	5	2	-	64
13.1-16.4	-	1	112	7	17	3	-	140
9.8-13.1	-	114	220	38	22	5	3	402
8.2-9.8	-	289	34	38	18	9	6	394
6.6-8.2	11	493	107	37	41	14	21	726
4.9-6.6	372	499	125	87	64	62	38	1257
3.3-4.9	734	529	169	121	183	147	21	1909
1.6-3.3	691	371	115	111	270	55	4	1469
0.9-1.6	10	75	31	16	63	15	3	213
TOTAL	2012	2031	942	512	700	314	95	6607

COASTAL DATA INFORMATION PROGRAM



U.S. DEPARTMENT OF JUSTICE
FEDERAL BUREAU OF INVESTIGATION

8-5



Office of Intelligence
The National Security Agency
DEPARTMENT OF DEFENSE
AND MARITIME

HUMBOLDT BAY BUOY (OUTER)
JAN 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- FEET OR LESS

FEET	DAYS
1	0.
2	0.
3	0.
4	0.
5	0.
6	0.
7	0.
8	1. 1.
9	1. 2.
10	1. 2.
11	1. 2. 3.
12	2. 1. 3. 3.

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR JAN 1981

DATE (JAN)	1	2	3	4	5	6	7
SIG. HT (FT.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (JAN)	8	9	10	11	12	13	14
SIG. HT (FT.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (JAN)	15	16	17	18	19	20	21
SIG. HT (FT.)	12.0	11.1	15.1	12.4	14.2	18.1	21.5
DATE (JAN)	22	23	24	25	26	27	28
SIG. HT (FT.)	19.0	16.5	11.0	8.0	12.3	17.7	14.5
DATE (JAN)	29	30	31				
SIG. HT (FT.)	11.5	9.4	7.7				

HUMBOLDT BAY BUCY (INNER)
FEB 1981

PEPSISTENCE
CONSECUTIVE DAYS (1 OR MORE SIGNIFICANT
WAVE HEIGHT 15 -N- FEET OR LESS

FEET	DAYS
1	0,
2	0,
3	1,
4	3, 2,
5	8,
6	9,
7	9, 1, 1, 1,
8	12, 1, 1, 2,
9	13, 1, 1, 1, 2,
10	13, 2, 1, 1, 2,
11	16, 1, 1, 2,
12	19, 1, 2,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR FEB 1981

DATE (FEB)	1	2	3	4	5	6	7
SIG. HT (FT.)	8.6	8.1	6.4	5.5	4.4	3.9	3.9
DATE (FEB)	8	9	10	11	12	13	14
SIG. HT (FT.)	5.0	3.4	4.1	5.3	7.6	7.9	10.9
DATE (FEB)	15	16	17	18	19	20	21
SIG. HT (FT.)	9.6	7.4	12.2	7.3	12.1	16.0	9.2
DATE (FEB)	22	23	24	25	26	27	28
SIG. HT (FT.)	0.0	0.0	0.0	0.0	0.0	7.1	8.1
DATE (FEB)	29	30	31				
SIG. HT (FT.)	0.0	0.0	0.0				

HUMBOLDT BAY BUDY (INNER)
MAR 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- FEET OR LESS

FEET	DAYS
1	0.
2	0.
3	0.
4	0.
5	1.
6	1, 2.
7	1, 1, 1, 2.
8	1, 1, 1, 1, 1, 1, 2, 1.
9	3, 1, 1, 1, 2, 2, 1, 1.
10	3, 2, 1, 1, 1, 5, 1, 2.
11	3, 2, 1, 2, 1, 5, 1, 1, 2.
12	3, 2, 6, 6, 1, 4.

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAR 1981

DATE (MAR)	1	2	3	4	5	6	7
SIG. HT (FT.)	6.8	8.9	5.5	14.7	10.0	8.2	14.3

DATE (MAR)	8	9	10	11	12	13	14
SIG. HT (FT.)	13.7	9.6	11.9	11.5	7.3	11.7	7.5

DATE (MAR)	15	16	17	18	19	20	21
SIG. HT (FT.)	13.1	11.4	9.1	8.1	10.3	5.8	5.3

DATE (MAR)	22	23	24	25	26	27	28
SIG. HT (FT.)	0.0	0.0	0.0	11.0	12.7	13.9	7.5

DATE (MAR)	29	30	31
SIG. HT (FT.)	11.9	10.4	9.2

HUMBOLDT BAY BUOY (INNER)
APR 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- FEET OR LESS

FEET	DAYS
1	0,
2	0,
3	1, 1,
4	1, 1,
5	2, 1, 2, 1,
6	4, 1, 2, 1,
7	1, 1, 7, 1, 7,
8	2, 2, 11, 8,
9	2, 14, 8,
10	2, 15, 8,
11	4, 24,
12	5, 24,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR APR 1981

DATE (APR)	1	2	3	4	5	6	7
SIG. HT (FT.)	10.5	11.0	8.0	7.2	12.3	13.2	9.7

DATE (APR)	8	9	10	11	12	13	14
SIG. HT (FT.)	7.1	8.1	8.5	8.4	8.2	4.5	3.1

DATE (APR)	15	16	17	18	19	20	21
SIG. HT (FT.)	5.6	6.2	7.3	7.4	4.7	7.8	7.1

DATE (APR)	22	23	24	25	26	27	28
SIG. HT (FT.)	10.6	8.3	7.2	6.6	4.9	3.4	6.9

DATE (APR)	29	30	31
SIG. HT (FT.)	7.3	4.6	0.0

HUMBOLDT BAY BUOY (INNER)
MAY 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.50	0,
1.00	1, 1,
1.50	1, 1, 1, 4, 3,
2.00	6, 6, 10, 1,
2.50	7, 20,
3.00	9, 21,
3.50	31,
4.00	31,
4.50	31,
5.00	31,
5.50	31,
6.00	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAY 1981

DATE (MAY)	1	2	3	4	5	6	7
SIG. HT (M.)	2.5	2.5	1.8	1.7	2.0	1.7	1.9
DATE (MAY)	8	9	10	11	12	13	14
SIG. HT (M.)	0.9	2.8	3.4	2.6	2.1	0.9	1.6
DATE (MAY)	15	16	17	18	19	20	21
SIG. HT (M.)	1.8	1.7	1.0	1.9	2.1	1.9	1.4
DATE (MAY)	22	23	24	25	26	27	28
SIG. HT (M.)	1.2	1.2	1.2	1.6	1.8	1.4	1.1
DATE (MAY)	29	30	31				
SIG. HT (M.)	1.4	2.2	1.9				

HUMBOLDT BAY BUOY (INNER)
JUL 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.50	0.
1.00	2, 1,
1.50	3, 5, 2, 1, 1, 1,
2.00	13, 6, 1, 1, 2,
2.50	13, 6, 1, 2,
3.00	13, 6, 4, 3,
3.50	13, 6, 5, 3,
4.00	13, 6, 9,
4.50	13, 6, 9,
5.00	13, 6, 9,
5.50	13, 6, 9,
6.00	13, 6, 9,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR JUN 1981

DATE (JUN)	1	2	3	4	5	6	7
SIG. HT (M.)	1.5	0.9	1.0	1.6	1.6	2.0	1.7
DATE (JUN)	8	9	10	11	12	13	14
SIG. HT (M.)	1.7	1.3	1.3	1.1	1.2	1.2	0.0
DATE (JUN)	15	16	17	18	19	20	21
SIG. HT (M.)	0.9	1.3	1.9	1.6	1.4	1.6	0.0
DATE (JUN)	22	23	24	25	26	27	28
SIG. HT (M.)	1.5	2.8	2.1	1.9	3.4	3.7	2.7
DATE (JUN)	29	30	31				
SIG. HT (M.)	2.0	1.0	0.0				

HUMBOLDT BAY BUOY (INNER)
JUL 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	0,
1.5	1, 1,
2.0	4, 1, 2,
2.5	4, 4, 4, 2, 1,
3.0	11, 8, 7,
3.5	12, 10, 7,
4.0	12, 10, 7,
4.5	12, 10, 7,
5.0	12, 10, 7,
5.5	12, 10, 7,
6.0	12, 10, 7,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR JUL 1981

DATE (JUL)	1	2	3	4	5	6	7
SIG. HT (M.)	3.0	2.5	1.2	0.8	1.2	1.4	2.1
DATE (JUL)	8	9	10	11	12	13	14
SIG. HT (M.)	2.2	0.8	1.6	1.8	1.6	0.0	2.1
DATE (JUL)	15	16	17	18	19	20	21
SIG. HT (M.)	2.2	1.8	1.4	1.1	1.6	2.1	2.2
DATE (JUL)	22	23	24	25	26	27	28
SIG. HT (M.)	2.5	2.9	0.0	2.3	2.2	1.7	1.7
DATE (JUL)	29	30	31				
SIG. HT (M.)	2.1	2.1	1.9				

HUMBOLDT BAY BUOY (INNER)
AUG 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	0,
1.5	3, 6,
2.0	5, 7, 2, 1,
2.5	7, 3, 9, 3, 1,
3.0	31,
3.5	31,
4.0	31,
4.5	31,
5.0	31,
5.5	31,
6.0	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR AUG 1981

DATE (AUG)	1	2	3	4	5	6	7
SIG. HT (M.)	1.1	0.8	0.7	0.8	1.4	1.6	1.8
DATE (AUG)	8	9	10	11	12	13	14
SIG. HT (M.)	2.2	1.8	1.7	1.8	2.3	2.2	1.7
DATE (AUG)	15	16	17	18	19	20	21
SIG. HT (M.)	1.4	0.8	0.7	0.9	0.9	0.7	0.7
DATE (AUG)	22	23	24	25	26	27	28
SIG. HT (M.)	1.6	2.3	1.7	1.4	1.4	2.4	2.2
DATE (AUG)	29	30	31				
SIG. HT (M.)	1.3	2.1	2.3				

HUMBOLDT BAY BUOY (INNER)
OCT 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0.
1.0	1, 2.
1.5	1, 6, 1.
2.0	3, 10, 3, 2.
2.5	4, 16, 2, 1.
3.0	6, 16, 3, 1.
3.5	6, 16, 3, 2.
4.0	6, 16, 6.
4.5	24, 6.
5.0	24, 6.
5.5	24, 6.
6.0	24, 6.

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR OCT 1981

DATE (OCT)	1	2	3	4	5	6	7
SIG. HT (M.)	2.5	2.2	1.8	1.7	1.3	2.9	4.3
DATE (OCT)	8	9	10	11	12	13	14
SIG. HT (M.)	4.2	2.2	2.4	1.8	1.7	1.7	1.4
DATE (OCT)	15	16	17	18	19	20	21
SIG. HT (M.)	0.9	1.1	1.0	0.8	1.0	1.8	2.1
DATE (OCT)	22	23	24	25	26	27	28
SIG. HT (M.)	1.6	1.3	1.5	0.0	1.8	1.6	2.8
DATE (OCT)	29	30	31				
SIG. HT (M.)	3.8	3.1	2.3				

HUMBOLDT BAY BUOY (INNER)
NOV 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS			
0.5	0,			
1.0	0,			
1.5	2,			
2.0	1,	3,		
2.5	3,	5,	1,	1,
3.0	9,	1,	2,	1,
3.5	9,	6,	2,	
4.0	11,	7,	2,	
4.5	13,	8,	2,	
5.0	13,	11,		
5.5	13,	11,		
6.0	13,	11,		

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR NOV 1981

DATE (NOV)	1	2	3	4	5	6	7
SIG. HT (M.)	2.3	1.9	2.3	3.0	2.1	2.1	1.8
DATE (NOV)	8	9	10	11	12	13	14
SIG. HT (M.)	1.4	1.1	3.7	4.0	4.5	4.4	7.1
DATE (NOV)	15	16	17	18	19	20	21
SIG. HT (M.)	3.6	2.8	3.1	2.9	2.4	3.5	2.5
DATE (NOV)	22	23	24	25	26	27	28
SIG. HT (M.)	4.2	4.8	3.4	2.4	0.0	0.0	0.0
DATE (NOV)	29	30	31				
SIG. HT (M.)	0.0	0.0	0.0				

HUMBOLDT BAY BUOY (INNER)
JAN 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0.
1.0	0.
1.5	1, 1,
2.0	4,
2.5	5,
3.0	5, 1, 3,
3.5	5, 1, 4, 3,
4.0	5, 6, 1, 3,
4.5	5, 7, 5,
5.0	20,
5.5	20,
6.0	20,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR JAN 1982

DATE (JAN)	1	2	3	4	5	6	7
SIG. HT (M.)	(0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (JAN)	8	9	10	11	12	13	14
SIG. HT (M.)	0.0	0.0	0.0	0.0)	2.2	1.9	1.5
DATE (JAN)	15	16	17	18	19	20	21
SIG. HT (M.)	1.6	1.1	4.8	4.5	4.1	2.5	4.0
DATE (JAN)	22	23	24	25	26	27	28
SIG. HT (M.)	3.0	2.5	2.9	3.4	4.8	3.7	4.3
DATE (JAN)	29	30	31				
SIG. HT (M.)	3.3	3.3	3.3				

HUMBOLDT BAY BUOY (INNER)
FEB 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	0,
1.5	2,
2.0	3,
2.5	1, 3,
3.0	6,
3.5	7,
4.0	7,
4.5	7,
5.0	7,
5.5	7,
6.0	7,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR FEB 1982

DATE (FEB)	1	2	3	4	5	6	7
SIG. HT (M.)	3.2	2.6	2.0	2.9	1.8	1.4	1.2
DATE (FEB)	8	9	10	11	12	13	14
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (FEB)	15	16	17	18	19	20	21
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (FEB)	22	23	24	25	26	27	28
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (FEB)	29	30	31				
SIG. HT (M.)	0.0	0.0	0.0				

HUMBOLDT BAY BUOY (INNER)
MAR 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	0,
1.5	1, 1,
2.0	2, 1, 1,
2.5	2, 5,
3.0	2, 1, 1, 2, 5,
3.5	5, 4, 8, 1,
4.0	5, 5, 9, 1,
4.5	11, 9, 1,
5.0	11, 11,
5.5	11, 11,
6.0	11, 11,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAR 1982

DATE (MAR)	1	2	3	4	5	6	7
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (MAR)	8	9	10	11	12	13	14
SIG. HT (M.)	0.0	1.5	1.6	3.1	2.7	3.3	4.1
DATE (MAR)	15	16	17	18	19	20	21
SIG. HT (M.)	3.7	2.5	3.3	3.0	2.6	0.0	1.4
DATE (MAR)	22	23	24	25	26	27	28
SIG. HT (M.)	2.2	2.2	2.3	2.0	3.4	3.1	3.1
DATE (MAR)	29	30	31				
SIG. HT (M.)	3.7	4.6	3.1				

HUMBOLDT BAY BUOY (INNER)
APR 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	1, 1,
1.5	2, 2, 2,
2.0	3, 1, 8,
2.5	1, 1, 4, 2, 11,
3.0	1, 9, 2, 11,
3.5	1, 10, 3, 12,
4.0	1, 10, 16,
4.5	1, 27,
5.0	30,
5.5	30,
6.0	30,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR APR 1982

DATE (APR)	1	2	3	4	5	6	7
SIG. HT (M.)	2.3	4.9	4.9	2.4	2.7	2.9	2.1

DATE (APR)	8	9	10	11	12	13	14
SIG. HT (M.)	1.0	1.4	1.7	2.9	2.7	3.4	4.1

DATE (APR)	15	16	17	18	19	20	21
SIG. HT (M.)	3.1	2.3	1.6	3.5	3.1	1.3	1.1

DATE (APR)	22	23	24	25	26	27	28
SIG. HT (M.)	1.8	1.7	1.8	1.7	1.4	0.9	2.3

DATE (APR)	29	30	31
SIG. HT (M.)	2.4	2.2	0.0

HUMBOLDT BAY BUOY (INNER)
MAY 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	0,
1.0	1, 1,
1.5	1, 5,
2.0	2, 1, 8, 1, 1,
2.5	2, 2, 8, 3, 1, 4,
3.0	2, 13, 4, 1, 4,
3.5	3, 20, 6,
4.0	31,
4.5	31,
5.0	31,
5.5	31,
6.0	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAY 1982

DATE (MAY)	1	2	3	4	5	6	7
SIG. HT (M.)	1.5	1.5	3.3	3.5	2.9	1.8	2.5
DATE (MAY)	8	9	10	11	12	13	14
SIG. HT (M.)	2.9	1.9	1.9	1.9	1.1	1.1	0.8
DATE (MAY)	15	16	17	18	19	20	21
SIG. HT (M.)	1.2	0.9	2.8	3.1	2.6	1.6	2.1
DATE (MAY)	22	23	24	25	26	27	28
SIG. HT (M.)	2.1	3.0	2.4	4.0	3.3	3.2	2.4
DATE (MAY)	29	30	31				
SIG. HT (M.)	2.4	2.0	1.6				

HUMBOLDT COAST GUARD
NOV 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	3, 3, 4,
1.0	13,
1.5	13,
2.0	13,
2.5	13,
3.0	13,
3.5	13,
4.0	13,
4.5	13,
5.0	13,
5.5	13,
6.0	13,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR NOV 1981

DATE (NOV)	1	2	3	4	5	6	7
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DATE (NOV)	8	9	10	11	12	13	14
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DATE (NOV)	15	16	17	18	19	20	21
SIG. HT (M.)	0.0	0.0	0.0	0.3	0.4	0.3	0.6

DATE (NOV)	22	23	24	25	26	27	28
SIG. HT (M.)	0.6	0.3	0.3	0.5	0.5	0.3	0.4

DATE (NOV)	29	30	31
SIG. HT (M.)	0.4	0.4	0.0

HUMBOLDT COAST GUARD
DEC 1981

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	23, 7,
1.0	31,
1.5	31,
2.0	31,
2.5	31,
3.0	31,
3.5	31,
4.0	31,
4.5	31,
5.0	31,
5.5	31,
6.0	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR DEC 1981

DATE (DEC)	1	2	3	4	5	6	7
SIG. HT (M.)	0.4	0.4	0.4	0.5	0.4	0.4	0.4
DATE (DEC)	8	9	10	11	12	13	14
SIG. HT (M.)	0.3	0.3	0.2	0.3	0.4	0.5	0.5
DATE (DEC)	15	16	17	18	19	20	21
SIG. HT (M.)	0.4	0.1	0.4	0.3	0.3	0.4	0.2
DATE (DEC)	22	23	24	25	26	27	28
SIG. HT (M.)	0.1	0.3	0.7	0.4	0.4	0.3	0.3
DATE (DEC)	29	30	31				
SIG. HT (M.)	0.2	0.2	0.3				

HUMBOLDT COAST GUARD
JAN 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	31,
1.0	31,
1.5	31,
2.0	31,
2.5	31,
3.0	31,
3.5	31,
4.0	31,
4.5	31,
5.0	31,
5.5	31,
6.0	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR JAN 1982

DATE (JAN)	1	2	3	4	5	6	7
SIG. HT (M.)	0.5	0.3	0.2	0.2	0.2	0.2	0.2

DATE (JAN)	8	9	10	11	12	13	14
SIG. HT (M.)	0.2	0.3	0.2	0.2	0.2	0.2	0.2

DATE (JAN)	15	16	17	18	19	20	21
SIG. HT (M.)	0.1	0.4	0.5	0.5	0.4	0.4	0.4

DATE (JAN)	22	23	24	25	26	27	28
SIG. HT (M.)	0.2	0.3	0.3	0.5	0.4	0.5	0.4

DATE (JAN)	29	30	31
SIG. HT (M.)	0.4	0.4	0.3

HUMBOLDT COAST GUARD
FEB 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	28,
1.0	28,
1.5	28,
2.0	28,
2.5	28,
3.0	28,
3.5	28,
4.0	28,
4.5	28,
5.0	28,
5.5	28,
6.0	28,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR FEB 1982

DATE (FEB)	1	2	3	4	5	6	7
SIG. HT (M.)	0.2	0.2	0.3	0.3	0.2	0.3	0.2
DATE (FEB)	8	9	10	11	12	13	14
SIG. HT (M.)	0.2	0.1	0.1	0.2	0.2	0.2	0.2
DATE (FEB)	15	16	17	18	19	20	21
SIG. HT (M.)	0.2	0.2	0.2	0.2	0.4	0.3	0.4
DATE (FEB)	22	23	24	25	26	27	28
SIG. HT (M.)	0.3	0.3	0.2	0.1	0.2	0.2	0.2
DATE (FEB)	29	30	31				
SIG. HT (M.)	0.0	0.0	0.0				

HUMBOLDT COAST GUARD
MAY 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	13,
1.0	13,
1.5	13,
2.0	13,
2.5	13,
3.0	13,
3.5	13,
4.0	13,
4.5	13,
5.0	13,
5.5	13,
6.0	13,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAY 1982

DATE (MAY)	1	2	3	4	5	6	7
SIG. HT (M.)	0.3	0.1	0.3	0.3	0.4	0.4	0.2
DATE (MAY)	8	9	10	11	12	13	14
SIG. HT (M.)	0.3	0.4	0.5	0.1	0.2	0.0	0.0
DATE (MAY)	15	16	17	18	19	20	21
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (MAY)	22	23	24	25	26	27	28
SIG. HT (M.)	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DATE (MAY)	29	30	31				
SIG. HT (M.)	0.0	0.0	0.0				

HUMBOLDT COAST GUARD
APR 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	30.
1.0	30.
1.5	30.
2.0	30.
2.5	30.
3.0	30.
3.5	30.
4.0	30.
4.5	30.
5.0	30.
5.5	30.
6.0	30.

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR APR 1982

DATE (APR)	1	2	3	4	5	6	7
SIG. HT (M.)	0.4	0.2	0.2	0.2	0.2	0.2	0.2
DATE (APR)	8	9	10	11	12	13	14
SIG. HT (M.)	0.1	0.2	0.1	0.1	0.2	0.2	0.2
DATE (APR)	15	16	17	18	19	20	21
SIG. HT (M.)	0.2	0.1	0.2	0.2	0.1	0.2	0.3
DATE (APR)	22	23	24	25	26	27	28
SIG. HT (M.)	0.4	0.2	0.4	0.2	0.3	0.2	0.4
DATE (APR)	29	30	31				
SIG. HT (M.)	0.3	0.3	0.0				

HUMBOLDT COAST GUARD
MAR 1982

PERSISTENCE
CONSECUTIVE DAYS (1 OR MORE) SIGNIFICANT
WAVE HEIGHT IS -N- METERS OR LESS

METERS	DAYS
0.5	12, 11, 6,
1.0	31,
1.5	31,
2.0	31,
2.5	31,
3.0	31,
3.5	31,
4.0	31,
4.5	31,
5.0	31,
5.5	31,
6.0	31,

MAXIMUM DAILY SIGNIFICANT WAVE HEIGHT FOR MAR 1982

DATE (MAR)	1	2	3	4	5	6	7
SIG. HT (M.)	0.4	0.5	0.3	0.1	0.2	0.2	0.2

DATE (MAR)	8	9	10	11	12	13	14
SIG. HT (M.)	0.3	0.2	0.2	0.4	0.4	0.8	0.5

DATE (MAR)	15	16	17	18	19	20	21
SIG. HT (M.)	0.3	0.4	0.4	0.4	0.4	0.2	0.2

DATE (MAR)	22	23	24	25	26	27	28
SIG. HT (M.)	0.3	0.3	0.3	0.5	0.5	0.4	0.4

DATE (MAR)	29	30	31
SIG. HT (M.)	0.5	0.2	0.2

TABLE 19

HUMBOLDT BAY BUOY (INNER) MAR-DEC 1980

CUMULATIVE HEIGHT PROBABILITIES

HEIGHT (CM)	PROBABILITY	OCCURRENCE (HRS)
✓ 295	0. 1236	1083
285	0. 1453	1272
275	0. 1693	1482
265	0. 1921	1682
255	0. 2377	2082
245	0. 2713	2376
235	0. 3217	2818
225	0. 3649	3196
215	0. 4106	3596
205	0. 4562	3996
195	0. 4982	4364
185	0. 5534	4847
175	0. 5954	5216
165	0. 6387	5594
155	0. 6819	5973
145	0. 7395	6477
135	0. 7791	6825
125	0. 8223	7203
115	0. 8523	7466
105	0. 9004	7887
95	0. 9220	8076
85	0. 9424	8255
75	0. 9712	8507
65	0. 9880	8654
55	0. 9964	8728
45	0. 9988	8749
35	0. 9988	8749
25	0. 9988	8749
15	0. 9988	8749
5	0. 9988	8749

CUMULATIVE PEAK PERIOD PROBABILITIES

PERIOD (SEC)	PROBABILITY	OCCURRENCE (HRS)
22+	0. 0048	42
20	0. 0084	73
17	0. 0276	241
15	0. 0768	673
13	0. 1849	1619
11	0. 3782	3312
9	0. 7071	6194
7	0. 9520	8339
5	0. 9988	8749

TABLE 20

HUMBOLDT BAY BUOY(OUTER) MAR-APR 1980

CUMULATIVE HEIGHT PROBABILITIES

HEIGHT (CM)	PROBABILITY	OCCURRENCE (HRS)
295	0. 3333	2919
285	0. 4222	3698
275	0. 5333	4671
265	0. 6000	5255
255	0. 6667	5839
245	0. 6667	5839
235	0. 7333	6423
225	0. 7333	6423
215	0. 7556	6618
205	0. 7778	6813
195	0. 8222	7202
185	0. 8222	7202
175	0. 8444	7397
165	0. 8667	7591
155	0. 8667	7591
145	0. 9111	7981
135	0. 9333	8175
125	0. 9556	8370
115	0. 9556	8370
105	0. 9778	8565
95	0. 9778	8565
85	0. 9778	8565
75	0. 9778	8565
65	0. 9778	8565
55	0. 9778	8565
45	0. 9778	8565
35	0. 9778	8565
25	0. 9778	8565
15	0. 9778	8565
5	0. 9778	8565

CUMULATIVE PEAK PERIOD PROBABILITIES

PERIOD (SEC)	PROBABILITY	OCCURRENCE (HRS)
22+	0. 0000	<12
20	0. 0000	<12
17	0. 0667	583
15	0. 1778	1557
13	0. 5111	4477
11	0. 6000	5255
9	0. 6889	6034
7	0. 9333	8175
5	0. 9778	8565

AD-A189 838

BUNNE POINT SHORELINE EROSION DEMONSTRATION PROJECT
VOLUME 2 APPENDICES E(U) ARMY ENGINEER DISTRICT LOS
ANGELES CA AUG 87


2/3

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

TABLE 22.

HUMBOLDT BAY BUOY (INNER) JAN-NOV 1981

CUMULATIVE HEIGHT PROBABILITIES

HEIGHT (CM)	PROBABILITY	OCCURRENCE (HRS)
900	0.0000	<12
870	0.0000	<12
840	0.0000	<12
810	0.0000	<12
780	0.0000	<12
750	0.0000	<12
720	0.0018	15
690	0.0018	15
660	0.0018	15
630	0.0018	15
600	0.0018	15
570	0.0018	15
540	0.0027	23
510	0.0053	46
480	0.0062	54
450	0.0133	116
420	0.0283	247
390	0.0469	410
360	0.0760	666
330	0.1061	929
300	0.1574	1378
270	0.2219	1944
240	0.3271	2865
210	0.4500	3942
180	0.6118	5359
150	0.7675	6722
120	0.8798	7706
90	0.9841	8620
60	0.9991	8752
30	0.9991	8752

CUMULATIVE PEAK PERIOD PROBABILITIES

PERIOD (SEC)	PROBABILITY	OCCURRENCE (HRS)
22+	0.0000	<12
20	0.0062	54
17	0.0407	356
15	0.0937	821
13	0.2042	1789
11	0.3820	3345
9	0.7065	6188
7	0.9496	8310
5	0.9991	8752

TABLE 23.

HUMBOLDT BAY BUOY (OUTER) JAN-JUN 1981

CUMULATIVE HEIGHT PROBABILITIES


HEIGHT (CM)	PROBABILITY	OCCURRENCE (HRS)
900	0.0000	<12
870	0.0000	<12
840	0.0000	<12
810	0.0000	<12
780	0.0000	<12
750	0.0000	<12
720	0.0000	<12
690	0.0000	<12
660	0.0034	29
630	0.0034	29
600	0.0068	59
570	0.0102	89
540	0.0137	119
510	0.0239	209
480	0.0307	269
450	0.0751	657
420	0.1092	956
390	0.1741	1524
360	0.2662	2332
330	0.3345	2929
300	0.4164	3647
270	0.5119	4484
240	0.6075	5321
210	0.6962	6099
180	0.7850	6876
150	0.8464	7414
120	0.9352	8191
90	0.9966	8730
60	0.9966	8730
30	0.9966	8730

CUMULATIVE PEAK PERIOD PROBABILITIES

PERIOD (SEC)	PROBABILITY	OCCURRENCE (HRS)
22+	0.0034	29
20	0.0171	149
17	0.0853	747
15	0.1980	1734
13	0.3652	3199
11	0.6519	5710
9	0.8396	7354
7	0.9693	8490
5	0.9966	8730


Deep Water WAVE STATISTICS for the California Coast

Station 2











STATION 2
METEOROLOGICAL INTERPOLATION

OFFICE OF CALIFORNIA
WATER RESOURCES BOARD
DEPARTMENT OF NAVIGATION
AND OCEAN DEVELOPMENT



2-III-2









Figure III. 1
 FREQUENCY DISTRIBUTION ROSE
 1951 - 1974
 STATION 2
 (39.6N 124.5W)
 COMBINED SEA/SWELL



2-III-4

STATION 2 WAVE HEIGHT DURATION GRAPH 1946-1974 COMBINED SEA/SWELL HEIGHT¹



* DATA NOT AVAILABLE
1 TIME INTERVAL = 24 HRS

Figure III. 2

— — — — —

EXTREME WAVE EVENT LISTING

COMBINED SEA/SWELL ~ 5 METERS
COMPILED FROM ONCE-DAILY WAVE COMPUTATIONS
1951-1974

CHRONOLOGICAL ORDERING			WAVE HEIGHT ORDERING			PERIOD ORDERING		
DATA	WEIGHT	PERIOD DIRECTION	DATA	WEIGHT	PERIOD DIRECTION	DATA	WEIGHT	PERIOD DIRECTION
18 NOV 51	5	10	22 DEC 64	10	0	15 FEB 69	5	1
19 NOV 51	5	10	23 JAN 72	8	9	20 DEC 64	10	0
20 NOV 51	5	10	24 JAN 74	8	9	21 JAN 72	8	9
21 NOV 51	5	10	25 FEB 69	5	1	22 JAN 74	8	9
22 NOV 51	5	10	26 FEB 69	5	1	23 JAN 74	8	9
23 NOV 51	5	10	27 FEB 69	5	1	24 JAN 71	7	8
24 NOV 51	5	10	28 FEB 69	5	1	25 JAN 71	7	8
25 NOV 51	5	10	29 FEB 69	5	1	26 MAR 72	5	5
26 NOV 51	5	10	30 FEB 69	5	1	27 DEC 72	7	9
27 NOV 51	5	10	31 FEB 69	5	1	28 DEC 72	7	9
28 NOV 51	5	10	01 MAR 71	7	8	29 JAN 74	8	9
29 NOV 51	5	10	02 JAN 71	7	8	30 JAN 74	8	9
30 NOV 51	5	10	03 JAN 72	7	7	31 FEB 72	5	5
31 NOV 51	5	10	04 JAN 68	7	7	01 FEB 74	7	7
32 NOV 51	5	10	05 FEB 68	7	7	02 FEB 74	7	7
33 NOV 51	5	10	06 FEB 68	7	7	03 FEB 74	7	7
34 NOV 51	5	10	07 FEB 68	7	7	04 FEB 74	7	7
35 NOV 51	5	10	08 FEB 68	7	7	05 FEB 74	7	7
36 NOV 51	5	10	09 FEB 68	7	7	06 FEB 74	7	7
37 NOV 51	5	10	10 FEB 68	7	7	07 FEB 74	7	7
38 NOV 51	5	10	11 FEB 68	7	7	08 JAN 73	6	3
39 NOV 51	5	10	12 FEB 68	7	7	09 JAN 73	6	3
40 NOV 51	5	10	13 FEB 68	7	7	20 JAN 73	6	3
41 NOV 51	5	10	14 FEB 68	7	7	21 FEB 56	6	3
42 NOV 51	5	10	15 FEB 68	7	7	22 JAN 58	6	4
43 NOV 51	5	10	16 FEB 68	7	7	23 JAN 58	6	4
44 NOV 51	5	10	17 FEB 68	7	7	24 JAN 58	6	4
45 NOV 51	5	10	18 FEB 68	7	7	25 JAN 58	6	4
46 NOV 51	5	10	19 FEB 68	7	7	26 JAN 58	6	4
47 NOV 51	5	10	20 FEB 68	7	7	27 JAN 58	6	4
48 NOV 51	5	10	21 FEB 68	7	7	28 JAN 58	6	4
49 NOV 51	5	10	22 FEB 68	7	7	29 JAN 58	6	4
50 NOV 51	5	10	23 FEB 68	7	7	30 JAN 58	6	4
51 NOV 51	5	10	24 FEB 68	7	7	31 JAN 58	6	4
52 NOV 51	5	10	25 FEB 68	7	7	01 JAN 58	6	4
53 NOV 51	5	10	26 FEB 68	7	7	02 JAN 58	6	4
54 NOV 51	5	10	27 FEB 68	7	7	03 JAN 58	6	4
55 NOV 51	5	10	28 FEB 68	7	7	04 JAN 58	6	4
56 NOV 51	5	10	29 FEB 68	7	7	05 JAN 58	6	4
57 NOV 51	5	10	30 FEB 68	7	7	06 JAN 58	6	4
58 NOV 51	5	10	31 FEB 68	7	7	07 JAN 58	6	4
59 NOV 51	5	10	01 MAR 68	7	7	08 JAN 58	6	4
60 NOV 51	5	10	02 MAR 68	7	7	09 JAN 58	6	4
61 NOV 51	5	10	03 MAR 68	7	7	10 JAN 58	6	4
62 NOV 51	5	10	04 MAR 68	7	7	11 JAN 58	6	4
63 NOV 51	5	10	05 MAR 68	7	7	12 JAN 58	6	4
64 NOV 51	5	10	06 MAR 68	7	7	13 JAN 58	6	4
65 NOV 51	5	10	07 MAR 68	7	7	14 JAN 58	6	4
66 NOV 51	5	10	08 MAR 68	7	7	15 JAN 58	6	4
67 NOV 51	5	10	09 MAR 68	7	7	16 JAN 58	6	4
68 NOV 51	5	10	10 MAR 68	7	7	17 JAN 58	6	4
69 NOV 51	5	10	11 MAR 68	7	7	18 JAN 58	6	4
70 NOV 51	5	10	12 MAR 68	7	7	19 JAN 58	6	4
71 NOV 51	5	10	13 MAR 68	7	7	20 JAN 58	6	4
72 NOV 51	5	10	14 MAR 68	7	7	21 JAN 58	6	4
73 NOV 51	5	10	15 MAR 68	7	7	22 JAN 58	6	4
74 NOV 51	5	10	16 MAR 68	7	7	23 JAN 58	6	4
75 NOV 51	5	10	17 MAR 68	7	7	24 JAN 58	6	4
76 NOV 51	5	10	18 MAR 68	7	7	25 JAN 58	6	4
77 NOV 51	5	10	19 MAR 68	7	7	26 JAN 58	6	4
78 NOV 51	5	10	20 MAR 68	7	7	27 JAN 58	6	4
79 NOV 51	5	10	21 MAR 68	7	7	28 JAN 58	6	4
80 NOV 51	5	10	22 MAR 68	7	7	29 JAN 58	6	4
81 NOV 51	5	10	23 MAR 68	7	7	30 JAN 58	6	4
82 NOV 51	5	10	24 MAR 68	7	7	31 JAN 58	6	4
83 NOV 51	5	10	25 MAR 68	7	7	01 JAN 58	6	4
84 NOV 51	5	10	26 MAR 68	7	7	02 JAN 58	6	4
85 NOV 51	5	10	27 MAR 68	7	7	03 JAN 58	6	4
86 NOV 51	5	10	28 MAR 68	7	7	04 JAN 58	6	4
87 NOV 51	5	10	29 MAR 68	7	7	05 JAN 58	6	4
88 NOV 51	5	10	30 MAR 68	7	7	06 JAN 58	6	4
89 NOV 51	5	10	31 MAR 68	7	7	07 JAN 58	6	4
90 NOV 51	5	10	01 APR 68	7	7	08 JAN 58	6	4
91 NOV 51	5	10	02 APR 68	7	7	09 JAN 58	6	4
92 NOV 51	5	10	03 APR 68	7	7	10 JAN 58	6	4
93 NOV 51	5	10	04 APR 68	7	7	11 JAN 58	6	4
94 NOV 51	5	10	05 APR 68	7	7	12 JAN 58	6	4
95 NOV 51	5	10	06 APR 68	7	7	13 JAN 58	6	4
96 NOV 51	5	10	07 APR 68	7	7	14 JAN 58	6	4
97 NOV 51	5	10	08 APR 68	7	7	15 JAN 58	6	4
98 NOV 51	5	10	09 APR 68	7	7	16 JAN 58	6	4
99 NOV 51	5	10	10 APR 68	7	7	17 JAN 58	6	4
100 NOV 51	5	10	11 APR 68	7	7	18 JAN 58	6	4
101 NOV 51	5	10	12 APR 68	7	7	19 JAN 58	6	4
102 NOV 51	5	10	13 APR 68	7	7	20 JAN 58	6	4
103 NOV 51	5	10	14 APR 68	7	7	21 JAN 58	6	4
104 NOV 51	5	10	15 APR 68	7	7	22 JAN 58	6	4
105 NOV 51	5	10	16 APR 68	7	7	23 JAN 58	6	4
106 NOV 51	5	10	17 APR 68	7	7	24 JAN 58	6	4
107 NOV 51	5	10	18 APR 68	7	7	25 JAN 58	6	4
108 NOV 51	5	10	19 APR 68	7	7	26 JAN 58	6	4
109 NOV 51	5	10	20 APR 68	7	7	27 JAN 58	6	4
110 NOV 51	5	10	21 APR 68	7	7	28 JAN 58	6	4
111 NOV 51	5	10	22 APR 68	7	7	29 JAN 58	6	4
112 NOV 51	5	10	23 APR 68	7	7	30 JAN 58	6	4
113 NOV 51	5	10	24 APR 68	7	7	31 JAN 58	6	4
114 NOV 51	5	10	25 APR 68	7	7	01 JAN 58	6	4
115 NOV 51	5	10	26 APR 68	7	7	02 JAN 58	6	4
116 NOV 51	5	10	27 APR 68	7	7	03 JAN 58	6	4
117 NOV 51	5	10	28 APR 68	7	7	04 JAN 58	6	4
118 NOV 51	5	10	29 APR 68	7	7	05 JAN 58	6	4
119 NOV 51	5	10	30 APR 68	7	7	06 JAN 58	6	4
120 NOV 51	5	10	31 APR 68	7	7	07 JAN 58	6	4
121 NOV 51	5	10	01 MAY 68	7	7	08 JAN 58	6	4
122 NOV 51	5	10	02 MAY 68	7	7	09 JAN 58	6	4
123 NOV 51	5	10	03 MAY 68	7	7	10 JAN 58	6	4
124 NOV 51	5	10	04 MAY 68	7	7	11 JAN 58	6	4
125 NOV 51	5	10	05 MAY 68	7	7	12 JAN 58	6	4
126 NOV 51	5	10	06 MAY 68	7	7	13 JAN 58	6	4
127 NOV 51	5	10	07 MAY 68	7	7	14 JAN 58	6	4
128 NOV 51	5	10	08 MAY 68	7	7	15 JAN 58	6	4
129 NOV 51	5	10	09 MAY 68	7	7	16 JAN 58	6	4
130 NOV 51	5	10	10 MAY 68	7	7	17 JAN 58	6	4
131 NOV 51	5	10	11 MAY 68	7	7	18 JAN 58	6	4
132 NOV 51	5	10	12 MAY 68	7	7	19 JAN 58	6	4
133 NOV 51	5	10	13 MAY 68	7	7	20 JAN 58	6	4
134 NOV 51	5	10	14 MAY 68	7	7	21 JAN 58	6	4
135 NOV 51	5	10	15 MAY 68	7	7	22 JAN 58	6	4
136 NOV 51	5	10	16 MAY 68	7	7	23 JAN 58	6	4
137 NOV 51	5	10	17 MAY 68	7	7	24 JAN 58	6	4
138 NOV 51	5	10	18 MAY 68	7	7	25 JAN 58	6	4
139 NOV 51	5	10	19 MAY 68	7	7	26 JAN 58	6	4
140 NOV 51	5	10	20 MAY 68	7	7	27 JAN 58	6	4
141 NOV 51	5	10	21 MAY 68	7	7	28 JAN 58	6	4
142 NOV 51	5	10	22 MAY 68	7	7	29 JAN 58	6	4
143 NOV 51	5	10	23 MAY 68	7	7	30 JAN 58	6	4
144 NOV 51	5	10	24 MAY 68	7	7	31 JAN 58	6	4
145 NOV 51	5	10	25 MAY 68	7	7	01 JAN 58	6	4
146 NOV 51	5	10	26 MAY 68	7	7	02 JAN 58	6	4
147 NOV 51	5	10	27 MAY 68	7	7	03 JAN 58	6	4
148 NOV 51	5	10	28 MAY 68	7	7	04 JAN 58	6	4
149 NOV 51	5	10	29 MAY 68	7	7	05 JAN 58	6	4
150 NOV 51	5	10	30 MAY 68	7	7	06 JAN 58	6	4
151 NOV 51	5	10	31 MAY 68	7	7	07 JAN 58	6	4
152 NOV 51	5	10	01 JUN 68	7	7	08 JAN 58	6	4
153 NOV 51	5	10	02 JUN 68	7	7	09 JAN 58	6	4
154 NOV 51	5	10	03 JUN 68	7	7	10 JAN 58	6	4
155 NOV 51	5	10	04 JUN 68	7	7	11 JAN 58	6	4
156 NOV 51	5	10	05 JUN 68	7	7	12 JAN 58	6	4
157 NOV 51	5	10	06 JUN 68	7	7	13 JAN 58	6	4
158 NOV 51	5	10	07 JUN 68	7	7	14 JAN 58	6	4
159 NOV 51	5	10	08 JUN 68	7	7	15 JAN 58	6	4
160 NOV 51	5	10	09 JUN 68	7	7	16 JAN 58	6	4
161 NOV 51	5	10	10 JUN 68	7	7	17 JAN 58	6	4
162 NOV 51	5	10	11 JUN 68	7	7	18 JAN 58	6	4
163 NOV 51	5	10	12 JUN 68	7	7	19 JAN 58	6	4
164 NOV 51	5	10	13 JUN 68	7	7	20 JAN 58	6	4
165 NOV 51	5	10	14 JUN 68	7	7	21 JAN 58	6	4
166 NOV 51	5	10	15 JUN 68	7	7	22 JAN 58	6	4
167 NOV 51	5	10	16 JUN 68	7	7	23 JAN 58	6	4
168 NOV 51	5	10	17 JUN 68	7	7	24 JAN 58	6	4
169 NOV 51	5	10	18 JUN 68	7	7	25 JAN 58	6	4
170 NOV 51	5	10	19 JUN 68	7	7	26 JAN 58	6	4
171 NOV 51	5	10	20 JUN 68	7	7	27 JAN 58	6	4
172 NOV 51	5	10	21 JUN 68	7	7	28 JAN 58	6	4
173 NOV 51	5	10	22 JUN 68	7	7	29 JAN 58	6	4
174 NOV 51	5	10	23 JUN 68	7	7	30 JAN 58	6	4
175 NOV 51	5	10	24 JUN 68	7	7	31 JAN 58	6	4
176 NOV 51	5	10	25 JUN 68	7	7	01 JAN 58	6	4
177 NOV 51	5	10	26 JUN 68	7	7	02 JAN 58	6	4
178 NOV 51	5	10	27 JUN 68	7	7	03 JAN 58	6	4
179 NOV 51	5	10	28 JUN 68	7	7	04 JAN 58	6	4
180 NOV 51	5	10	29 JUN 68	7	7	05 JAN 58	6	4
181 NOV 51	5	10	30 JUN 68	7	7	06 JAN 58	6	4
182 NOV 51	5	10	31 JUN 68	7	7			

-CONTINUED-

TABLE III (CONT.)

STATION 2 (59 6N 124.5W)									
EXTREME WAVE EVENT LISTING									
COMBINED SEA/SWELL - 5 METERS									
COMPILED FROM ONCE-DAILY WAVE COMPUTATIONS									
1951-1974									
CHRONOLOGICAL ORDERING					WAVE HEIGHT ORDERING				
DATA	HEIGHT	PERIOD	DIRECTION		DATA	HEIGHT	PERIOD	DIRECTION	
19 FEB 81	5.2	10	216		25 FEB 57	6.0	10	197	
19 FEB 81	5.1	10	187		16 JAN 74	6.0	11	204	
19 FEB 81	5.1	12	246		12 DEC 69	5.9	10	201	
19 FEB 81	5.1	12	218		13 DEC 69	5.9	10	184	
21 DEC 84	6.8	12	231		05 DEC 51	5.9	11	301	
22 DEC 84	10.0	15	243		15 DEC 72	5.9	11	189	
23 DEC 84	7.5	11	243		17 DEC 72	5.8	11	192	
23 DEC 84	6.5	11	260		03 DEC 70	5.8	11	208	
23 DEC 84	5.4	11	167		08 FEB 60	5.7	10	214	
14 NOV 85	5.1	11	174		04 DEC 51	5.7	10	211	
27 DEC 85	5.3	10	204		23 OCT 73	5.6	10	244	
04 JAN 86	5.6	10	228		07 FEB 61	5.6	10	238	
24 JAN 86	5.4	10	205		17 FEB 59	5.5	10	199	
24 JAN 86	5.4	10	205		12 MAR 71	5.5	13	248	
27 JAN 87	5.1	9	191		08 JAN 53	5.5	10	226	
02 DEC 87	5.0	12	255		24 JAN 70	5.5	10	226	
03 JAN 88	5.3	10	199		22 DEC 52	5.5	10	191	
12 JAN 88	5.3	10	199		26 JAN 60	5.5	10	187	
12 JAN 88	5.3	12	182		26 JAN 60	5.5	10	187	
14 JAN 88	5.2	10	176		28 FEB 74	5.5	10	212	
14 JAN 88	5.2	10	185		26 JAN 67	5.5	10	205	
13 DEC 88	5.4	10	185		29 DEC 73	5.4	10	262	
23 DEC 88	5.8	11	179		25 DEC 64	5.4	10	262	
24 DEC 88	5.2	11	182		13 DEC 54	5.4	10	180	
13 DEC 89	7.7	12	199		13 DEC 54	5.4	10	159	
13 DEC 89	7.7	12	201		13 MAR 73	5.4	10	345	
13 DEC 89	6.0	10	184		09 JAN 68	5.3	10	199	
13 DEC 89	5.5	10	226		16 DEC 72	5.3	10	184	
24 JAN 70	5.5	10	226						
PERIOD ORDERING					DATA				
HEIGHT	PERIOD	DIRECTION			DATA	HEIGHT	PERIOD	DIRECTION	
5.9	11	216			01 MAR 74	5.9	11	216	
5.9	11	167			13 NOV 85	5.9	11	167	
6.0	11	204			16 JAN 74	6.0	11	204	
6.0	11	219			26 MAR 71	6.0	11	219	
6.8	11	293			24 DEC 84	6.8	11	293	
6.8	11	259			23 JAN 60	6.8	11	259	
6.8	11	172			23 JAN 60	6.8	11	172	
6.0	11	151			20 DEC 60	6.0	11	151	
5.8	11	192			17 DEC 72	5.8	11	192	
5.0	10	173			18 NOV 51	5.0	10	173	
5.4	10	185			03 DEC 68	5.4	10	185	
5.4	10	216			10 FEB 41	5.4	10	216	
5.2	10	204			29 DEC 73	5.2	10	204	
5.2	10	199			27 JAN 54	5.2	10	199	
5.2	10	199			17 FEB 59	5.2	10	199	
5.1	10	185			08 JAN 60	5.1	10	185	
5.1	10	260			25 NOV 51	5.1	10	260	
5.5	10	212			28 FEB 74	5.5	10	212	
5.5	10	184			13 DEC 69	5.5	10	184	
5.3	10	264			20 DEC 76	5.3	10	264	
5.2	10	169			12 DEC 62	5.2	10	169	
5.2	10	189			12 DEC 62	5.2	10	189	
6.0	10	201			12 DEC 69	6.0	10	201	
5.1	10	154			04 DEC 72	5.1	10	154	
5.4	10	154			16 FEB 54	5.4	10	154	

STAT:ON 2
(39 6N 124.5W)

EXTREME WAVE EVENT LISTING
COMBINED SEA/SWELL ~ 5 METERS
COMPILED FROM ONCE-DAILY WAVE COMPUTATIONS
1951-1974

CHRONOLOGICAL ORDERING			WAVE HEIGHT ORDERING			PERIOD ORDERING		
DATA	HEIGHT	PERIOD DIRECTION	DATA	HEIGHT	PERIOD DIRECTION	DATA	HEIGHT	PERIOD DIRECTION
1 DEC 73	5 0	10	27 DEC 65	5 3	10	28 OCT 73	5 0	10
2 DEC 73	5 0	10	12 DEC 62	5 3	10	23 OCT 73	5 0	10
3 DEC 73	5 0	10	12 DEC 62	5 2	10	05 NOV 73	5 1	10
4 DEC 73	5 0	10	12 DEC 62	5 2	10	09 NOV 73	5 1	10
5 DEC 73	5 0	10	12 DEC 62	5 2	10	21 FEB 72	4 0	10
6 DEC 73	5 0	10	12 DEC 62	5 2	10	25 FEB 72	4 0	10
7 DEC 73	5 0	10	14 JAN 68	5 2	10	08 JAN 53	5 5	10
8 DEC 73	5 0	10	30 MAR 74	5 2	10	01 FEB 58	5 5	10
9 DEC 73	5 0	10	04 MAR 72	5 1	10	08 JAN 60	5 5	10
10 DEC 73	5 0	10	14 NOV 65	5 1	10	24 JAN 60	5 5	10
11 DEC 73	5 0	10	14 NOV 65	5 1	10	24 JAN 60	5 5	10
12 DEC 73	5 0	10	19 DEC 55	5 1	10	25 JAN 60	5 5	10
13 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
14 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
15 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
16 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
17 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
18 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
19 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
20 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
21 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
22 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
23 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
24 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
25 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
26 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
27 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
28 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
29 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
30 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
31 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
32 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
33 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
34 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
35 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
36 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
37 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
38 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
39 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
40 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
41 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
42 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
43 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
44 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
45 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
46 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
47 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
48 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
49 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
50 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
51 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
52 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
53 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
54 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
55 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
56 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
57 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
58 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
59 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
60 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
61 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
62 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
63 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
64 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
65 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
66 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
67 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
68 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
69 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
70 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
71 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
72 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
73 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
74 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
75 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
76 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
77 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
78 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
79 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
80 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
81 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
82 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
83 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
84 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
85 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
86 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
87 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
88 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
89 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
90 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
91 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
92 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
93 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
94 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
95 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
96 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
97 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
98 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
99 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10
100 DEC 73	5 0	10	20 DEC 55	5 1	10	26 JAN 60	5 5	10

2. !!! 24

TABLE III 5

-CONTINUED-

Δ78114-161 6-77 500 LDA

K-40

2 1 1 1 85

TABLE III 5

[illegible][illegible][illegible]

COUNTRY	2000 COUNTRIES (12-15-25)					2000 COUNTRIES (12-15-25)					2000 COUNTRIES (12-15-25)					2000 COUNTRIES (12-15-25)				
	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ALGERIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ANDORRA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ANGOLA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ANTIGUA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ARGENTINA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ARMENIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
ARUBA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
AUSTRIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
AZERBAIDJAN	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BAHAMAS	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BAHRAIN	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BALNE	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BANGLADESH	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BARBADO	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BARCELONA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BELARUS	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BELGIUM	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BELIZE	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BENIN	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BERMUDA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BHUTAN	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BOLIVIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BONAI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BOSNIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BOTSWANA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BRUNEI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BULGARIA	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
BURUNDI	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5					

TABLE III 1.13

ALL YEARS (1951-1974) DIRECTION-HEIGHT-PERIOD FREQUENCY OF OCCURRENCE DISTRIBUTION
COMBINED SEASWELL - COUPLED FROM 8727 ORCE-DAILY WAVE COMPUTATIONS

DIRECTION		200 DEGREES (190-200)							190 DEGREES (180-190)							180 DEGREES (170-180)							170 DEGREES (160-170)										
SECONDS	METERS	4	6	8	10	12	14	16	SUM	4	6	8	10	12	14	16	SUM	4	6	8	10	12	14	16	SUM	4	6	8	10	12	14	16	SUM
12	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
13	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
14	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
15	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
16	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
17	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
18	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
19	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
20	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
21	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
22	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
23	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
24	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
25	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
26	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
27	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
28	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
29	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
30	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
31	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
32	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
33	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
34	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12
35	0.5	21	2					34		8	10	12	14	16	18		0	10	12	14	16	18		0	10	12	14	16	18		0	10	12

DIRECTION	10 DEGREES (15-185)			10 DEGREES (185-235)			10 DEGREES (235-300)		
	SECONDS	MINUTES	HOURS	SECONDS	MINUTES	HOURS	SECONDS	MINUTES	HOURS
40	10	12	14	10	12	14	10	12	14
10	10	12	14	10	12	14	10	12	14
12	10	12	14	10	12	14	10	12	14
14	10	12	14	10	12	14	10	12	14
16	10	12	14	10	12	14	10	12	14
18	10	12	14	10	12	14	10	12	14
20	10	12	14	10	12	14	10	12	14
22	10	12	14	10	12	14	10	12	14
24	10	12	14	10	12	14	10	12	14
26	10	12	14	10	12	14	10	12	14
28	10	12	14	10	12	14	10	12	14
30	10	12	14	10	12	14	10	12	14
32	10	12	14	10	12	14	10	12	14
34	10	12	14	10	12	14	10	12	14
36	10	12	14	10	12	14	10	12	14
38	10	12	14	10	12	14	10	12	14
40	10	12	14	10	12	14	10	12	14

1990

THE

SWELL AVERAGE TOTAL HOURS : , . . .

[illegible]

SEA

DIR.	N				NNW				NW				WNW				W				WSW				SW				SSW								
T _h	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12							
H _h	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+							
1-2.9	228	11				33	34	02			58	28				46	02				46	09				5	02				26	02					
3-4.9	27	200	40			91	392	36			87	535	43	02		12	42	02			29	69	05			2	52	02			13	45	04				
5-6.9		120	14				181	23	04			144	52	04			16	02				21	04			02	22	20				17	02				
7-8.9		22	214				11	322	05			08	240	04			04	02				02	30									5	39				
9-10.9			14	05				30	09			36	14																				14				
11-12.9			04	16				14	21				07	22																			07				
13-14.9			02	12				05	12					09																			15				
15-16.9			05						15				02																				05				
17-18.9									01																								12				
19 +																																	24	02			
Σ	255	529	555	38		404	624	532	75		674	715	588	58		10	64	26	02		174	101	41		65	81	48	02	255	216	140	14	58	94	80	56	02

1 Based on 365-1/3 Days


2 Includes waves of 0 to 0.9 feet




(1956, 1957, 1958)

[illegible]

W					WSW					SW					SSW					S					SSE					OFFSHORE	CALC. ²	Σ
12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12	4	6	8	10	12							
+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+	6	8	10	12	+							
	4	09				51	02				42	07				34	02				24	09				47	02		20.78			
	4	09	05			12	57	07			57	11	12			15	45	05			35	04	18			05	46	12		24.06		
		21	02			02	22	02			07	04				12	02				81	05				07	02		792			
		02	10				27				65	05				15	39				7	26				03	37	05		12.28		
							07				04	07	02			22					59	05				24	02		4.00			
						05	02				07	07				12	02				10	15				15	21		2.35			
											07					15					12	12				02			.86			
																05					07	07				02			.43			
																12						14							.33			
																04	02				09	02				02			.19			

B-43





FOR STATION 2

AVERAGE ANNUAL SEA ROSE FOR STATION 2

13-45

APPENDIX C

WIND DATA STATISTICS and SUMMARY

for

HUMBOLDT BAY AREA

SUMMARY OF COMBINED WIND DATA
FROM
EUREKA WEATHER STATION
AND
HUMBOLDT BAY POWER PLANT

DIRECTION	WIND SPEED (Miles per Hour)				PERCENT OF TIME	MEAN WIND SPEED (MPH)
	1-3	4-5	16-31	32-47		
N	1.7	15.5	5.0	-	22.2	12.1
NE	1.6	4.9	0.7	-	7.2	9.2
E	2.0	3.7	0.0	-	5.7	5.9
SE	2.7	8.4	2.0	-	13.1	10.1
S	1.7	8.5	2.8	-	13.0	11.1
SW	1.9	6.9	1.5	-	12.3	10.0
W	1.8	5.7	0.3	-	7.8	9.3
NW	1.9	11.4	1.1	-	14.3	9.3
CALM	-	-	-	-	4.4	9.0
TOTAL	15.2	67.0	13.4	0.0	100.0	

Total Number of Observations 21,122

Data Compiled from records obtained from Eureka, California,
U. S. Weather Bureau Station July 1939 to December 1967 and
Humboldt Bay Power Plant Weather Station, January 1965 to
December 1967.

PERCENTAGE FREQUENCY OF WIND
DIRECTION AND SPEED
(FROM HOURLY OBSERVATIONS)

<u>Eureka, CA WBO</u>	<u>STATION NAME</u>	<u>July 1939 thru December 1942</u>	<u>ALL MONTHS</u>
		<u>TAB A</u>	
	<u>ALL WEATHER</u>		<u>ALL MONTHS (A.M.T.)</u>

SPEED MPH DIR.	1-3	4-15	16-31	32-47	> 47					%	MEAN WIND SPEED
N	1.3	10.4	1.7							13.4	9.5
NNE	0.7	2.3	0.1							3.0	6.7
NE	1.3	2.4								3.7	4.8
NNE	0.6	1.2	0.0							1.8	4.6
E	1.6	1.6								3.2	3.2
ESE	1.3	2.8								4.1	4.9
SE	2.9	6.7	0.3							9.9	6.0
SSE	0.8	5.8	1.0							7.6	9.7
S	1.3	4.6	0.4							6.3	7.8
SSW	0.7	3.9	0.4	0.0						5.0	8.1
SW	1.4	6.2	0.4							8.0	7.6
WSW	0.3	2.2	0.0							3.0	5.7
W	1.0	2.9								3.9	5.8
WNW	0.7	3.5	0.0							4.2	6.2
NW	1.1	7.7	0.2							9.0	7.2
NNW	0.7	7.9	0.9							9.3	9.4
CAUA										4.5	7.1
A 5	18.0	72.1	5.5	0.0						100.0	

DATA FROM NATIONAL CLIMATIC CENTER
FEDERAL BUILDING - ASHEVILLE, N.C., 23801

	TOTAL NUMBER OF OBSERVATIONS	63,771
1980-1981	10,000	
1981-1982	10,000	
1982-1983	10,000	
1983-1984	10,000	
1984-1985	10,000	
1985-1986	10,000	
1986-1987	10,000	
1987-1988	10,000	
1988-1989	10,000	
1989-1990	10,000	
1990-1991	10,000	
1991-1992	10,000	
1992-1993	10,000	
1993-1994	10,000	
1994-1995	10,000	
1995-1996	10,000	
1996-1997	10,000	
1997-1998	10,000	
1998-1999	10,000	
1999-2000	10,000	
2000-2001	10,000	
2001-2002	10,000	
2002-2003	10,000	
2003-2004	10,000	
2004-2005	10,000	
2005-2006	10,000	
2006-2007	10,000	
2007-2008	10,000	
2008-2009	10,000	
2009-2010	10,000	
2010-2011	10,000	
2011-2012	10,000	
2012-2013	10,000	
2013-2014	10,000	
2014-2015	10,000	
2015-2016	10,000	
2016-2017	10,000	
2017-2018	10,000	
2018-2019	10,000	
2019-2020	10,000	
2020-2021	10,000	
2021-2022	10,000	
2022-2023	10,000	
2023-2024	10,000	
2024-2025	10,000	
2025-2026	10,000	
2026-2027	10,000	
2027-2028	10,000	
2028-2029	10,000	
2029-2030	10,000	
2030-2031	10,000	
2031-2032	10,000	
2032-2033	10,000	
2033-2034	10,000	
2034-2035	10,000	
2035-2036	10,000	
2036-2037	10,000	
2037-2038	10,000	
2038-2039	10,000	
2039-2040	10,000	
2040-2041	10,000	
2041-2042	10,000	
2042-2043	10,000	
2043-2044	10,000	
2044-2045	10,000	
2045-2046	10,000	
2046-2047	10,000	
2047-2048	10,000	
2048-2049	10,000	
2049-2050	10,000	
2050-2051	10,000	
2051-2052	10,000	
2052-2053	10,000	
2053-2054	10,000	
2054-2055	10,000	
2055-2056	10,000	
2056-2057	10,000	
2057-2058	10,000	
2058-2059	10,000	
2059-2060	10,000	
2060-2061	10,000	
2061-2062	10,000	
2062-2063	10,000	
2063-2064	10,000	
2064-2065	10,000	
2065-2066	10,000	
2066-2067	10,000	
2067-2068	10,000	
2068-2069	10,000	
2069-2070	10,000	
2070-2071	10,000	
2071-2072	10,000	
2072-2073	10,000	
2073-2074	10,000	
2074-2075	10,000	
2075-2076	10,000	
2076-2077	10,000	
2077-2078	10,000	
2078-2079	10,000	
2079-2080	10,000	
2080-2081	10,000	
2081-2082	10,000	
2082-2083	10,000	
2083-2084	10,000	
2084-2085	10,000	
2085-2086	10,000	
2086-2087	10,000	
2087-2088	10,000	
2088-2089	10,000	
2089-2090	10,000	
2090-2091	10,000	
2091-2092	10,000	
2092-2093	10,000	
2093-2094	10,000	
2094-2095	10,000	
2095-2096	10,0	

SURFACE WINDS

PERCENTAGE FREQUENCY OF WIND
DIRECTION AND SPEED
(FROM HOURLY OBSERVATIONS)

Station Eureka CA, Humboldt Bay P.P. Jan 1966 thru Dec 1967 ALL
 EUREKA NAME ALL WEATHER MONTH
 CLASS 40° 48', 120° 12' ALL
 LOCATION 40° 48', 120° 12' MOSES (1-2, 1-7)

HEIGHT ABOVE GROUND

SPEED MPH Dir.	1-3	4-7	8-12	15-18	19-24	> 25							%	MEAN WIND SPEED
N	0.7	3.7	6.1	4.7	2.2	1.1							18.4	12.7
NNE	0.6	2.1	2.7	1.2	0.3	0.1							6.9	9.6
NE	0.4	1.6	1.2	0.2	0.0								3.5	7.3
ENE	0.4	1.3	0.5	0.1	0.0								2.3	6.2
E	0.6	1.4	0.5	0.0									2.5	5.5
ESE	0.3	1.3	0.7	0.1	0.0	0.0							2.4	6.9
SE	0.2	1.0	0.8	0.9	0.5	0.5							3.9	13.3
ESE	0.3	1.0	1.0	2.1	1.4	0.9							6.7	15.7
S	0.5	1.5	2.1	1.9	0.6	0.2							6.7	11.3
SSW	0.6	1.9	2.3	1.0	0.4	0.2							6.5	10.1
SW	0.7	2.5	2.1	0.9	0.5	0.4							7.2	10.2
WSW	1.0	2.0	1.3	0.5	0.2	0.1							5.1	10.3
W	1.0	2.0	0.9	0.2	0.1	0.0							4.2	6.1
WNW	0.9	1.5	0.7	0.1	0.1	0.0							3.1	6.2
NW	0.9	2.2	1.5	0.3	0.1	0.1							5.0	7.3
NNW	0.7	2.9	3.5	1.8	0.5	0.1							9.6	9.9
CALM													5.9	9.6
5.9	9.9	30.0	27.8	15.9	6.9	3.8							100.0	

TOTAL NUMBER OF OBSERVATIONS 17,351

DATA FROM Pacific Gas and Electric Company

TABLE 1. PERCENT FREQUENCY OF WIND SPEEDS OF 17 KNOTS OR MORE

Station	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Average	Yrs Rec
Alameda	6.5	8.2	8.0	7.7	8.3	7.6	3.4	3.0	2.7	3.2	4.2	5.1	5.7	12
Arcata	4.2	6.9	6.3	6.6	7.6	5.6	2.6	1.7	1.9	2.0	3.0	3.2	4.2	12
Bakersfield Meadows	6.9	1.6	1.5	1.9	2.3	1.8	0.3	0.3	0.3	0.3	0.5	0.7	1.0	12
Bale AFB	4.1	4.5	3.0	2.2	0.9	1.8	0.4	0.7	1.2	2.8	2.9	3.9	2.4	7
Beaumont	8.2	2.0	3.8	1.0	0.6	0.5	0.8	0.6	0.9	3.6	9.9	6.7	3.2	4
Blyth	7.1	8.2	10.7	6.8	6.9	6.6	4.4	3.6	2.1	2.6	6.3	6.2	6.0	7
Burbank	1.3	2.5	1.7	2.0	0.7	0	0	0	0	0.5	1.4	1.7	1.0	12
Castle AFB	3.3	4.7	3.7	3.9	2.9	3.2	1.2	0.6	0.6	2.0	1.4	2.9	2.5	12
Chico	8.7	14.3	11.7	11.6	12.4	9.4	1.6	1.6	5.4	6.6	7.7	5.4	8.0	4
China Lake	9.6	12.6	18.7	19.3	17.5	15.5	10.2	10.3	8.6	9.2	7.8	7.9	12.3	12
Crescent City	20.7	11.7	15.9	13.0	17.4	12.2	9.7	4.1	4.8	5.8	8.1	0.5	11.2	6
Crows Landing	2.3	1.5	2.1	1.2	1.5	1.0	0.1	0.1	0.1	1.8	1.3	1.4	1.2	7
Daggett	9.9	13.3	25.5	25.9	32.5	29.2	15.3	10.5	10.1	8.2	7.8	7.5	16.3	12
Edwards AFB	8.6	8.9	15.6	17.5	20.0	19.8	12.0	10.3	8.2	6.0	6.8	7.5	11.8	12
El Centro	6.2	8.1	13.3	15.7	18.1	16.1	4.3	4.0	4.6	5.5	6.1	4.8	8.9	12
El Toro	1.4	1.9	1.2	0.9	0.5	0.1	0	0.1	0.1	0.3	2.4	2.4	0.9	12
Fall River Mills	2.3	2.3	3.2	2.0	1.8	1.3	0.2	0.3	0.6	1.4	1.4	2.5	1.6	10
Fallon	1.5	2.9	4.0	4.1	2.7	1.8	0.7	0.4	0.6	1.6	0.9	1.9	1.9	12
Fort Bragg	5.4	8.1	7.1	5.6	3.6	2.4	1.2	1.0	2.2	1.0	2.0	3.4	3.6	3
Fort Ord	0.2	0.3	1.3	1.8	1.4	0.7	0.4	0.3	0.3	0.4	0.3	0.2	0.6	6
Fresno AT	0.6	0.6	1.1	1.3	0.9	0.8	0.1	0	0.2	0.4	0.2	0.3	0.5	12
George AFB	7.1	9.7	13.1	13.9	13.2	10.4	5.9	6.6	4.4	4.7	6.1	6.3	8.5	13
Hamilton AFB	2.6	3.6	2.4	2.3	2.0	1.6	0.4	0.6	0.7	2.1	2.0	3.2	2.0	12
Hollister	2.3	1.5	2.1	1.2	1.5	1.0	0.1	0.1	0.1	1.8	1.3	1.4	1.2	7
Holtville	1.5	3.6	2.8	3.8	2.3	2.6	3.6	2.8	0.9	1.1	2.0	1.5	2.4	12
Imperial Beach	2.9	2.5	1.3	1.8	1.0	0.9	0.5	0.3	0.3	0.4	1.9	1.3	1.3	10
Las Vegas	6.3	11.0	14.2	15.4	15.8	13.7	9.2	8.4	7.7	7.6	5.6	6.3	10.1	12
Lemoore	1.6	2.0	3.3	3.6	3.4	3.8	1.2	1.2	1.0	1.2	1.5	1.0	2.1	9
Livermore	2.5	2.3	2.2	1.9	1.6	1.8	0.3	0.1	0.4	1.7	1.1	1.4	1.5	9
Long Beach	0.8	1.8	1.5	1.7	1.0	0.3	0.1	0.3	0.3	0.4	1.3	1.1	0.9	12
Los Alamitos	1.7	1.9	2.5	1.8	1.4	0.3	0	0	0.2	0.2	2.3	2.2	1.2	12
Los Angeles AP	1.5	3.0	2.8	2.8	1.7	0.3	0.1	0.1	0.2	0.6	1.2	1.7	1.3	12
March AFB	0.8	0.9	0.9	0.9	0.5	0.5	0.4	0.4	0.1	0.4	0.9	0.9	0.6	12
McChesney AFB	8.9	8.5	5.9	3.7	2.2	2.3	1.1	0.6	0.6	2.5	3.5	6.7	3.9	12
McClellan AFB	6.3	7.4	6.2	3.9	4.2	3.5	1.0	1.3	0.6	3.3	4.0	6.7	4.1	11
Medford	3.3	2.9	2.7	2.6	2.1	1.7	1.1	1.0	0.7	0.9	1.6	1.6	1.9	12
Miramar	0.6	0.4	0.8	0.6	0	0	0	0	0	0.1	0.5	0.5	0.3	12
Norfolk Field	4.1	5.2	3.3	4.1	4.4	6.0	3.6	2.6	2.0	1.9	2.1	3.9	3.6	12
Mojave	10.1	9.6	19.6	30.0	21.3	29.4	16.9	11.2	11.7	14.2	10.8	5.8	15.9	3
Montague	11.6	6.3	9.4	8.7	4.7	4.2	4.0	3.2	1.7	5.7	9.4	6.8	6.3	5
Monterey	1.1	1.8	1.5	2.3	2.0	0.9	0.2	0.3	0.2	0.5	0.9	2.5	1.2	12
Naval Air Station	8.0	10.1	10.2	9.1	8.4	7.1	3.5	3.8	3.2	5.9	8.9	8.3	7.2	7
Nellis AFB	4.6	7.3	11.3	10.8	9.8	7.2	4.3	4.5	4.0	5.1	5.2	3.6	6.5	12
Norton AFB	1.7	3.5	2.1	0.8	0.6	0.3	0.1	0.1	0.4	0.7	1.9	2.1	1.2	12
Oakland AP	2.6	4.6	4.5	4.9	5.4	3.9	1.5	1.4	1.2	2.2	2.3	2.7	3.1	12
Occidental	4.6	1.4	3.2	2.0	1.9	0.3	0	0.2	0.4	0.8	1.2	3.8	1.7	5
Ontario	3.3	2.9	2.9	0.9	1.0	0.1	0.1	0.1	0.7	0	4.2	1.9	1.5	4
Oxnard	4.0	3.3	2.4	2.1	1.8	0.4	0	0.1	0.1	0.8	3.2	5.9	2.0	13
Palm Springs	2.6	3.7	6.8	14.9	16.9	17.8	9.6	5.3	5.2	3.1	1.7	0.8	7.4	4
Palm Springs	8.7	8.5	15.7	14.7	15.8	15.1	8.4	6.9	4.5	5.3	7.2	8.4	9.9	7
Point Air	2.3	2.9	4.6	6.5	10.3	13.7	11.8	8.8	5.0	2.6	2.0	3.0	6.0	7
Point Arguello	3.8	5.5	8.3	9.4	8.2	1.6	0.7	0.4	0.7	2.9	3.0	3.0	4.0	7
Point Barlow	12.1	10.8	9.7	7.5	6.6	2.3	1.1	1.0	1.0	3.0	11.4	16.3	6.9	12
Porterville	1.6	2.0	3.3	3.6	3.4	3.8	0.8	0.8	0.7	1.2	1.5	1.0	2.0	9
Red Bluff	10.6	12.4	11.0	8.8	6.9	4.8	1.8	1.4	4.5	7.2	7.7	7.8	7.1	12
Red Bluff	11.1	12.7	10.9	8.5	6.5	5.1	1.7	1.4	4.2	7.0	6.9	7.9	7.0	12
Red Bluff	7.2	6.8	8.5	7.4	7.1	6.1	4.4	4.5	3.0	4.5	4.1	5.0	5.7	12
Red Bluff	8.3	9.4	7.1	5.4	5.2	6.1	3.8	3.2	2.7	4.8	4.5	7.5	5.7	13
Red Bluff	2.3	2.1	2.5	0.5	0.2	0.3	0	0	0	0.7	1.8	4.1	1.2	7
San Diego AP	11.0	5.7	11.0	5.9	5.7	1.8	0.7	0.6	0.9	1.2	6.9	5.6	4.8	5

TABLE 3
EXTREME ANNUAL WIND SPEED
FASTEST MILE, 1871-1978
(mph)

Year	Eureka	Fresno	Los Angeles	Mt. Tamalpais	Red Bluff	Sacramento	San Diego	San Francisco	Yuma, AZ
1871									
1872								30	
1873							30	38	
1874							19	27	
1875							27	40	
1876							30	36	
1877							57	32	
1878			22		37	32	47	33	36
1879			24		41	32	26	33	30
1880			22		47	32	29	36	27
1881			37		34	27	29	30	34
1882			38		32	29	30	30	31
1883			34		31	30	27	30	35
1884			32		38	30	27	37	27
1885			30		35	30	21	30	38
1886			30		40	35	30	35	35
1887	34		30		36	32	30	30	33
1888	31	26	27		36	38	30	33	37
1889	35	24	21		35	34	30	31	37
1890	34	22	21		38	34	25	30	37
1891	32	25	24		41	32	25	40	38
1892	40	25	21		38	38	22	49	35
1893	32	24	24		30	36	28	39	35
1894	37	28	25		37	47	29	33	43
1895	35	24	22		32	38	22	36	37
1896	38	31	21		34	38	29	35	32
1897	36	27	28		30	35	29	37	30
1898	35	27	21		30	34	27	36	35
1899	32	27	25	70	34	38	27	39	34
1900	35	22	20	62	30	41	25	40	29

Corrected to true wind speed.

TABLE 3 (cont)
EXTREME ANNUAL WIND SPEED
FASTEST MILE, 1871-1978
(mph)

Year	Eureka	Farallon	Fresno	Los Angeles	Mt. Tamalpais	Point Reyes	Red Bluff	Reno, NV	Sacramento	San Diego	San Francisco	San Jose	Yuma, AZ
1901	32		24	21	69		37		47		47		32
1902	37		30	25	66		32		49		49		35
1903	35		30	22	69		30		32		35		34
1904	38	54	31	30	54		35		51		40		31
1905	38	56	28	30	61		30		35		35		32
1906	36	59	30	30	57		32	47	41		52		33
1907	36	50	22	28	60		27	40	35		35		33
1908	38	46	21	32	60		32	37	31		29	30	32
1909	38	52	25	28	64		28	43	38		40	34	30
1910	36	53	30	32	56		31	36	30		31	29	32
1911	37		27	31	66	64	32	44	32		36	30	35
1912	35		30	34	57	68	27	47	38		40	30	32
1913	35		30	31	57	66	30	40	35		35	30	32
1914	46		32	30	68	72	27	38	36		36	35	29
1915	46		35	30	68	84	29	45	45		42	38	32
1916	35		41	34	70	80	27	43	40	43	40	37	32
1917	35		28	29	70	77	26	47	39	35	43	37	37
1918	40		31	31	68	65	27	39	32	34	35	30	32
1919	35		30	24	68	65	30	40	38	32	51	30	34
1920	32		34	29	70	69	31	40	32	30	37	30	30
1921	38		30	35		76	35	43	40	32	47	35	33
1922	39		29	28		64	32	46	38	41	37	35	33
1923	37		34	30		59	32	41	32	29	52	26	34
1924	34		30	25		64	30	38	32	34	35	30	29
1925	38		27	22		57	27	37	27	31	33	30	35
1926	36		28	30		73	31	41	32	30	41	30	30
1927	32		38	26			26	40	41	31	36	32	30
1928	36		29	24			27	39	32	26	42	30	31
1929	32		30	21			27	40	33	26	38	30	40
1930	50		30	21			25	38	37	31	32	34	30

Corrected to true wind speed.

TABLE 3 (cont)
EXTREME ANNUAL WIND SPEED
FASTEST MILE, 1871-1978
(mph)

Year	Eureka	Fresno	Los Angeles	Oakland AP	Red Bluff	Red Bluff AP	Redding	Sacramento	San Diego	San Francisco	Santa Maria	Yuma, AZ
1931	42	33	24		36			31	30	33		35
1932	37	32	28		30			58	28	40		34
1933	30	30	25		35			34	32	30		35
1934	31	25	23					29	24	30		30
1935	30	32	23				30	30	29	41		35
1936	34	30	25				38	35	31	34		32
1937	38	31	23				36	29	28	31		29
1938	35	35	26				41	46	34	38		34
1939	35	40	30	57			42	32	34	34		30
1940	34	26	33	44			40	34	33	34		29
1941	35	35	36	49			36	37	36	39		29
1942	37	31	36	45			36	35	34	34		31
1943	40	30	43	63			34	33	44	35		29
1944	37	34	35	44				35	37	30	35	30
1945	35	32	38	46		37		36	36	32	36	33
1946	38	35	48	48		38		34	33	31	40	37
1947	34	31	34	45		39		29	27	31	38	34

Records before 1931 corrected to "true" windspeed.

(Table 3 continued on next page)

TABLE 5
PEAK GUST IN KNOTS
(Direction/Wind speed)

	Yrs Rec	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	TOTAL
Alameda	28	4 60	SSW 59	50	SSE 46	W 46	W 43	W 35	W 32	NNE 42	W 55	SSW 61	NW 67	NW 62
Beale AFB	16	17 51	16 54	16 44	32 38	34 37	15 36	SSW 28	SSW 30	NNE 42	S 46	15 54	19 58	19 58
Corp Headleton	4	SSW 40	S 39	W 37	W 44	W 26	SW 23	W 16	W 20	SW 29	NW 30	SE 35	WSW 33	W 44
China Lake	20	SW 67	W 65	W 70	SW 64	WSW 71	WSW 67	SW 52	WSW 50	WSW 60	SW 59	W 58	SSW 62	NW 71
Castle AFB	29	SE 51	NW 51	SE 49	NW 48	NW 43	NW 43	NW 30	NW 25	NW 42	SSW 43	LA 48	SE 47	NW 54
Edwards AFB	29	NW 51	W 56	W 64	NW 50	29 54	27 51	27 44	ENE 52	W 65	NW 65	W 48	WSW 50	W 65
El Centro	13	WSW 50	WSW 52	WSW 58	WSW 58	W 58	W 52	WSW 41	SE 51	SSE 48	W 48	WSW 53	W 55	WSW 58
El Toro	27	NE 55	NE 65	NE 55	SSW 46	NE 48	NNE 33	SE 47	SSE 36	NE 43	E 45	NE 63	E 60	NE 65
Fort Ord	11	13 44	18 50	SE 37	NW 40	27 40	SW 38	WSW 26	W 26	WSW 29	SW 40	ESE 47	SSW 42	18 50
George AFB	23	5 54	15 52	SSE 62	S 52	NW 46	W 76	N 50	SE 44	19 35	NW 44	SW 52	N 56	W 76
Hamilton AFB	24	SSW 56	SSW 75	S 49	SW 49	NW 45	NW 41	NW 32	WSW 46	SSW 46	NW 64	S 53	S 53	SSW 75
Imperial Beach	18	SSE 48	S 37	NW 44	WSW 48	WSW 28	SW 27	SSW 28	SW 26	NE 30	28 43	W 51	S 40	W 51
Lemoore	12	NW 38	NW 43	N 38	NW 32	N 37	25 33	N 28	NW 27	NW 13	14 39	SSE 32	32 41	NW 43
Los Alamitos	20	W 54	NE 42	WSW 54	NW 47	NE 33	ENE 32	W 25	SE 26	E 26	NW 39	ENE 53	ENE 54	ENE 54
Los Angeles NAS	15	SW 42	N 50	W 54	N 51	N 39	W 26	W 23	SW 27	SW 23	N 40	N 48	S 43	N 54
March AFB	19	NNE 46	NW 43	NNE 41	ENE 38	W 34	N 39	NE 43	S 35	SE 39	N 39	W 40	NNE 45	NNE 49
Marathon AFB	31	SSE 61	15 62	S 62	SE 53	NNE 43	NW 45	SSW 33	24 32	SSE 50	S 63	SSE 56	SSE 64	SSE 64
McGuire AFB	31	SSE 66	15 60	SE 66	SSE 55	NW 55	NW 56	S 39	S 34	S 40	SSE 71	SSE 55	SSE 65	SSE 71
Miramar	26	NW 39	SSW 39	W 37	WSW 41	ESE 31	S 25	32 5	28 42	31 33	SW 50	W 44	SW 50	SW 50
Moffett Field	27	ESE 56	SE 56	SE 44	N 43	NW 38	NW 40	NW 30	NW 31	SE 33	SE 48	N 48	SSE 54	SE 56
Monterey	16	SSW 54	SSW 69	100	SW 46	WSW 39	WSW 40	SSW 33	N 32	ESE 31	W 56	SSE 49	SW 63	100
Norton AFB	27	NW 65	N 55	N 47	NE 47	NE 40	NW 48	SE 39	WSW 54	SW 60	SW 57	01 54	N 64	NW 69
Orland AFB	10	ESE 47	ENE 44	WSW 43	N 36	NW 36	W 23	SW 22	SW 21	ESE 32	ENE 44	ENE 50	ENE 45	ENE 50
Point Mugu	13	ENE 61	NE 49	W 47	N 50	WSW 44	W 29	SE 33	SE 27	NE 40	ENE 48	ENE 54	NE 56	ENE 61
San Clemente	10	NW 35	NE 44	NW 42	NW 37	NW 34	NW 31	SW 24	14 28	16 29	23 33	E 39	NW 38	NE 44
San Diego USN	33	SSE 52	W 46	S 52	NW 63	ENE 33	W 28	NW 24	NW 28	NW 23	NW 51	SW 46	S 40	WSW 63
San Francisco AP	17	WSW 68	WSW 56	SW 50	SSW 52	W 54	W 50	W 41	W 43	S 49	SW 56	SSW 58	S 57	WSW 68
San Nicolas Island	11	NW 52	W 64	NW 51	NW 55	NW 56	NW 52	NW 45	NW 43	N 47	SW 50	NW 52	NW 53	W 64
Santa Ana	10	NE 57	NE 53	NE 42	SSE 34	ENE 40	WSW 28	SSW 26	N 31	NE 40	05 37	NE 54	NE 58	NE 59
Travis AFB	25	N 60	NW 63	SE 56	SE 53	SSW 45	SSW 47	23 46	SW 45	34 47	NW 51	N 54	SE 49	NW 65
Vandenberg	13	33 41	19 43	SE 40	N 40	NW 35	32 36	30	30	31 32	31 32	44	44	44
White Mountain 1	22	W 94	SW 66	S 58	N 52	49	56	38	68	38	58	W 55	S 64	W 94
White Mountain 2	18	N 82	70	NW 65	W 72	W 56	W 44	5	46	SW 46	NE 44	W 70	N 58	W 62
San Diego NAS	7	W 38	SE 44	S 46	N 37	S 34	NE 26	S 26	S 39	NE 26	N 30	W 42	SE 34	SE 44

TABLE 6
FASTEST MILE,
FROM LOCAL CLIMATOLOGICAL DATA
(Direction/Wind speed in mph)

	Yrs Rec	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	TOTAL
Bakersfield	28	02 35	29 44	35 38	29 40	32 38	35 41	29 25	06 30	14 35	32 31	34 30	17 35	29 44
Rishop	2	47	52	58	58	53	60	46	75	48	48	56	66	75
Elvis Canyon	19	20 67	17 76	07 67	20 50	23 37	07 49	09 32	07 30	09 49	05 70	19 54	07 51	17 76
Eureka	66	5 54	SW 48	SW 48	E 49	NW 40	NW 39	N 35	N 34	N 44	SW 56	S 43	S 56	SW 56
Fresno	26	SE 32	W 38	NW 41	NW 36	UL 38	W 34	NE 25	S 31	SW 29	NE 40	NW 29	NE 43	NW 43
Long Beach	18	17 37	18 40	32 35	29 44	27 37	27 21	18 23	27 23	33 23	32 38	34 35	32 39	29 44
Los Angeles AP	26	SW 48	N 57	W 62	N 59	N 45	W 32	W 29	SE 33	SW 26	W 46	N 55	S 49	W 62
Los Angeles CC	35	N 48	NW 40	NW 47	NW 40	NW 39	N 32	W 21	E 24	NW 27	N 48	N 42	SE 44	N 49
Oakland	28	16 46	36 44	20 45	25 32	27 38	27 42	27 24	27 29	02 33	25 43	02 46	23 48	36 49
Red Bluff	32	SE 59	SE 61	SE 63	SE 58	S 46	NW 36	N 38	SW 30	N 50	SE 63	SE 56	SW 60	60
San Antonio FAP	28	55 60	SE 51	S 66	SW 45	S 35	SW 42	SW 36	SW 38	NW 42	SE 68	SE 70	SE 70	70
San Diego	33	SW 39	S 38	SW 46	S 37	SW 27	S 26	NW 23	SW 23	W 25	N 31	SE 51	S 34	SE 51
San Francisco FOH	36	55 47	SW 47	S 44	W 38	W 38	W 40	W 38	W 34	W 32	SE 43	S 42	SE 45	47
San Francisco AP	27	16 58	25 52	20 40	16 46	20 41	28 44	27 38	27 36	24 38	25 41	20 47	18 47	16 58
Sandburg	21	20 64	32 74	34 74	36 64	34 59	34 64	34 46	34 40	35 45	34 5	34 62	34 53	32 77
Stockton	13	14 46	35 31	33 35	24 35	31 33	26 31	25 26	32 28	34 33	34 34	13 40	15 46	14 46
Waco Nevada	16	SW 80	SW 64	SW 80	SE 48	SW 48	NW 46	SW 44	SW 43	W 42	S 50	SW 52	SW 60	80
Yuba P	26	SW 41	W 54	N 43	NE 47	NW 38	SW 42	NE 52	SE 60	E 57	S 47	N 47	W 47	SE 60
Yuba P	27	23 50	24 46	16 59	14 59	12 38	33 18	07 44	15 48	14 32	20 40	16 30	14 16	55
Las Vegas	12	SW 54	NW 64	SW 50	SW 52	SW 52	SW 46	NE 64	NE 55	NW 56	NE 52	SE 46	SW 54	NE 64

TABLE 8
ANNUAL FASTEST MILE IN MILES PER HOUR

Station	Years ^{a/} of Record	Latitude	Longitude	Elevation Feet	Inst. Height Feet	Mean MPH	Return Period—Years				Record Maximum
							10	25	50	100	
Bakersfield	30	35 25	119 03	497	20	34	41	44	46	60	41 NW
Blue Canyon	22	39 17	120 42	5,280	20	49	69	78	84	90	76 S
Eureka	31	40 48	124 10	43	88	43	52	56	59	62	56 SW
Farallon ^{b/}	7	37 42	123 09	30		53	59	61	63	65	59 S
Fresno	31	36 46	119 43	328	20	33	39	42	44	46	43 NW
Las Vegas											64 NE
Long Beach	20	33 49	118 09	34	20	33	40	43	45	47	44 W
Los Angeles	29	34 02	118 14	257	104	45	54	59	61	63	62 N
Medford	30	42 22	122 52	1,298	20	37	47	51	54	57	55 SSE
Mt. Tamalpais ^{b/}	22	37 56	122 35	2,586		64	72	75	77	79	70 NW
Oakland	31	37 44	122 12	6	20	39	47	51	53	56	50 N
Point Reyes ^{b/}	16	38 00	123 01	510		69	79	84	87	90	84 SE
Red Bluff	31	40 09	122 15	342	20	50	61	65	69	72	68 SE
Redding ^{b/}	9	40 35	122 23	560		37	42	44	46	47	42 SE
Reno	28	39 30	119 47	4,404	20	56	69	75	79	82	80 SW
Sacramento EAP	31	38 31	121 30	17	20	43	59	66	70	75	70 SE
San Diego	31	32 44	117 10	13	37	33	40	43	45	47	47 SE
San Francisco AP	28	37 37	122 23	5	20	45	55	59	62	65	60 SE
San Francisco FOB	25	37 47	122 25	52	132	38	45	49	51	53	47
San Jose ^{b/}	23	37 20	121 54	95		32	36	38	39	40	38 SE
Sandberg	29	34 45	118 44	4,517	30	66	82	90	96	101	97 NW
Santa Maria	17	34 54	120 27	236	24	36	44	47	50	52	46
Stockton	31	37 54	121 15	22	20	34	41	44	47	49	46 SL
Yuma	31	32 40	114 36	194	20	44	54	58	61	63	60 SE

^{a/} Based on 1948 to 1978 data except where noted.

^{b/} Based on older records which have been corrected.

APPENDIX D


**PLATES from PREVIOUS
U.S. CORPS of ENGINEERS REPORTS**


at






BUHNE POINT/KING SALMON AREA

REFERENCE MATERIAL
FROM
U. S. ARMY CORPS OF ENGINEERS
REPORTS





Previous investigations and studies made by the Corps of Engineers were used to obtain a background on the wave climate, surface and subsurface soils, and sediment transport system along the shore between Fields Landing Channel to Buhne Point. The Corps' previous report "Beach Erosion Control Report on Cooperative Study of Humboldt Bay (Buhne Point)" furnished most of the design data needed to formulate our design study. Surface and subsurface materials investigations carried out by the Corps for their "Design Memorandum No. 1 Humboldt Harbor and Bay" set parameters for the design of the sheet-pile groins and the H-Beam pile structures. Needed background on the wave climate within the bay in the vicinity of Buhne Spit was obtained from the Corps' "Survey Report Humboldt Bay, California". The plates appended to this report were copied from the Corps' reports and are used to give the reader a better understanding of the bottom materials within the bay and the erosion that has taken place within the Buhne Point area during the past five decades.












SAMOA CHANNEL



EUREKA CHANNEL



FIELDS LANDING CHANNEL

GENERAL NOTES

1. Elevations indicate approximate ground surface at boring location based on the datum of Mean Lower Low Water.
2. Soil descriptions as tested by the field inspector are shown to the right of the log along with laboratory gradation tests.
3. Locations of investigation holes are shown on Plate B-1.

LEGEND

PT = Push Tube Sample




GR 18%, SA 72%, F 10% = Laboratory Gradation Test:
Gravel 18%, Sand 72%, Fines 10%

C.B. = Proposed Channel Bottom


⊗ = No Recovery











W=21% = Natural Water Content 21%

BC = Blow Count: Number of blows required to drive a 2 1/2 inch diameter sampler 2 1/2 feet by using a 140-pound hammer with a 30-inch drop








AMCA CHANNEL













NORTH BAY CHANNEL



NORTH BAY CHANNEL





EUREKA CHANNEL



NOTES:

1. Legend and General Notes are shown on Plate C-2.
2. Additional logs of exploration holes in Eureka channel are shown on Plate C-2.

NORTH BAY CHANNEL




EUREKA CHANNEL

DESCRIPTION		DATE
REVISIONS		
U.S. ARMY ENGINEER DISTRICT SAN FRANCISCO CHIEF OF ENGINEERS SAN FRANCISCO, CALIFORNIA		
PROJECT NO.	HUMBOLDT COUNTY HUMBOLDT HARBOR AND BAY NAVIGATION CHANNEL IMPROVEMENTS	
REPORT NO.	LOGS OF EXPLORATION HOLES	
DATE OF FIELD WORK	DATE OF REPORT	BY
PREPARED UNDER THE DIRECTION OF CHIEF OF ENGINEERS COLONEL C.E. DISTRICT ENGINEER		
NO. OF SHEETS	3 5 5 3	

PLATE C-1

COMPS OF ENGINEERS




HOLE NO. P 1-151

Depth in feet	Stratification	Notes
0		Very fine sand, light brown, silty
10		Very fine sand, light brown, silty
20		Very fine sand, light brown, silty
30		Very fine sand, light brown, silty
40		Very fine sand, light brown, silty
50		Very fine sand, light brown, silty
60		Very fine sand, light brown, silty
70		Very fine sand, light brown, silty
80		Very fine sand, light brown, silty
90		Very fine sand, light brown, silty
100		Very fine sand, light brown, silty
110		Very fine sand, light brown, silty
120		Very fine sand, light brown, silty
130		Very fine sand, light brown, silty
140		Very fine sand, light brown, silty
150		Very fine sand, light brown, silty




HOLE NO. P 7 1-151

Depth in feet	Stratification	Notes
0		Very fine sand, light brown, silty
10		Very fine sand, light brown, silty
20		Very fine sand, light brown, silty
30		Very fine sand, light brown, silty
40		Very fine sand, light brown, silty
50		Very fine sand, light brown, silty
60		Very fine sand, light brown, silty
70		Very fine sand, light brown, silty
80		Very fine sand, light brown, silty
90		Very fine sand, light brown, silty
100		Very fine sand, light brown, silty
110		Very fine sand, light brown, silty
120		Very fine sand, light brown, silty
130		Very fine sand, light brown, silty
140		Very fine sand, light brown, silty
150		Very fine sand, light brown, silty




STATE OF CALIFORNIA COOPERATIVE MARINERS ON CONTAMINATED
BUHNE POINT AREA, HUMBOLDT BAY, CALIFORNIA
LOCATION AND LOGS
OF BEACH AND BOTTOM SAMPLES
AND BORINGS
SCALE 1:50,000
W. SNEYD
PRINTED BY THE DISTRICT COURT HOUSE, SAN FRANCISCO, CALIF. 1970
DRAFT COPY
TO BEADMAN BEACHES
CONTAMINATED AREAS
JAN 1970
3-3-70

CORPS OF ENGINEERS





VELOCITY RANGE MILES PER HOUR



WIND DIAGRAM

BASED ON OBSERVATIONS AT EUREKA, CALIF.
U.S. WEATHER BUREAU, STA. 117, 1916-1917



NOTES
Scale of map is 1 inch = 1 mile.
Map is not to be used for navigation.
For detailed information, consult the latest edition of the Sailing Directions for the Pacific Coast of North America.




STATE OF CALIFORNIA COOPERATIVE BEACH EROSION CONTROL STUDY
SUNNY POINT AREA, HUMBOLOT BAY CALIFORNIA
LOCATION MAP

610 899187



[illegible]




TYPICAL SECTION OFFSHORE BREAKWATER



GROIN PROFILE BUNNE SPIT



RUBBLE-MOUND OFFSHORE BREAKWATER, FOUR DETACHED SECTIONS, EACH 500 FT LONG, TOTAL LENGTH 2000 FT





ALIGNMENT OF CONSIDERED SEAWALL, 2,200 FT LONG

ALIGNMENT OF RECOMMENDED SEAWALL, 800 FT LONG

RECOMMENDED STONE GROIN, 790 FT LONG

NOTE: For rubble-mound seawalls, 10% filter blanket required prior to placement of large stone





LAND AND GROIN PROFILE
R.R. FRONTAGE

TYPICAL SECTION
OFFSHORE BREAKWATER

GROIN PROFILE
BUHNE SPIT

RUBBLE-MOUND OFFSHORE
BREAKWATER, FOUR DETACHED
SECTIONS, EACH 500 FT LONG,
TOTAL LENGTH 2000 FT

ALIGNMENT OF CONSIDERED
SEAWALL, 2,200 FT LONG

ALIGNMENT OF RECOMMENDED
SEAWALL, 800 FT LONG

RECOMMENDED STONE
GROIN, 790 FT LONG


ALIGNMENT OF CONSIDERED
R.R. TRACK RELOCATION


ALIGNMENT OF CONSIDERED
NEW SEAWALL, 3,300 FT LONG

STATE OF CALIFORNIA COOPERATIVE BEACH EROSION CONTROL STUDY
BUHNE POINT AREA, HUMBOLDT BAY, CALIFORNIA
PLANS OF IMPROVEMENT CONSIDERED


1" = 100' HORIZONTAL
1" = 10' VERTICAL
SHEET NO. 1
APPROVED BY THE BOARD OF SUPERVISORS
COUNTY OF HUMBOLDT, CALIFORNIA
OCTOBER 9, 1956

CORPS OF ENGINEERS





CORPS OF ENGINEERS



U.S. ARMY

BUCKSPORT

NORTH

BAY

HUMBOLDT

LEGEND

—	1846
—	1866
—	1881
—	1893
—	1898
—	1870
—	1894

NOTES

Surveys of 1846, 1866 and 1881 by
Corps of Engineers
Topography from Corps of Engineers
Survey of November 1846

HUMBOLDT BAY
CALIFORNIA

RELATIVE POSITIONS OF
MHW AT VARIOUS PERIODS
1854—1926

IN 2 SHEETS SHEET No. 1


SAN FRANCISCO DISTRICT
CORPS OF ENGINEERS

10 FEBRUARY 1927


APP. I FILE - 501.1

SCALE FEET

CORPS OF ENGINEERS



U.S. ARMY



LEGEND

—	1946
- - -	1946 (MLLW)
...	1939
- . - . -	1931
- - - - -	1929
- - - - -	1926

NOTES
 All surveys by Corps of Engineers
 Topography from Corps of Engineers
 survey of November 1936

**HUMBOLDT BAY
 CALIFORNIA**

**RELATIVE POSITIONS OF
 MHW AT VARIOUS PERIODS
 1926-1946**

IN 2 SHEETS SHEET No. 2

**SAN FRANCISCO DISTRICT
 CORPS OF ENGINEERS**

10 FEBRUARY 1947

APP. I


FIG. 2-SH. 2

APPENDIX E


CONCEPTUAL PLANS of ALTERNATE DESIGNS

at


BUHNE SPIT AREA



SECTION C-C




SECTION A-A



PROFILE SECTION

400 LF. OFFSHORE BREAKWATER




PROFILE SECTION

1400 L.F. GROIN TRAINING WALL


PLAN

A




SCALE 1" = 500 FEET


ROCK
PG 81
IN F



SECTION C-C




TYPICAL SECTION B-B
STEEL H-PILES WITH TIMBER LAGGING
USE FULL LENGTH IN ALT. 2 AND
FOR 1000 LF IN ALT. 3



ICK

PROFILE SECTION


400 LF. OFFSHORE BREAKWATER



APPROX. ALIGN.
OF GROIN
PROPOSED BY
U.S.C.E. ON A
OCT. 1956

1400 LF.
GROIN

ANTICIPATED
FUTURE
STABLE
SHORELINE
ALIGNMENT




Map No. 15 5972 USGS Map of Fields
Landing, California.
Shore line shown represents the
approx. line of Mean High Water.
Depth contours are in feet below
Mean High Water (MHW) datum.
The shore depth contours (1:00) are
represented from a July 1960 U.S.C. of
F's Hydrographic Survey Contract and
from Humboldt Co. Aerial Photography
taken at 9:05 a.m. on May 25, 1962 (Tide
Elev. -1.3).
Grid coordinates are from the Calif.
Coordinate System Zone 1.
Humboldt Shippers, Inc. property
lines established from P.G. & E.'s map of
Tidelands Survey #102.

SITE PLAN


WALL 0 500 1000 1500

SCALE 1" = 500 FEET


ROCK REVETMENT PLACED BY
PG&E AND HUMBOLDT CO.
IN FALL 1982



PROFILE SECTION
1600 L.F. TRAINING WALL GROIN



PROFILE SECTION
200 L.F. GROIN



PLAN B

APPROXIMATE
ALIGNMENT OF GROIN
PROPOSED BY USCE
ON OCT. 1956



1600'
GROIN

NOTES

Base Map is 1917 and Map of Field
Landing Quadrangle
Shore line shown represents the
approx. line of Mean High Water
Depth contours are in feet below
Mean Lower Low Water (MLLW) Datum
The first depth contours shown are
approximately from a 1940 U.S. Coast
and Geodetic Survey contract and
from Hydrographic Survey Photography
taken at 9:05 a.m. on March 1942 (Tide
Stage 3.5 ft)
Elev. soundings are from the United
States Coast and Geodetic Survey
Hydrographic Survey of 1942
Line established from U.S. map of
Tide and Currents, 1942

ANTI
FUTU
SHOR
ALIGN


0




TYPICAL SECTION B-B


STEEL H-PILES WITH TIMBER LAGGING
USE FULL LENGTH IN ALT. 2 AND
FOR 1000 L.F. IN ALT. 3

SECTION **RAINING WALL GROIN**





PROFILE SECTION
1750 L.F. TRAINING WALL GROIN




PROFILE
200 L.F. GROIN

APPROXIMATE
ALIGNMENT OF WEST
RETENTION GROIN
PROPOSED BY USCE IN
SECTION III PROJECT IN
SPRING 1982

1750' GROIN

200

ANTI
FUTU
SHOI
ALIG




SECTION A-A

PLAN C

NOTES

Base Map is 1972 USGS Map of Fields
Landing Quadrangle
Shore line shown represents the
approx. line of Mean High Water.
Depth contours are in feet below
Mean Lower Low Water (MLLW) Datum.
One foot depth contours (---) are
approximated from a July 1980 U.S.C. of
E's Hydrographic Survey Contract and
from Humboldt Co. Aerial Photography
taken at 9:05 a.m. on May 25, 1982 (Tide
Flev = 1.5).
Grid coordinates are from the Calif
coordinate System Zone 1.
Eureka Shipbuilders, Inc., property
lines established from U.S.C. map of
Tidelands Survey #102.

0





PROFILE SECTION

E. TRAINING WALL GROIN


TYPICAL SECTION B-B

STEEL H-PILES WITH TIMBER LAGGING FOR SHOREWARD 1000 L.F.







PROFILE
1400 L.F. TRAINING WALL



PROFILE
400 L.F. ROCK GROIN






SECTION A-A





PLAN D

NOTES:
Base Map is 1972 USGS Map of Fields Landing Quadrangle.
Shore line shown represents the approx. line of Mean High Water.
Depth contours are in feet below Mean Lower Low Water (MLLW) Datum.
One foot depth contours (1'-0") are approximated from a July 1980 U.S.C. of 1" Hydrographic Survey Contract and from Humboldt Co. Aerial Photography taken at 9:05 a.m. on May 5, 1982 (Tide Elev. = 1.5').
Grid coordinates are from the Calif. Coordinate System Zone 1.
Eureka Shipbuilders, Inc., property lines established from P.M. Map of Tidelands Survey #102.







STEEL H-PILES WITH TIMBER LAGGING
FOR SHOREWARD 900 L.F.



40 TON NOM.
ROCK RIP RAP




1/2 TON TOE ROCK
6' X 2' EA. SIDE



SITE PLAN

ROCK REVEYMENT
PLACED BY P.G.E. AND
HUMBOLDT CO. IN FALL 1982



NOTES

This Map is 1972 USGS Map of Fields Landing Quadrangle.

The above line sketch represents the approximate line of Mean High Water.

Depth contours are in feet below Mean Lower Low Water (MLLW) Datum.



Our foot depth contours (10' - 5') are approximated from a July 1980 U.S.C. of E.'s Hydrographic Survey Contract and from Munitions Co. Aerial Photography taken at 9:05 a.m. on May 25, 1982 (Tide Flw. = -1.5).

Gravel estimates are from the Calif. Coordinate System Zone 1.


Eureka Shipbuilders, Inc., property lines established from P.G. & E.'s map of Tidelands Survey P102.

[illegible]

DATE	STATE OF CALIFORNIA	BOATING	FACILITIES	DIVISION	RESOURCES AGENCY
AREA WORK NUMBER	HUMBOLDT COUNTY BUNNE SPIT - KING SALMON CONCEPTUAL DESIGN STUDY FOR THREE GROIN CONFIGURATION				
SHEET NUMBER					
OF					





ROCK RUBBLE MOUNDS
2000' L.F.



PLAN F

NOTES:
Base Map is 1954 USGS Map of Fields
Landing Grounds.
Shore line shown represents the
approx. line of Mean High Water.
Depth contours are in feet below
Mean Lower Low Water (MLLW).
New bathymetric contours (10, 20, 30)
are approximated from a July 1980 USGS
Hydrographic Survey contract and
from Humboldt County Aerial Photographs
taken at 1:25,000 scale on May 25, 1982.
Grid coordinates are from the latest
coordinate system (Zone 10).
Property boundaries are shown
lines established from 1:25,000 map of
Tidelands Survey #1.



NOTES
 Base Map is 1972 USGS Map of Fields Landing Quadrangle.
 Shore line shown represents the approx. line of Mean High Water.
 Depth contours are in feet below Mean Lower Low Water (MLLW) datum.
 One foot depth contours are approximated from a July 1980 report of U.S. Hydrographic Survey Contract and from Humboldt Co. Aerial Photography taken at 9:05 a.m. on May 20, 1982 (file #10-1-15).
 Grid coordinates are from the California State Plane Zone 1.
 Fureka Shipbuilders, Inc., property lines established from P.L. 84 map of Tidal Lands Survey #102.


RUBBLE MOUND SEAWALL
 PLACED BY PGE AND
 HUMBOLDT CO. IN FALL 1982



DESIGNED BY DR. W. PULIDO	CHECKED BY	DATE
BY	DATE	DATE
REVISION	DATE	DATE
DATE	DATE	DATE

STATE OF CALIFORNIA	RESOURCE AGENCY
BOATING	FACILITIES
HUMBOLDT COUNTY	
BUMNE SPIT-KING SALMON	
CONCEPTUAL DESIGN STUDY	
FOR ROCK RUBBLE SEAWALL	

DATE	DRAWING NUMBER	SHEET NUMBER	OF
------	----------------	--------------	----



SECTION A - A

0 500 1000 1500

SCALE 1" = 500 FEET






PLAN G

NOTES

Base Map is 1972 USGS Map of Fields Landing Quadrangle.
Shore line shown represents the approx. line of Mean High Water.
Depth contours are in feet below Mean Lower Low Water (MLLW) Datum.
One foot depth contours (-1, -2, -3) are approximated from a July 1980 U.S.C. of E.'s Hydrographic Survey Contract and from Humboldt Co. Aerial Photography taken at 9:05 a.m. on May 25, 1982 (Tide Elev. + 1.5).
Grid coordinates are from the Calif. Coordinate System Zone 1.
Eureka Shipbuilders, Inc., property lines established from P.C. & S. map of Tidelands Survey #102.

OPTION	SAND FILL
I	488,000 CUBIC YDS.
II	347,000 CUBIC YDS.
III	170,000 CUBIC YDS.





OPTION	SAND FILL
I	488,000 CUBIC YDS.
II	347,000 CUBIC YDS.
III	170,000 CUBIC YDS.

SITE PLAN

RUBBLE MOUND SEAWALL PLACER
 PLACED BY P.G. & E. AND HUMBOLOT CO.
 IN FALL 1982



NOTES

Base Map is 1972 USGS Map of Field Landing Quadrangle.

Shore line shown represents the approx. line of Mean High Water.


Depth contour^s are in feet below Mean Lower Low Water (MLLW) Datum.

One foot depth contours (1 - 5) are approximated from a July 1980 U.S.C. of E.'s Hydrographic Survey Contract and from the 1972 Aerial Photographic taken at 9:05 a.m. on May 25, 1982. Tide Elev. = 1.5.

Grid coordinates are from the Calif. Coordinate System Zone 1.


Eureka Shipbuilders, Inc., property lines established from P.L. 88's map of Tidelands Survey, #102.

PLAN H



FILE
KWATERS
IGGING

BOTTOM OF
TREATED
WOOD LAGGING




SECTION C-C


TYPICAL SECTION B-B
STEEL H-PILES WITH TIMBER LAGGING
FOR SHOREWARD 500' L.F.

10 0 AVG F
O.G.
CK

APPROX. ALIGN. OF
GROIN PROPOSED
BY U.S.C.E. ON
OCT. 1956




Base Map is 1977 USGS Map of Field
ing Quadrangle
shore line shown represents the
line of Mean High Water
depth contours are in feet below
mean low water (MLW) datum
one foot depth contours (1' - 10') are
derived from a July 1980 U.S.C. of
Hydrographic Survey Contract and
a number of Aerial Photographs
taken on May 25, 1982 (Tide
gauge 9.05 a.m. on May 25, 1982)
Coordinates are from the 1983
Datum (Source: Zone 1)
Humboldt Shipbuilders, Inc. property
established from P. 1. 50' map of
the area survey 1972




PROFILE

1200 L.F. TRAINING WALL GROIN




PROFILE

550' L GROIN





PLAN I

TYPICAL SECTION
STEEL H-PILES AND
FOR SHOREWARD





NOTE:
Base Map is 1972 USGS Map of Fields
Landing Quadrangle.
Shore line shown represents the
approx. Line of Mean High Water.
Depth contours are in feet below
Mean Lower Low Water (MLLW) datum.
One foot depth contours (1' M) are
approximated from a July 1980 U.S. Navy
1:50,000 Hydrographic Survey Chart and
from NOAA Aerial Photographs
taken at Point A on May 25, 1980 (side
view) and at Point B.
Depth soundings are from the chart.
Tide gauges are from the chart.
Tide gauges are from the chart.
Tide gauges are from the chart.
Tide gauges are from the chart.

BY P.G. & E. A.
IN FALL 1980




TYPICAL SECTION B-B
STEEL H-PILES WITH TIMBER LAGGING
FOR SHOREWARD 900 L.F.






PROFILE SECTION

TYPICAL STEEL H-PILE




SECTION C-C



SECTION A-A


PLAN J




NOTES

Base Map is 1972 USGS Map of Fields Landing Quadrangle. Shore line shown represents the approx. line of Mean High Water. Depth contours are in feet below Mean Lower Low Water (MLLW) Datum. One foot depth contours (1.0 m) are approximated from a July 1980 U.S.C. of 1:5 Hydrographic Survey Contract and from Humboldt Co. Aerial Photography taken at 9:05 a.m. on May 25, 1987 (Tide Elev. = 1.5). Grid coordinates are from the Calif. coordinate system Zone 1. Eureka Shipyard, Inc., property lines established from P.G. & E.'s map of Tidelands Survey #102.


DESIGN)



E.V.



TYPICAL SECTION B-B
STEEL H-PILES WITH TIMBER LAGGING



I. P

I.G.


E ROCK DE

NOTES

Base Map is 1972 USGS Map of Fields Landing Quadrangle.
Shore line shown represents the approx. line of Mean High Water.
Depth contours are in feet below Mean Lower Low Water (MLLW) Datum.
One foot depth contours (1, 2, 3) are approximated from a July 1980 U.S.C. of 1:14 Hydrographic Survey Contract and from Humboldt Co. Aerial Photography taken at 9:55 a.m. on May 25, 1982 (Tide Elev. = 1.15).
Grid coordinates are from the Calif. Coordinate System Zone 1.
Eureka Shipbuilders, Inc., property lines established from P.G. & E. map of Tidelands Survey #172.

SITE PLAN

ROCK RETEMENT PLACED BY P.G. & E. AND HUMBOLDT CO. IN FALL 1982



APPENDIX F

CORRESPONDENCE and DOCUMENTS

for

BUHNE SPIT/KING SALMON

SHORE PROTECTION PROJECT



DEPARTMENT OF THE ARMY
SAN FRANCISCO DISTRICT, CORPS OF ENGINEERS
211 MAIN STREET
SAN FRANCISCO, CALIFORNIA 94105

April 25, 1983

Construction-Operations Div.

Mr. George Armstrong
Department of Boating & Waterways
1629 S. Street
Sacramento, California 95814

Dear Mr. Armstrong:

This is to confirm the Buhne Point Demonstration Project Steering Committee Meeting to be held at the Humboldt Bay Harbor Recreation and Conservation District Office on 3 May 1983 at 1:00 PM.

Preliminary plans, schedules and cost estimates for Phase I (H - pile with wood lagging groin parallel to Fields Landing Channel from the southwest end of Buhne Point Road near the intersection of Halibut Avenue and a smaller offshore structure north of the spit); Phase II (placement of dredged fill material in the area formed by the two structures;) and proposed model studies of the project area. Additional items to be discussed are the lands, easements and rights-of-way for project construction; maintenance agreement for the erosion phase of project; schedule and cost estimates for design/construction of Buhne Point Road; and coordination with Coastal Zone Commission and Regional Water Quality Control Board.

The following persons have been invited to attend this meeting:

Dave Eyres	Federal Highway Administration
Tom Smith	Federal Highway Administration
Jack Alderson	Humboldt Bay Harbor Recreation and Conservation District
Guy Kulstad	County of Humboldt
Don Tuttle	County of Humboldt
George Armstrong	California Department of Boating and Waterways
Ed Weeks	Pacific Gas and Electric Company
Mrs. Scott	King Salmon Area Residents
Don Spensor	Los Angeles District, Corps of Engineers
Jack Farless	San Francisco District, Corps of Engineers
Jack McKellar	Eureka Project Office, S.F. District, Corps of Engrs.

Sincerely,

Jay K. Soper
Chief, Planning/Engineering Division

Copy furnished:
Federal Highway Administration
HCS-31
400 7th St., S.W.
Washington, D. C. 20590



DEPARTMENT OF THE ARMY
OFFICE OF THE CHIEF OF ENGINEERS
WASHINGTON, D.C. 20314

REPLY TO
ATTENTION OF

6 APR 1983

WRSC-D

Mr. Frank Torkelson, Interim Director
Department of Boating and Waterways
State of California - Resources Agency
1629 S. Street
Sacramento, California 95814-7291

Dear Mr. Torkelson:


I am responding to your letter of February 23, 1983, in which you provided a status of your agency's planning efforts for the Buhne Spit shore protection project.

The San Francisco District has been given the lead role for development and construction of the shore protection at Buhne Point. Colonel Ed Lee, San Francisco District Engineer, is the overall manager for the project. He will insure close coordination at all levels - Federal, state, and local.

In connection with the beach replenishment, San Francisco District will do sediment sampling to determine the best area to position a hydraulic cutterhead dredge to enable the coarser sands to be pumped directly on the beach. Plans and specifications for the beach replenishment will be prepared, and we anticipate a contract award early this fall.

I appreciate your interest in our dredging program, and particularly your interest in dredged material as a beneficial resource. Colonel Lee and his staff will continue to coordinate directly with you on their efforts at Buhne Point.

Sincerely,


John F. Wall
Major General, U. S. Army
Director of Civil Works

Maj. Gen. John F. Wall
Director of Civil Works
Department of the Army
Office of the Chief of Engineers
Washington, D. C. 20314

Reply to Attention of: WSRC-D

SUBJECT: Buhne Point Dredge Spoil Area, Humboldt Bay, California

Dear General Wall:

We appreciate your consideration and study for placing dredge spoils within the Buhne Point Shoal area. At the present time, the Department of Boating and Waterways (Cal Boating) is in the preliminary design phase of a shore-protection project for the Buhne Spit area. We have developed several alternative plans for the project area which provide a groin system. The groins will prevent sands from the Buhne Point area being transported into the Fields Landing Channel and also into the Pacific Gas and Electric Company (PG&E) cooling water intake channel (Fisherman's Channel). Prints of the conceptual plans and cost estimates are enclosed.

The Buhne Point/King Salmon Shore Protection Project is included in Cal Boating's FY 1983-84 Budget. We have sufficient funds for construction of the structures but no funds allocated this year for sand fill to provide the protective beach within the groin pocket. We have assumed that the Corps of Engineers would deposit dredge spoils within the project area over a period of several years, providing sand fill for a protective beach. Plan A, enclosed would require approximately 200,000 cubic yards of sand fill. The other alternatives would require about the same quantity of sand.

The material from the middle ground could provide the main line fill for our project. We would suggest that the San Francisco District investigate the use of an auxiliary pumpout line. The line could be anchored alongside the hopper dredge within the Fields

General Wall

-2-

landing Channel, immediately downbay of the project area. This method would be an alternative to dumping the material in quiet waters and pumping the sand to the site by use of a hydraulic cutterhead dredge. Cal Boating used this method successfully on the Alameda Beach Renourishment Project, completed last fall.

Cal Boating will be very interested in the cost of sand and method of delivery to the Buena Spit project site. If you have any questions about the shore-protection project, please contact George Armstrong, Supervisor, Beach Erosion Branch, at (916) 445-8349.

Sincerely,

FRANK TORKELSON
Interim Director

Enclosures

cc: Mr. J. Robert Edmisten w/encls.
USCE, South Pacific Div.

Col. Gary Lord, District Engineer w/encls.
USCE, San Francisco District

Mr. Jack Alderson
Humboldt Bay Harbor, Recreation
and Conservation District

CA:am

February 13, 1983

Mr. Roy Trent
Department of Transportation
Federal Highway Administration
Research Department, Room 6320
400 - 7th St., South West
Washington, D.C. 20590

SUBJECT: Buhne Point Shore Protection Project, King Salmon,
Humboldt Bay, California

Dear Mr. Trent:

Enclosed are copies of the conceptual plans and cost estimates for the Buhne Point project. The various plans are designed to intercept sand which would be transported down bay toward the Fields Landing Channel and subsequently find its way into the PG&E cooling water intake channel (Fisherman's Channel). The plans also provide a "groin pocket" to trap any littoral transport and with time build a wide protective beach.

The proposed projects will recreate Buhne Spit to its approximate area in 1955. Sand fill is not included in the cost estimates enclosed. We anticipate that the U. S. Army Corps of Engineers will deposit their maintenance dredge spoils within the groin pocket. The time necessary to fill the pocket will be dependent on the availability of sand and the frequency of maintenance dredging.

The Department will be coordinating the project design with all local, state and federal agencies. We will send you a copy of our feasibility report when completed. The conceptual design will give you an understanding of the scope of the project and how it will fit into your future project. Our project can be considered "Phase I" of any subsequent development on Buhne Spit.

If you have any further questions about our proposed project, please feel free to contact George Armstrong, Supervisor, Beach Erosion Branch, at (916) 445-8149.

Sincerely,

BILL E. SAWYER, Chief
Beaching Facilities Division

by

CHARLES A. ARMSTRONG, Supervisor -
Beach Erosion Branch

cc: Mr. Jack Alderton

6-11

February 17, 1983

Mr. Don Tuttle
Natural Resources Division
Department of Public Works
County of Humboldt
1106 Second Street
Eureka, California 95501-0579

SUBJECT: Buhne Point Shore Protection Project, King Salmon,
Humboldt County

Dear Mr. Tuttle:

Enclosed are prints and masters of the alternative plans and cost estimates for the Buhne Point project to be included in your environmental document.

We will forward to you a draft copy of the feasibility report when completed.

If you need any other plates from the feasibility report for your environmental document, please contact George Armstrong, Supervisor, Beach Erosion Branch, at (916) 445-3549.

Sincerely,

BILL S. SATOW, CHIEF
Boating Facilities Division

By

GEORGE A. ARMSTRONG, Supervisor
Beach Erosion Branch

cc: Mr. Don Tuttle

cc: Mr. Don Tuttle
Engineering & Surveying Co.

cc: Mr. Don Tuttle



DEPARTMENT OF THE ARMY
OFFICE OF THE CHIEF OF ENGINEERS
WASHINGTON, D.C. 20315

REPLY TO
ATTENTION OF:

WRSC-D

24 JAN 1983

Ms. Marty Mercado
Department of Boating and Waterways
State of California-Resources Agency
1629 S Street
Sacramento, California 95814

Dear Mr. Mercado:

This is in further response to your letter of October 22, 1982, to Lieutenant General J. K. Bratton, Chief of Engineers, regarding the Buhe Point dredged material disposal area.

The Corps agrees that efforts should be made to utilize dredged sands for beach replenishment at Buhe Point. The area in question was a disposal site for new construction dredging of Fields Landing Channel which was accomplished in the 1930's. The sediment, which was fine sand and silt, was placed hydraulically in a confined area and dewatered.


Most of the sediments presently hopper dredged from the Fields Landing and North Bay Channels tend to be finer, ranging from sandy silts to silts and clays and, therefore, may not be suitable for beach replenishment. However, sediments removed from the middle ground, at the east end of the entrance channel, are coarse sands, and should be ideal for beach replenishment. Two requirements for use of these sands at Buhe Point are a groin system to prevent sand transport into Fields Landing Channel and equipment to transfer the sand to the beach.


Dredging of the middle ground must be accomplished by hopper dredges. There are no suitable hopper dredges available for this project which have a direct pumpout capability. Because of severe currents, waves, weather and safety considerations, other types of dredging plant, such as hydraulic cutterhead or clamshell equipment, cannot be utilized at this location. In order to maintain clarity of the dredged sand on the beach, it would be necessary to utilize a hydraulic cutterhead dredge to pump the sand from a deep, quiet water dump location of the hopper dredge. This results in different hydraulic design considerations, all in addition to the design costs which would have to be borne by the project local sponsor or entity providing the beach replenishment.

24 JAN 1953

The Corps is well aware of the erosion problems at Buhne Point and the potential benefits of erosion control, recreation and steady habitat development with a beach replenishment program. The San Francisco District is presently developing cost analysis estimates for beach replenishment from the potential sources mentioned above. The District Engineer will provide these estimates to you as soon as they are finalized.

Sincerely,


J. P. Wall
Major General, U. S. Army
Director of Civil Works



DEPARTMENT OF PUBLIC WORKS
COUNTY OF HUMBOLDT
MAILING ADDRESS: 1106 SECOND STREET, EUREKA, CA 95501-0579
AREA CODE 707

OFFICE LOCATIONS

CLAREMONT AIRPORT TERMINAL
CLAREMONT, CA 95521
445-7551

CLARE COMPLEX
HAUGEN & H ST., EUREKA
REAL PROPERTY
SERVICES 445-7251

JACOBS AVENUE GARAGE
JACOBS AVENUE, EUREKA
EQUIPMENT MAINTENANCE 445-7575
ROADS & ADMINISTRATION 445-7421 BUSINESS

PUBLIC WORKS BUILDING
SECOND & L ST., EUREKA
445-7431
ENGINEERING 445-7441
445-7552 NATURAL RESOURCES 445-7741

December 24, 1982

Mr. George Armstrong
California Department of Boating and Waterways
1629 "S" Street
Sacramento, CA 95814

REGARDING: Buhne Point Shore Protection Project, King Salmon,
Humboldt Bay, Environmental Document

Dear Mr. Armstrong:


Enclosed is a copy of the preliminary environmental document for the Buhne Point project.

We intend to revise the document (after the draft feasibility study is sent to us) to include a discussion of the sub-alternatives to the groin/rubble-mound breakwater project. We will revise the document to include any additional impacts, if any, and correlate the alternative construction project titles.

The document is double-spaced for purposes of making any comments, additions, corrections you find are necessary.

Hope to hear from you after January 1.

Sincerely,


JOHN A. CLATZEL
NATURAL RESOURCES DIVISION

cc: [illegible]

cc: [illegible]

PACIFIC GAS AND ELECTRIC COMPANY

27 BEALE STREET • SAN FRANCISCO, CALIFORNIA 94106 • (415) 781-4211 • TWX 910 372-6587

December 3, 1982

Mr. Don Tuttle
Department of Public Works
1106 Second Street
Eureka, CA 95501

Subject: Humboldt Bay Bathymetry Survey

Dear Don,

Please find enclosed the Bathymetry profiles we discussed on the phone. I hope they will be of use to you.

I have been informed that our contractor has completed our seawall and that your section should be completed by Saturday. I plan to fly up to Eureka next week to take a look at the wall and hope to see you at that time.

If I can be of any further help or wish to discuss the enclosed data, please call me at (415) 781-4211, extension 2521.

Sincerely,


COURTNEY ALLEN

CFA:dl

Enclosures

15 NOV 1932

Mr. Marty Mercado, Director
Department of Boating and Waterways
State of California Resources Agency
1025 S Street
Sacramento, CA 95814-7291

Dear Mr. Mercado:

I received your letter of October 29, 1932, to Lieutenant General J. A. Patton, Chief of Engineers, in which you relayed the State of California's desire to obtain dredged sediment for beach restoration in the Laguna Beach Area, Laguna Bay, California.

I have asked for a report on this matter from the District Engineer of the Army Corps of Engineers. Upon receipt of his report, I will let you know the results.

Sincerely,

LIEUTENANT GENERAL, USA, Ret.
Lieutenant General, USA
Active Director of Civil Works

HUMBOLDT BAY
HARBOR, RECREATION, AND CONSERVATION
DISTRICT
(707) 443 0801
P. O. Box 134
Eureka, California 95501



Mr. George Armstrong
Department of Boating & Waterways
Commission
1822 "B" Street
San Francisco, CA 94114

Dear Mr. Armstrong:

In response to our telephone conversation of 2 Nov. 1982, the property needed for a public pool/beach building west of Eureka Bay is in private ownership. However, the Humboldt Bay Harbor, Recreation, and Conservation District is in the process of acquisition.

The property is owned by Buck's Shipyard, Inc. and at a meeting earlier this month, the Board of Directors of the property as a gift to the District. This property is owned by a principal and majority shareholder of Buck's Shipyard, Inc. The property is being transferred to all of the estate's assets to provide for the future of the property.

The property, Inc. are still willing to transfer, at no cost to the District, the property and the resources of the Humboldt Bay Harbor Recreation and Conservation District.

The property, which is located, will soon become a valuable recreational area for the community. The property is currently being used as a playground for children. The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property.

The property is located in the heart of the city. The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property. The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property.

The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property. The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property.

The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property. The property is a park-like setting. The area was once a very productive and productive area. The property is being used extensively by those who are interested in the property.

OCT 22 1982

Major General Joseph K. Bratton
Chief of Engineers
Department of the Army
Forrestal Building
Washington, D.C. 20312

SUBJECT: Buhne Point Dredge Spoil Area, Humboldt Bay, California

Dear General Bratton:

The State of California's "Policy for Shoreline Erosion Protection" promulgated on September 14, 1978 by the Secretary of Resources under Section II, Planning and Regulations, Subsection C stipulates:

"Beach and dune sand, and similar sediment lying in river beds, estuaries or in harbor channels is a valuable resource that should be used for shoreline protection. It is, therefore, the policy of the Resources Agency that all such dredge or excavation material removed within the coastal zone or near-shore waters, which is suitable in quantity, size, distribution, and chemical constituency, be discharged as follows:

1. Directly onto a natural beach in an appropriate manner for effective beach nourishment and in a manner to protect significant natural resources and the public use of such resources at those locations; or
2. When beach nourishment is not needed or appropriate at the time of dredging, the sand should be deposited at locations for eventual use for beach nourishment, provided that suitable locations are available and steps are taken to protect both significant natural resources and the public use of such resources at those locations; or
3. In those instances where quantity, distribution, or chemical constituency of dredge or excavation material limit its use as described in paragraphs one and two, the material should be used to optimize its mineral values or its utility as construction material;"

Public Law 94-587 - September 22, 1976, 94th Congress, Section 100 states:
The Secretary of the Army, acting through the Chief of Engineers, in
consultation with the Governor of the State, to place on the list of such
high-quality sand which has been helpful in constructing and

J. Van. Bratton:

-2-

"maintaining navigation inlets and channels adjacent to such beaches, if the Secretary deems such action to be in the public interest and upon payment of the increased cost thereof above the cost required for alternative methods of disposing of such sand."

The Buhe Point area, on Humboldt Bay, California, was built from previous Corps of Engineers' channel maintenance dredging spoils in the late 1930's. This dredge spoil sand fill lasted for over 40 years.

The State of California requests, under the provisions of PL 94-587, and in conformance with "The Policy for Shoreline Protection", that the Corps of Engineers place channel maintenance and/or new work dredged sand on the Buhe Point Spit area. It is believed that placement of sand on Buhe Spit will be less costly than the present method of placement at sea. The State also requests that a determination of cost be made if the placement of sand on Buhe Spit is more costly. The State would consider contributions to make up the difference in cost.

Informal discussions between Mr. George Armstrong, Supervisor, Beach Erosion Branch of this Department and the Department of Fish and Game, North Coast Region Water Quality Control Board and the State Coastal Commission indicates that the proposed dredge spoil project at Buhe Point does not have any major environmental problems.

Sincerely,

MARTY MERCADO
Director

cc: Mr. Jack Alderson
Mr. Guy Kulstad
Brig. Gen. Homer Johnstone
Col. Gary Lord
CAA:pm

SECTION 2

PHASE II BASIS FOR DESIGN

Buhne Point Shoreline Erosion Demonstration
Project, Phase II, Humboldt Bay
Basis For Design

1. Phase I Timber Groin. The Phase I timber groin was designed by Humboldt County with soil design values provided by the Los Angeles District Corps of Engineers. The design values are based upon soil investigation conducted in June 1983 and are given in Table 4 of the inclosed foundation report. The total length of the timber groin would be 1,250 feet. It would begin at the existing stone riprap along Buhne Drive at coordinates N 519,204.06 and E 1,385,293.08. From sta. 0+00 to sta. 10+00, the timber groin would have a direction north 32 degrees west, generally paralleling the existing Fields Landing channel. From sta 10+00 to sta 12+50, the timber groin enters a circular curve of 600 feet radius and central angle of 57 degrees, 17 minutes, and 45 seconds. A 200-foot long rubble mound head (sta 12+00 to sta 14+00) would be provided to protect the seaward end of the timber groin. A 6-foot-wide, 5-foot high stone toe protection structure consisting of one-ton stone and quarry waste would be placed along the downcoast (south) side of the timber groin to prevent scouring of the toe. A filter fabric on the upcoast (north) side would be provided to prevent the phase II sandfill from passing through voids in the timber groin.

2. The primary function of the timber groin is to stabilize the phase II sandfill and prevent it from being transported downcoast into the Fields Landing Channel by the predominant downcoast drift. The downcoast drift is caused by the diffracted deep water wave trains approaching through the entrance channel and tidal current in the bay. The length of the timber groin is based upon the amount of structure that can be constructed with the State Department of Boating and Waterways budgeted funds of \$495,000. The objective is to build the longest groin possible with the available funds for stabilizing the phase II sandfill.

3. Soils Investigation. Soils investigations were conducted in July 1983 to determine the extent, distribution, and physical properties of the foundation and borrow area materials for the proposed alignments of the timber and stone groin and stone slope protection and fill off Buhne Point in Humboldt Bay, California. Detailed information of the borrow materials and foundation conditions were obtained in order to provide a sound basis for the design of the proposed structures. The inclosed report describes the soils and soil properties, soil explorations, field survey and laboratory testing, analysis of data, soil design values, and discusses some of the design and construction considerations(Incl 1).

4. Phase II Sandfill. The phase II sandfill was designed to temporarily restore the spit at Buhne Point and provide protection for Buhne Drive and underground utilities. A borrow area about 4,000 feet long and 400 feet wide adjacent to the North Bay Channel of Humboldt Bay will be dredged to a project depth of minus 35 feet mean lower low water (MLLW) and will provide about

600,000 cubic yards of materials for the sandfill. A 2 feet over-depth is allowed for the dredging.

5. The materials in the borrow area consist predominantly of loose to very dense, fine to medium grained sands with shells. For the sands, the percent of the material by weight passing the No. 4 sieve varies from 98 to 100 percent; the percent passing the No. 10 sieve varies from 92 to 100 percent, and the percent passing the No. 200 sieve varies from 1 to 6 percent. Approximately 90 percent of the material in the borrow area will be sand. The remainder consists of silt or clay material.

6. The materials at Buhne Point consist of layered heterogeneous soils extending to a depth greater than 60 feet. The upper layer, varying in thickness from 9 feet near shore to 20 feet, consists of gravelly sands and sands with shells. The percent of the material by weight passing the No. 4 sieve varies from 64 to 100 percent, and the percent of the material by weight passing the No. 200 sieve varies from 1 to 9 percent.

The second layer, varying in thickness from 8 to 14 feet, consists of plastic sandy silts and sandy clays. The percent by weight passing the No. 4 sieve varies from 95 to 100 percent, and the percent by weight passing the No. 200 sieve varies from 56 to 81 percent. The third layer occurs below elevations ranging from -32 to -35.5 feet MLLW and consists of dense silty sands and medium to fine sands. One hundred percent of the material by weight passes the No. 4 sieve. The percent of the material by weight passing the No. 200 sieve varies from 5 to 21 percent.

7. The material in the borrow area would be excavated by hydraulic dredging and could be placed from the upcoast end to the downcoast end of the timber groin until the required amount of material has been dredged. The average pumping distance from the borrow area to the sandfill is approximately 1.2 miles. To minimize erosion the crest elevation of the sandfill would be plus 15 feet MLLW, and the material would be spread out during the phase III project to plus 12 feet MLLW. The seaward construction slope of the sandfill would be 1 vertical on 10 horizontal, and it is estimated that the equilibrium slope would be 1 vertical on 15 horizontal. The construction slope of the sandfill at the timber groin would be 1 vertical on 3 horizontal which is approximately the angle of repose for the dredged material. The elevation of the sandfill at the timber groin would be about plus 11 feet MLLW.

8. Model Study. Tidal currents and wave-induced currents are the major contributors to the erosion problem at Buhne Point. Since there is no guidance for the design of engineering structures for such areas where wave-induced and tidal current interaction is significant, a series of model studies are proposed to evaluate alternative plans required for the alleviation of shoreline erosion. A 1:100-scale physical model of central Humboldt Bay is proposed to determine the wave climate (angle of the wave front) and will include the entrance to Humboldt Bay, the central portion of the Bay, the Buhne Point area, and approximately 18,000 linear feet of shoreline inside the Bay. A range of significant wave periods and heights will be generated through the jetties (from the Pacific Ocean) for various

directions and still-water levels (SWL's) both with and without tidal flow conditions to determine the wave climate in the vicinity of the problem area.

A 1:50-scale physical model of Buhne Point is proposed to determine the causes of erosion at the point and the effectiveness of various improvement structures under various wave and tidal current conditions. A curved wave generator capable of reproducing a variable height wave front (as determined in the 1:100-scale model of central Humboldt Bay) will be used to generate test waves for various SWL's both with and without tidal flow conditions. A 1:50-scale model is required since wave breaking and sediment transport are important in the area, and scale effects become significant for scales greater than approximately 1:50.

A two-dimensional hydrodynamic tidal circulation numerical model is proposed to determine the tidal current field in central Humboldt Bay and adjacent Buhne Point. Maximum flood and ebb tidal current velocities will be determined and used in both the 1:100-scale physical model of central Humboldt Bay and the 1:50-scale physical model of Buhne Point.

A three-dimensional sediment transport numerical model of Humboldt Bay is proposed to determine the impacts of the proposed Buhne Point structures on adjacent areas in the Bay. It will determine if the proposed structures would produce or result in erosion problems at other locations not included in the physical model or shoaling problems in the navigation channels.

In summary, the two physical hydraulic models and two numerical models would determine the effectiveness of engineering structures to alleviate erosion problems at Buhne Point, Humboldt Bay, California. The final solution required to protect the project, based on the hydraulic model tests results, will be incorporated into the Phase III project.

Prepared by
Los Angeles District
February 1984

SECTION 3

PHASE II FOUNDATION REPORT

HUMBOLDT BAY, CALIFORNIA

FOUNDATION REPORT

FOR

BUHNE POINT

SHORELINE EROSION DEMONSTRATION PROJECT

PHASE II, HUMBOLDT BAY

U.S. ARMY ENGINEER DISTRICT,

LOS ANGELES

CORPS OF ENGINEERS

AUGUST 1983

FOUNDATION REPORT
FOR
BUHNE POINT
SHORELINE EROSION DEMONSTRATION PROJECT
PHASE II, HUMBOLDT

1. PURPOSE AND SCOPE.

Soils investigations were conducted to determine the extent, distribution and physical properties of the foundation and borrow area materials for the proposed alignments of the timber and stone groin and stone slope protection and fill off Buhne Point in Humboldt Bay, California. Detailed information of the borrow materials and foundation conditions were obtained in order to provide a sound basis for the design of the proposed structures. The report describes the soils and soils properties, the soils exploration, field and laboratory testing, analysis of data, soil design values, and discusses some design and construction considerations.

2. SITE DESCRIPTION.

The proposed project is located off Buhne Point in Humboldt Bay, California. The site is a tidal mud flat varying in elevation from +1 to -4 feet MLLW. The site is normally covered by water and is exposed only during low tide. See plate 1 for location of project.

3. PROJECT FEATURES.

The proposed project consists of a timber groin 1250 feet in length, a stone groin 150 feet in length from the end of the timber groin, approximately 600,000 cubic yards of sand fill and stone slope protection. See plate 1 for location and typical section of project features.

4. FIELD INVESTIGATIONS.

Geotechnical investigations consisted of drilling holes with a barge mounted, 4 inch diameter rotary wash drill rig along the proposed alignment of the groin in the fill area and in the borrow area. See plate 1 and 2 for location of drill holes. Representative disturbed samples were obtained at 5-foot intervals for classification tests. Undisturbed samples along the proposed alignment of the groin were obtained with a drive Sampler at depths below 30 feet in TH 83-3 thru 5 and with a 3-inch diameter Shelby tube sampler in TH 83-1 thru 3 to obtain samples for detailed laboratory testing. The borings by general location and depths are summarized in the table 1.

TABLE 1
EXPLORATION SUMMARY

<u>LOCATION</u>	<u>HOLE NO.</u>	<u>DEPTHS (Ft.)</u>
Groin	TH 83-1 thru 5	22 to 65.5
Fill Slope Area	TH 83-7 thru 11	11.5 to 21.5
Borrow Area	TH83-6, 8 thru 10	15 to 28.5

5. FIELD TESTS AND RESULTS.

a. Standard Penetration Tests.

Standard Penetration Tests were performed in all the test holes. The test consists of driving a sampling spoon, having an inside diameter of 1-3/8 inches and an outside diameter of 2 inches, with a 140-pound hammer falling from a height of 30 inches. The sampling spoon is seated 6 inches and the penetration resistance is recorded as the number of blows required to drive the sampler one additional foot.

b. Drive Sampler.

Density samples were obtained using a Drive Sampler and submerged hammer along the proposed groin alignment. The sampler which has an inside diameter of 2.0 inches and an outside diameter of 2.5 inches consists of a solid spoon which contains four 3-inch long brass rings having an inside diameter of 1.93 inches and an outside diameter of 2.0 inches and a 6-inch waste barrel. The hammer was dropped from a height of 18 inches and has a weight of 376 pounds. The driving resistance was measured as the number of blows by the submerged hammer to drive the sampler one foot after seating the sampler 6-inches.

6. LABORATORY TESTS AND RESULTS.

a. Testing Methods.

Representative disturbed and undisturbed samples were sent to the South Pacific Division (SPD) Laboratory for testing. The testing program consisted of unconfined compression, consolidation, density, mechanical analysis and Atterberg limits. These tests were performed in general accordance with EM 1110-2-1906 "Laboratory Soils Testing" dated 30 November 1970.

b. Test Results.

Results of classification tests are shown on the soils logs on plates 3 and 4. The results of the density tests are shown in table 2, the results of the unconfined compression tests are shown in table 3, and the results of the consolidation tests are shown in table 4.

TABLE 1
DENSITY TESTS

<u>Hole Number</u>	<u>Depth (Ft)</u>	<u>Soil Classification</u>	<u>Dry Density (Pcp)</u>	<u>Water (%)</u>
83-1	14	ML	85	35
83-2	30	SP/SM	103	24
83-3	10	SP	125	13
83-3	25	CL	93	30
83-3	45	SP/SM	102	21
83-3	55	SP/SM	97	25
83-4	30	CL/ML	90	31
83-4	40	SP/SM	102	23
83-5	36	ML	106	21
83-5	46	SP/SM	101	22

TABLE 2
UNCONFINED COMPRESSION TESTS

<u>Hole Number</u>	<u>Depth (Ft)</u>	<u>Unconfined Compressive Strength (Psf)</u>
83-1	14	720
83-2	30	1240
83-3	25	1300

TABLE 3
CONSOLIDATION TESTS

<u>Hole Number</u>	<u>Depth (Ft)</u>	<u>Initial Void Ratio</u>	<u>Compression Index (Cc)</u>
83-1	14	1.043	0.28
83-2	30	0.679	0.155
83-3	25	0.929	0.27

7. ANALYSIS OF DATA.

a. Groin Foundation.

The foundation materials for the groin consist of layered heterogeneous alluvial soils extending to a depth greater than 60 feet. Interpretation of the data contained on the soils logs indicate that there are three distinct soil layers in the groin foundation.

The upper layer, varving in thickness from 9 feet near shore (TH 83-1) to 20 feet (TH 83-2 thru 5), consists of gravelly sands and sands with shells. The percent of the material by weight passing the No. 4 sieve varies from 64 to 100 percent and the percent of the material by weight passing the No. 200 sieve varies from 1 to 9 percent. The SPT penetration resistance for this layer ranged from N=2 to N=9. The layer is approximately 20 feet thick.

The second layer consists of plastic sandy silts and sandy clays. The percent by weight passing the No. 4 sieve varies from 95 to 100 percent and the No. 200 sieve varies from 56 to 81 percent. The plastic index varies from 4 to 8 and the liquid limit varies from 27 to 31. The in-situ dry density of this material varies from 85 to 106 pcf with an average of 94 pcf. The in-situ moisture content

of this material varies from 24 to 35 percent with an average of 30 percent. The SPT penetration resistance for this layer ranged from N=4 to N=9. The unconfined compression strength (qu) ranged from 720 pounds per square foot (psf) to 1300 psf with an average of 1087 psf. The compression index varies from 0.27 to 0.28. The layer varies in thickness from approximately 8 feet (near shore TH 83-1 and 2) to 14 feet in TH 83-3 thru 5.

The third layer consists of silty sands and medium to fine sands. One hundred percent of the material, by weight passes the No. 4 sieve. The percent of the material by weight passing the No. 200 sieve varies from 5 to 21 percent. The in-situ dry density of this material varies from 90 to 103 pcf with an average of 101 pcf. The in-situ moisture content of this material varies from 21 percent to 30 percent with an average of 24 percent. The SPT penetration resistance for this layer in TH 83-2 was N=60+. The California Modified Sampler driving resistance averages 32 for the layer. The penetration and driving resistance data indicate that the materials are dense to very dense.

b. Fill Slope Foundation.

The foundation materials for the fill slope consist of sandy silts, sandy clays and sands with shells. The percent of the material by weight passing the No. 4 sieve varies from 98 to 100 percent and the percent of the material by weight passing the No. 200 sieve varies from 5 to 95 percent. For the plastic soils the plastic index varies from 3 to 13 and the liquid limit varies from 27 to 36. The SPT penetration resistance for these soils ranged from N=3 to N=7.

c. Borrow Area.

The materials in the borrow area consist predominately of loose to very dense fine to medium grained sands with shells. For the sands the percent of the

material by weight passing the No. 4 sieve varies from 98 to 100 percent, the No. 10 sieve varies from 92 to 100 percent, and the No. 200 sieve varies from 1 to 6 percent. The range of field gradations for the sands in the borrow area are shown in figure 1. Approximately 90 percent of the material in the borrow area will be sand. The remainder will be minus No. 200 material. The material in the borrow area becomes denser with depth. The penetration resistance ranged from N=6 to N=16 in the upper 10 feet, from N=16 to N=35 at a depth 10 to 25 feet, and N=60+ below 25 feet.

A clay layer was encountered at 19 feet in TH 83-6. TH 83-6 was located on the eastern edge of the borrow area.

8. DESIGN VALUES.

a. General.

The adopted design values are based on the results of laboratory and field tests. The selected design values for the groin foundation and the fill are presented in table 4 and the basis for the selection follows.

TABLE 4

FILL AND FOUNDATION, SUMMARY OF DESIGN VALUES

	Elevation	<u>Unit Weight</u> Sat	ϕ	C	Kw	Kp
	Depth (Ft.)	(Pcf)	Degree	(Psf)	(Pcf)	(Pcf)
Fill	+15 to -1	125	30	0	40	100
Foundation						
Gravelly sand	-1 to -21	110	27	0	40	100
Silt and clay	-21 to -36	120	0	500	40	100
Silty sand	-36 to -67	125	25	0	40	100

AD-A189 838

BUNNE POINT SHORELINE EROSION DEMONSTRATION PROJECT
VOLUME 2 APPENDICES E(U) ARMY ENGINEER DISTRICT LOS
ANGELES CA AUG 87


3/3

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

b. Fill Materials.

A saturated unit weight of $\gamma_{sat}=125$ pcf and a shear strength of $\phi=30^\circ$ were selected for the fill material. The design values were based on the material characteristics in the borrow area and the method of placement for the materials.

c. Foundation Materials.

From an elevation of -1 to -21, a saturated unit weight of $\gamma_{sat}=110$ pcf and a shear strength of $\phi=27^\circ$ were selected for the gravelly sand layer. The design values were based on the SPT results and gradation of the materials.


From an elevation of -21 to -36, a saturated unit weight of $\gamma_{sat}=120$ pcf and a shear strength of $c=500$ psf were selected for the clay layer. The unit weight was based on the average of the in-situ density tests and the shear strength was based on the average of the unconfined compression test results.

From an elevation of -36 and below, a saturated unit weight of $\gamma_{sat}=125$ pcf and a shear strength of $\phi=35^\circ$ were selected for the silty sand. The unit weight was based on the average of the in-situ density tests and the shear strength was based on the SPT results.

9. DESIGN AND CONSTRUCTION CONSIDERATIONS.


The following items should be considered during the design and construction of the Buhne Point groin, stone breakwater and fill. (1) A filter system will have to be designed for the groin to prevent the migration of material through the groin, (2) a filter system will have to be designed to prevent the migration of material through the stone breakwater, (3) to prevent the erosion of fill by waves and to contain the dredged materials during placement the stone breakwater should be constructed before placement of the fill, and (4) for estimating purposes the total settlement for the groin foundation is estimated to be less than 6 inches.


V. 'N' ERING PAYS



SANDHILL PLAIN







PLATE 1





VALUE EI

EEERING PAYS



NOTES:

1. SEE PLATE 3 FOR LEGEND, NOTES, AND BASIS OF CLASSIFICATION.
2. SEE PLATE 1 FOR LOCATION OF TEST HOLES.

<p>PROJECT NAME: SANDFILL AREA SOIL LOGS</p>	
<p>DATE: 07/11/71</p>	<p>BY: J. L. GEE</p>
<p>PROJECT NO. 100-100-100</p>	
<p>PROJECT NAME: SANDFILL AREA SOIL LOGS</p>	
<p>PROJECT NO. 100-100-100</p>	
<p>PROJECT NAME: SANDFILL AREA SOIL LOGS</p>	
<p>PROJECT NO. 100-100-100</p>	

SAFETY PAYS

DATE
FILMED
4 88